

US EPA ARCHIVE DOCUMENT

Coal Combustion Waste Impoundment Round 5 - Dam Assessment Report

Plant Wansley (Site # 006)
Ash Pond Separation Dike

Georgia Power
Carrolton, Georgia

Prepared for:

United States Environmental Protection Agency
Office of Resource Conservation and Recovery

Prepared by:

Dewberry & Davis, LLC
Fairfax, Virginia



Under Contract Number: EP-09W001727
July 2010

INTRODUCTION, SUMMARY, CONCLUSION AND RECOMMENDATIONS

The release of over five million cubic yards of coal ash from the Tennessee Valley Authority's Kingston, Tennessee facility in December 2008, which flooded more than 300 acres of land, damaging homes and property, is a wake-up call for diligence on coal combustion waste disposal units. . A first step to prevent such catastrophic failure and damage is to assess the stability and functionality of ash impoundments and other units, then quickly take any needed corrective measures.

This assessment of the stability and functionality of the Plant Wansley fly ash management unit is based on a review of available documents and on the site assessment conducted by Dewberry personnel on June 30, 2010. We found the supporting technical information adequate (Section 1.1.3). As detailed in Section 1.2.6 there are recommendations that may help to maintain a safe and trouble-free operation,

In summary, the Wansley Plant ash ponds are SATISFACTORY for continued safe and reliable operation, with no apparent existing or potential management unit safety deficiencies.

PURPOSE AND SCOPE

The U. S. Environmental Protection Agency (EPA) is investigating the potential for catastrophic failure of Coal Combustion Surface Impoundments (i.e. management unit) at electric utilities in an effort to protect lives and property from the consequences of a dam failure or the improper release of impoundment slurry. The EPA initiative is intended to identify conditions that may adversely affect the structural stability and functionality of a management unit and its appurtenant structures (if present); to note the extent of deterioration (if present); status of maintenance and/or a need for immediate repair; to evaluate conformity with current design and construction practices, and to determine the hazard potential classification for units not currently classified by the management unit owner or by a state or federal agency. The initiative addresses power plant management units that have a classification of Less-than-Low, Low, Significant or High Hazard Potential ranking. (For Classification, see pp. 3-8 of the 2004 Federal Guidelines for Dam Safety)

In December 2009, the EPA sent letters to coal-fired electric utilities seeking information on the safety of surface impoundments and similar facilities that receive liquid-borne material that store or dispose of coal combustion waste. This letter was issued under the authority of the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA) Section 104(e), to assist the Agency in assessing the structural stability and functionality of such management units, including which facilities should be visited to perform a safety assessment of the berms, dikes, and dams used in the construction of these impoundments.

EPA asked utility companies to identify all management units: surface impoundments or similar diked or bermed structures; and; landfills receiving liquid-borne materials that store or dispose of

coal-combustion residuals or by-products, including, but not limited to, fly ash, bottom ash, boiler slag, and flue gas emission control residuals. Utility companies responded with information on the size, design, age, and the amount of material placed in the units so that EPA could gauge which management units had or potential could rank as having High Hazard Potential. The USEPA and its contractors used the following definitions for this study:

“Surface Impoundment or impoundment means a facility or part of a facility which is a natural topographic depression, man-made excavation, or diked area formed primarily of earthen materials (although it may be lined with man-made materials), which is designed to hold an accumulation of liquid wastes or wastes containing free liquids, and which is not an injection well. Examples of surface impoundments are holding, storage, settling and aeration pits, ponds, and lagoons.”

For this study, the earthen materials could include coal combustion residuals. EPA did not provide an exclusion for small units based on whether the placement was temporary or permanent. Furthermore, the study covers not only waste units designated as surface impoundments, but also other units designated as landfills which receive free liquids.

EPA is addressing any land-based units that receive fly ash, bottom ash, boiler slag, or flue gas emission control waster along with free liquids. If the landfill is receiving coal combustion wastes with liquids limited to that for proper compaction, then there should not be free liquids present and the EPA did not seek information on such units which are appropriately designated a landfill.

In some cases coal combustion wastes are separated from the water, and the water containing de minimum levels of fly ash, bottom ash, boiler slag, or flue gas emission control wastes are sent to an impoundment. EPA is including such impoundments in this study, because chemicals of concern may have leached from the solid coal combustion wastes into the waster waters, and the suspended solids from the coal combustion wastes remain.

The purpose of this report is to **evaluate the condition and potential of waste release from management units that have not been rated for hazard potential classification**. A two-person team reviewed the information submitted to EPA, reviewed any relevant publicly available information from state or federal agencies regarding the unit potential hazard classification (if any) and accepted information provided via telephone communication with a management unit representative.

This evaluation included a site visit. EPA sent two engineers, one licensed in the State of Georgia, for a one-day visit. The two-person team met with the owner of the management unit as well as technical and several technical representative and management unit supervisors to discuss

the engineering characteristics of the unit as part of the site visit. During the site visit the team collected additional information about the management unit to be used in determining the hazard potential classifications of the management unit(s). Subsequent to the site visit the management unit owner provided additional engineering data pertaining to the management unit(s).

Factors considered in determining the hazard potential classification of the management unit(s) included the age and size of the impoundment, the quantity of coal combustion residuals or by-products that were stored or disposed in these impoundments, its past operating history, and its geographic location relative to down gradient population centers and/or sensitive environmental systems.

This report presents the opinion of the assessment team as to the potential of catastrophic failure and reports on the condition of the management units(s). The team considered criteria in evaluating the dams under the National Inventory of Dams in making these determinations.

LIMITATIONS

The assessment of dam safety reported herein is based on field observations and review of readily available information provided by the owner/operator of the subject coal combustion waste management unit(s). Qualified Dewberry engineering personnel performed the field observations and review and made the assessment in conformance with the required scope of work and in accordance with reasonable and acceptable engineering practices. No other warranty, either written or implied, is made with regard to our assessment of dam safety.

Contents

| | |
|---|-----|
| 1.0 CONCLUSIONS AND RECOMMENDATIONS | 1-1 |
| 1.1 CONCLUSIONS | 1-1 |
| 1.1.1 <i>Conclusions Regarding the Structural Soundness of the Management Unit(s)</i> | 1-1 |
| 1.1.2 <i>Conclusions Regarding the Hydrologic/Hydraulic Safety of the Management Unit(s)</i> 1-1 | |
| 1.1.3 <i>Conclusions Regarding the Adequacy of Supporting Technical Documentation</i> ... | 1-1 |
| 1.1.4 <i>Conclusions Regarding the Description of the Management Unit(s)</i> | 1-1 |
| 1.1.5 <i>Conclusions Regarding the Field Observations</i> | 1-1 |
| 1.1.6 <i>Conclusions Regarding the Adequacy of Maintenance and Methods of Operation</i> | 1-1 |
| 1.1.7 <i>Conclusions Regarding Adequacy of the Surveillance and Monitoring Program</i> | 1-1 |
| 1.1.8 <i>Classification Regarding Suitability for Continued Safe and Reliable Operation</i> .. | 1-2 |
| 1.2 RECOMMENDATIONS | 1-2 |
| 1.2.1 <i>Recommendations Regarding the Structural Stability</i> | 1-2 |
| 1.2.2 <i>Recommendations Regarding the Hydrologic/Hydraulic Safety</i> | 1-2 |
| 1.2.3 <i>Recommendations Regarding the Supporting Technical Documentation</i> | 1-2 |
| 1.2.4 <i>Recommendations Regarding the Description of the Management Unit(s)</i> | 1-2 |
| 1.2.5 <i>Recommendations Regarding the Field Observations</i> | 1-2 |
| 1.2.6 <i>Recommendations Regarding the Maintenance and Methods of Operation</i> | 1-2 |
| 1.2.7 <i>Recommendations Regarding the Surveillance and Monitoring Program</i> | 1-2 |
| 1.2.8 <i>Recommendations Regarding Continued Safe and Reliable Operation</i> | 1-2 |
| 1.3 PARTICIPANTS AND ACKNOWLEDGEMENT | 1-3 |
| 1.3.1 <i>List of Participants</i> | 1-3 |
| 1.3.2 <i>Acknowledgement and Signature</i> | 1-3 |
| 2.0 DESCRIPTION OF THE COAL COMBUSTION WASTE MANAGEMENT UNIT(S) | 2-1 |
| 2.1 LOCATION | 2-1 |
| 2.2 SIZE AND HAZARD CLASSIFICATION | 2-2 |
| 2.3 AMOUNT AND TYPE OF RESIDUALS CURRENTLY CONTAINED IN THE UNIT(S) AND MAXIMUM CAPACITY | 2-4 |
| 2.4 PRINCIPAL PROJECT STRUCTURES | 2-4 |
| 2.4.1 <i>Earth Embankment Dam</i> | 2-4 |
| 2.4.2 <i>Outlet Structures</i> | 2-6 |
| 2.5 CRITICAL INFRASTRUCTURE WITHIN FIVE MILES DOWN GRADIENT | 2-8 |
| 3.0 SUMMARY OF RELEVANT REPORTS, PERMITS AND INCIDENTS | 3-1 |
| 3.1 SUMMARY OF REPORTS ON THE SAFETY OF THE MANAGEMENT UNIT(S) .. | 3-1 |
| 3.2 SUMMARY OF LOCAL, STATE AND FEDERAL ENVIRONMENTAL PERMITS .. | 3-2 |
| 3.3 SUMMARY OF SPILL/RELEASE INCIDENTS (IF ANY) | 3-2 |

| | | |
|-------|--|-----|
| 4.0 | SUMMARY OF HISTORY OF CONSTRUCTION AND OPERATION | 4-1 |
| 4.1 | SUMMARY OF CONSTRUCTION HISTORY | 4-1 |
| 4.1.1 | <i>Original Construction</i> | 4-1 |
| 4.1.2 | <i>Significant Changes/Modifications in Design since Original Construction</i> | 4-1 |
| 4.1.3 | <i>Significant Repairs/Rehabilitation since Original Construction</i> | 4-1 |
| 4.2 | SUMMARY OF OPERATIONAL HISTORY | 4-2 |
| 4.2.1 | <i>Original Operational Procedures</i> | 4-2 |
| 4.2.2 | <i>Significant Changes in Operational Procedures since Original Startup</i> | 4-2 |
| 4.2.3 | <i>Current Operational Procedures</i> | 4-2 |
| 4.2.4 | <i>Other Notable Events since Original Startup</i> | 4-2 |
| 5.0 | FIELD OBSERVATIONS | 5-1 |
| 5.1 | PROJECT OVERVIEW AND ASSESSMENT | 5-1 |
| 5.2 | EARTH EMBANKMENT DAM | 5-1 |
| 5.2.1 | <i>II Crest</i> | 5-1 |
| 5.2.2 | <i>Upstream Slope</i> | 5-1 |
| 5.2.3 | <i>Downstream Slope and Toe</i> | 5-2 |
| 5.2.4 | <i>Abutments and Groin Areas</i> | 5-4 |
| 5.3 | OUTLET STRUCTURES | 5-4 |
| 5.3.1 | <i>Overflow Structure</i> | 5-4 |
| 5.3.2 | <i>Outlet Conduit</i> | 5-4 |
| 5.3.3 | <i>Emergency Spillway (If Present)</i> | 5-4 |
| 5.3.4 | <i>Low Level Outlet</i> | 5-4 |
| 6.0 | HYDROLOGIC/HYDRAULIC SAFETY | 6-1 |
| 6.1 | SUPPORTING TECHNICAL DOCUMENTATION | 6-1 |
| 6.1.1 | <i>Floods of Record</i> | 6-1 |
| 6.1.2 | <i>Inflow Design Flood</i> | 6-1 |
| 6.1.3 | <i>Spillway Rating</i> | 6-2 |
| 6.1.4 | <i>Downstream Flood Analysis</i> | 6-2 |
| 6.2 | ADEQUACY OF SUPPORTING TECHNICAL DOCUMENTATION | 6-2 |
| 6.3 | ASSESSMENT OF HYDROLOGIC/HYDRAULIC SAFETY | 6-2 |
| 7.0 | STRUCTURAL STABILITY | 7-1 |
| 7.1 | SUPPORTING TECHNICAL DOCUMENTATION | 7-1 |
| 7.1.1 | <i>Stability Analyses and Load Cases Analyzed</i> | 7-1 |
| 7.1.2 | <i>Design Properties and Parameters of Materials</i> | 7-1 |
| 7.1.3 | <i>Uplift and/or Phreatic Surface Assumptions</i> | 7-2 |
| 7.1.4 | <i>Factors of Safety and Base Stresses</i> | 7-4 |
| 7.1.5 | <i>Liquefaction Potential</i> | 7-6 |
| 7.1.6 | <i>Critical Geological Conditions and Seismicity</i> | 7-6 |
| 7.2 | ADEQUACY OF SUPPORTING TECHNICAL DOCUMENTATION | 7-7 |
| 7.3 | ASSESSMENT OF STRUCTURAL STABILITY | 7-7 |
| 8.0 | MAINTENANCE AND METHODS OF OPERATION | 8-1 |

| | | |
|-------|---|-----|
| 8.1 | OPERATIONAL PROCEDURES | 8-1 |
| 8.2 | MAINTENANCE OF THE DAM AND PROJECT FACILITIES..... | 8-1 |
| 8.3 | ASSESSMENT OF MAINTENANCE AND METHODS OF OPERATION | 8-1 |
| 8.3.1 | <i>Adequacy of Operational Procedures</i> | 8-1 |
| 8.3.2 | <i>Adequacy of Maintenance</i> | 8-1 |
| 9.0 | SURVEILLANCE AND MONITORING PROGRAM..... | 9-1 |
| 9.1 | SURVEILLANCE PROCEDURES | 9-1 |
| 9.2 | INSTRUMENTATION MONITORING..... | 9-1 |
| 9.2.1 | <i>Instrumentation Plan</i> | 9-1 |
| 9.2.2 | <i>Instrumentation Monitoring Results</i> | 9-1 |
| 9.2.3 | <i>Evaluation</i> | 9-1 |
| 9.3 | ASSESSMENT OF SURVEILLANCE AND MONITORING PROGRAM | 9-1 |
| 9.3.1 | <i>Adequacy of Inspection Program</i> | 9-1 |
| 9.3.2 | <i>Adequacy of Instrumentation Monitoring Program</i> | 9-2 |

APPENDICES

APPENDIX A – REFERENCE DOCUMENTS

Doc 1: 2009 4th Quarter Dam Safety Inspection Report.pdf
Doc 2: 2009 1st Quarter Dam Safety Inspection Report.pdf
Doc 3: 2008 4th Quarter Dam Safety Inspection Report.pdf
Doc 4: 2008 3rd Quarter Dam Safety Inspection Report.pdf
Doc 5: 2008 1st Quarter Dam Safety Inspection Report.pdf
Doc 6: Earth Embankment Report.pdf
Doc 7: Ash Pond Profile.pdf
Doc 8: Separation Dike Stability Analysis (1of3).pdf
Doc 9: Separation Dike Stability Analysis (2of3).pdf
Doc 10: Separation Dike Stability Analysis (3of3).pdf
Doc 11: Separation Dike Profiles.pdf
Doc 12: Gypsum Overall Plant View.pdf
Doc 13: Ash Pond Construction Dwg.pdf
Doc 14: Separation Dam Plan View.pdf
Doc 15: Ash Pond Overall.pdf
Doc 16: Plant Wansley Ash Pond Discharge Structure.pdf
Doc 17: Slope Stability Analysis.pdf
Doc 18: Liquefaction Potential.pdf
Doc 19: Stormwater Capacity.pdf

APPENDIX B – SITE ASSESSMENT DOCUMENTATION

Doc 1: Coal Combustion Dam Inspection Checklist Form – Georgia Power Wansley
Doc 2: Separation Dike Photo Logs.pdf
Doc 3: West Dike Photo Log.pdf
Doc 4: Photographs.pdf

APPENDIX C – CORRESPONDENCE & ADDITIONAL REFERENCE DOCUMENTATION

Reserved

1.0 CONCLUSIONS AND RECOMMENDATIONS

1.1 CONCLUSIONS

Conclusions are based on visual observations from the one-day site visit, review of technical documentation provided by Georgia Power, and review of state inspection reports.

1.1.1 Conclusions Regarding the Structural Soundness of the Management Unit(s)

The structural stability of the Ash Pond embankments appears to be in **Satisfactory** condition. Slope stability analyses were not provided for the western dike; however, foundation preparation, embankment soils and geometry are consistent. Performance of a separate slope stability analysis is not deemed critical.

1.1.2 Conclusions Regarding the Hydrologic/Hydraulic Safety of the Management Unit(s)

Adequate capacity and freeboard exist to safely pass the design storm.

1.1.3 Conclusions Regarding the Adequacy of Supporting Technical Documentation

Supporting technical documentation was adequate.

1.1.4 Conclusions Regarding the Description of the Management Unit(s)

Descriptions provided are appropriate.

1.1.5 Conclusions Regarding the Field Observations

The emergency overflow concrete channel was cracking and showed a potential to be undermined in future rain events. This is not a safety issue at this time, but needs to be monitored.

1.1.6 Conclusions Regarding the Adequacy of Maintenance and Methods of Operation

Maintenance and methods of operation are adequate.

1.1.7 Conclusions Regarding the Adequacy of the Surveillance and Monitoring Program

Existing surveillance and monitoring programs are adequate.

1.1.8 Classification Regarding Suitability for Continued Safe and Reliable Operation

Facility is SATISFACTORY for continued safe and reliable operation. A classification of “satisfactory” is appropriate when no existing or potential management unit safety deficiencies are recognized. Acceptable performance is expected under all applicable loading conditions (static, hydrologic, seismic) in accordance with the applicable criteria. Minor maintenance items may be required.

1.2 RECOMMENDATIONS

1.2.1 Recommendations Regarding the Structural Stability

Continue with the current maintenance and inspection programs set in place.

1.2.2 Recommendations Regarding the Hydrologic/Hydraulic Safety

None appear warranted at this time.

1.2.3 Recommendations Regarding the Supporting Technical Documentation

Although not deemed a critical analysis, additional documentation is needed to assess the slope stability analysis of the western dike.

1.2.4 Recommendations Regarding the Description of the Management Unit(s)

None appear warranted at this time.

1.2.5 Recommendations Regarding the Field Observations

None appear warranted at this time.

1.2.6 Recommendations Regarding the Maintenance and Methods of Operation

None appear warranted at this time.

1.2.7 Recommendations Regarding the Surveillance and Monitoring Program

Continue current program. Begin monitoring erosion at concrete channel to avoid channel being undermined. Monitor cracking along the concrete channel.

1.2.8 Recommendations Regarding Continued Safe and Reliable Operation

- Perform slope stability analyses with seismic loading conditions for western dike.

1.3 PARTICIPANTS AND ACKNOWLEDGEMENT

1.3.1 List of Participants

Jim Heibron – Georgia Power
Michelle Kroh – Georgia Power
C. R. (Randy) Purser - Georgia Power
Tammy S. Lovvorn - Georgia Power (GP)
Brandon E. Harcrow - Georgia Power (GP)
Rochelle Routman - Georgia Power (GP)
Hugh H. Armitage, P.E. – Southern Company
Gary H. McWhorter, P.E. – Southern Company
Wayne Wang, P.E. – Southern Company
Bradley J. Adams – Troutman Sanders LLP
Hollister A. Hill – Troutman Sanders LLP
Frederic Shmurak, P.E. – Dewberry & Davis, Inc.
Justin Story, E.I. – Dewberry & Davis, Inc.

1.3.2 Acknowledgement and Signature

We acknowledge that the management unit referenced herein has been assessed on June 30, 2010.

Frederic M. Shmurak, PE, Civil Engineer

Justin R. Story, E.I., Civil Designer

2.0 DESCRIPTION OF THE COAL COMBUSTION WASTE MANAGEMENT UNIT(S)

2.1 LOCATION

Plant Wansley's ash pond facility is located just south of Carrollton, Georgia. The ash pond dike is approximately 0.5 miles from the Chattahoochee River. The Town of Centralhatchee is approximately 4 miles downstream of the ash pond embankments. Figure 2.1a depicts a vicinity map around Plant Wansley, while Figure 2.1b depicts an aerial view of Plant Wansley.




Figure 2.1 a: Plant Wansley Vicinity Map




Figure 2.1 b: Plant Wansley Aerial View

2.2 SIZE AND HAZARD CLASSIFICATION

The ash pond is impounded by an earthen embankment system consisting of a dike (hereby referred to as the separation dike) that separates the pond from a large reservoir. A smaller dike (hereby referred to as the western dike) existing near the emergency spillway and outlet of the ash pond was also observed. Based on data provided by Georgia Power, Inc. the ash pond embankment system was constructed to a maximum height of 110 feet with a crest width of 35.4 feet, side slopes of 3(H):1(V) to 2.5(H):1(V) and a length just under 3,000 feet. The maximum storage volume corresponding to the top of the embankment is 16,920 acre-feet or 27,297,333 cubic yards (see Table 2.2b). The water elevation ranges from 795 to 799' and at 799' there is approximately 1,001 acre-feet of storage remaining. The classification for size, based on the height of the dam and storage capacity, is Intermediate in accordance with the USACE Recommended Guidelines for Safety Inspection of Dams ER 1110-2-106 criteria (see Table 2.2a for size classification criteria).

| Table 2.2a USACE ER 1110-2-106 Size Classification | | |
|---|-------------------|-------------|
| Category | Impoundment | |
| | Storage (Ac-ft) | Height (ft) |
| Small | < 1,000 | < 40 |
| Intermediate | 1,000 to < 50,000 | 40 to < 100 |
| Large | > 50,000 | > 100 |

Table 2.2b: Summary of Dam Dimensions and Size

| | Ash Pond |
|-------------------------------------|------------|
| Dam Height (ft) | 110 |
| Crest Width (ft) | 35.4 |
| Length (ft) | ≈3,000 |
| Side Slopes (upstream) H:V | 3 to 2.5:1 |
| Side Slopes (downstream) H:V | 3 to 2.5:1 |
| Hazard Classification | Low |

The ash pond embankment system has been assigned a Hazard Classification of Low by the Georgia Safe Dams Program (GSDP). The low hazard classification was assigned by the state due to the minimal economic damage that would result from improper operation or dam failure. Per the Federal Guidelines for Dam Safety dated April 2004, a low hazard potential classification applies to those dams where failure or misoperation results in no probable loss of human life and low economic and/or environmental losses. Losses are principally limited to the owner's property. Considering the low probability of loss of life as well as the low economic and/or environmental impacts, a Federal Hazard Classification of Low is appropriate for this facility (see Table 2.2c Federal Guidelines for Hazard Classification criteria).

* GSDP assigned a hazard classification of Low due to potential minimal economic loss due to failure.

**Table 2.2c FEMA Federal Guidelines for Dam Safety
Hazard Classification**

| Hazard Potential Classification | Loss of Human Life | Economic, Environmental, Lifeline Losses |
|--|--------------------------------|---|
| Low | None Expected | Low and generally limited to owner |
| Significant | None Expected | Yes |
| High | Probable. One or more expected | Yes (but not necessary for this classification) |

2.3 AMOUNT AND TYPE OF RESIDUALS CURRENTLY CONTAINED IN THE UNIT(S) AND MAXIMUM CAPACITY

Per Georgia Power, the ash pond primarily contains fly, bottom ash, boiler slag, flue gas emission control residues, pyrites and other low volume waste. Other materials that the pond may contain are ash sluice water, categorical low volume wastewater, coal pile storm water runoff and other storm water. The drainage area for the ash pond is approximately 711 acres while the surface area of the pond is approximately 343 acres. The maximum design storage capacity is approximately 16,920 acre-feet or 27,297,333 cubic yards.

| Table 2.3: Amount of Residuals and Maximum Capacity of Unit* | |
|---|-----------------|
| | Ash Pond |
| Surface Area (acre) | 711 |
| Current Storage Volume (acre-feet) | 8,321 |
| Max. Design Storage Capacity (acre-feet) | 16,920 |

2.4 PRINCIPAL PROJECT STRUCTURES

2.4.1 Earth Embankment Dam

The dam embankment generally consists of lean clays and silts obtained from borrow areas. Some sandy material was found in the borrow areas, but was tested and reported to be satisfactory per the design standards. A plan view of the Ash Pond is depicted in Figure 2.4.1 a. (Figures 2.4.1 a and b reflect conditions of the Ash Pond, per the Design Drawings prepared in 1976 and 1973 respectively. Additional drawings of the ash pond are included within Appendix A (Doc 07: Plant Wansley Unit No. 1 Ash Pond.pdf, Doc 13: Ash Pond Construction Drawing, Doc 14: Separation Dam Plan View.pdf and Doc 15: Ash Pond Overall).




Figure 2.4.1 a: Plant Wansley Unit No 1 – Ash Pond




Figure 2.4.1 b: Ash Pond Separation Dike

2.4.2 Outlet Structures

The outlet works consist of a broad crested weir and an open channel emergency spillway. Due to circulation and re-use of sluice water, the plant regulates the ash pond water surface elevation below the invert of the outlet works and has no record of the skimmer weir or the spillway ever being used. During the design of the ash

pond unit, some late changes were made to divert storm water flow away from the pond which eliminates a majority of the elevation fluctuation due to storm events. Once the skimmer weir elevation is breached the flow travels through a Corrugated Metal Pipe (CMP) to the downstream storm water pond.

2.5 CRITICAL INFRASTRUCTURE WITHIN FIVE MILES DOWN GRADIENT

All critical infrastructures were located using aerial photography and might not accurately represent what currently exists down-gradient of the site. Figure 2.5 shows Plant Wansley and associated critical infrastructure, listed in Table 2.5.




Figure 2.5: Plant Wansley Critical Infrastructure Map

| Table 2.5: Plant Wansley Critical Infrastructure Within 5 Miles | | |
|--|------------------------------|---------------|
| Schools | Transportation | Nursing Homes |
| Central Hatchee Elementary School 315 Central Hatchee Parkway Franklin, GA 30217 | Martha Berry Hwy (US Hwy 27) | None |
| | | Fire Stations |
| | | None |

3.0 SUMMARY OF RELEVANT REPORTS, PERMITS AND INCIDENTS

3.1 SUMMARY OF REPORTS ON THE SAFETY OF THE MANAGEMENT UNIT(S)

Approximately thirteen (13) quarterly safety inspection reports were provided by Georgia Power dating back to 2005. Information pertaining to the separation dike of the most recent reports is summarized below.

Southern Company Generation 2009 Inspection Report for Plant Wansley Ash Pond Complex, REA # WN-08900, December 9, 2009 (Appendix A, Doc 1: 2009 4th Quarter Dam Safety Inspection Report):

- The piezometers on the separation dike are generally registering within their historical ranges. Piezometer BB is registering an elevated water level and has generally followed the change in the ash pond elevation. This piezometer was repaired after being damaged in 2008.

Southern Company Generation 2009 Inspection Report for Plant Wansley Ash Pond Complex, REA # WN-08900, January 12, 2009 (Appendix A, Doc 3: 2008 4th Quarter Dam Safety Inspection Report):

- It was noticed the piezometer BB had been broken off and buried during the recent gypsum storage facility construction activities. Water levels in the piezometer appear to be higher, but this may be caused by inspectors using a different reference point to measure the water levels with the pipe being broken off. Plant personnel are inspecting and will advise Hydro Services.
- Current Recommendations: Cracks in concrete lined ditches should be cleaned out and caulked. **Pending completion - open.**
- Status of Previous Recommendations: Upstream and Downstream slopes - Localized erosion rills/gullies need to be repaired to mitigate further erosion. **Fixed – closed.**
- Status of Previous Recommendations: Runoff erosion at crest of upstream slope repaired. **Closed.**

Southern Company Generation 2008 Inspection Report for Plant Wansley Ash Pond Complex, REA # WN-08900, September 9, 2008 (Appendix A, Doc 4: 2008 3rd Quarter Dam Safety Inspection Report):

- The piezometers are registering in their historic ranges. They exhibit a muted relationship to the storage pond elevation, but little relationship to the ash pond elevation.
- Current Recommendations: Upstream and Downstream slopes - Localized erosion rills/gullies need to be repaired to mitigate further erosion

- Status of Previous Recommendations: Runoff erosion at crest of upstream slope repaired. **Pending completion - open.**

Southern Company Generation 2008 Inspection Report for Plant Wansley Ash Pond Complex, REA # WN-08900, May 28, 2008 (Appendix A, Doc 5: 2008 1st Quarter Dam Safety Inspection Report):

- The piezometers are registering in their historic ranges. They exhibit a muted relationship to the storage pond elevation, but little relationship to the ash pond elevation.
- Current Recommendations: Upstream and Downstream slopes - Localized erosion rills/gullies need to be repaired to mitigate further erosion
- Status of Previous Recommendations: Runoff erosion at crest of upstream slope repaired. **Pending completion - open.**

3.2 SUMMARY OF LOCAL, STATE AND FEDERAL ENVIRONMENTAL PERMITS

The ash pond facility is under regulation by the Georgia Department of Natural Resources (GDNR), Environmental Protection Division Safe Dams Program (EPDSDP). The discharges of the ash pond are permitted under the Federal National Pollutant Discharge Elimination Program. (NPDES Permit # GA0026778)

3.3 SUMMARY OF SPILL/RELEASE INCIDENTS (IF ANY)

No spills or releases from the Ash Pond facilities have been noted by Georgia Power for this site.

4.0 SUMMARY OF HISTORY OF CONSTRUCTION AND OPERATION

4.1 SUMMARY OF CONSTRUCTION HISTORY

4.1.1 Original Construction

Construction was started on the ash pond separation dike in 1973. The original designer for the ash pond management unit was Southern Services, Inc. Plant Wansley has disposed of coal combustion by-products (ash) in one main storage impoundment since 1976. The Plant Wansley ash pond was commissioned in 1975.

The dam assessor did not meet with, or receive information from, the design engineer of record regarding foundation preparation for the ash pond. However, the dam assessor did receive documentation from Georgia Power regarding impoundment materials for the ash pond. Information in the report from Georgia Power Company in May of 1975 and the Drawings for the ash pond (1973) provide documentation on the impoundment material (see Appendix A (Doc 06: Earth Embankment Report.pdf, Doc 13: Ash Pond Construction Dwg.pdf and Doc 08: Plant Wansley Separation Dam Stability Analysis, 1 of 3.pdf)). These drawings include soil descriptions for the separation dike. The dike was constructed over a core area that was undercut to weathered rock and then fill was compacted onto the inspected rock.

Gypsum dewatering cells from drawings dated in 2007 were recently added on to the existing ash pond (see Appendix A (Doc 12: Gypsum Overall Plan View)).

4.1.2 Significant Changes/Modifications in Design since Original Construction

No significant changes/modifications were noted for the Ash Pond before 2007.

Plans and specifications dated 2007 show new construction of gypsum dewatering cells that were installed on the existing ash pond facility. These dewatering cells were assumed to have been built to local codes and standards. Upon visual observation of the four dikes for this facility, everything appeared to be well maintained. See Appendix A Doc 12: Gypsum Overall Plan View for a drawing of the dewatering cells.

4.1.3 Significant Repairs/Rehabilitation since Original Construction

No significant repairs or rehabilitation had been noted other than typical maintenance items described in the quarterly reports.

4.2 SUMMARY OF OPERATIONAL HISTORY

4.2.1 Original Operational Procedures

The ash pond was designed and operated for reservoir sedimentation and sediment storage of fly ash, bottom ash and boiler slag. Plant process waste water, coal combustion waste, coal pile stormwater runoff, and minimal stormwater runoff around the Ash Pond facility are pumped into the reservoir. Inflow water is treated through gravity settling and deposition. The ash sluice water is re-circulated through the system by a combination of a gravity fed system and pumps.

4.2.2 Significant Changes in Operational Procedures since Original Startup

No significant operating procedures for the ash pond have changed since the original start-up.

4.2.3 Current Operational Procedures

The ash pond was designed and operated for reservoir sedimentation and sediment storage of fly ash, bottom ash and boiler slag. Plant process waste water, coal combustion waste, coal pile stormwater runoff, and minimal stormwater runoff around the Ash Pond facility are pumped into the reservoir. Inflow water is treated through gravity settling and deposition. The ash sluice water is re-circulated through the system by a combination of a gravity fed system and pumps.

4.2.4 Other Notable Events since Original Startup

No additional information was provided.

5.0 FIELD OBSERVATIONS

5.1 PROJECT OVERVIEW AND ASSESSMENT

Dewberry personnel Frederic Shmurak, PE and Justin Story, EI performed a site visit on Wednesday, June 30, 2010. The site visit began at 8:00 AM. Weather was hot and cloudy. The overall visual assessment of the Ash Pond was that it is in satisfactory condition and no significant findings were noted. Coal Combustion Dam Inspection Checklists created on June 30, 2030, by the two engineers for the Plant Wansley Ash Pond are provided in Appendix B, Doc 1: 2010.06.28 – Ash Pond Checklist. Photographs from the site visit are provided in Appendix B, Doc 4: Photographs.

5.2 EARTH EMBANKMENT DAM

5.2.1 Crest

The crest was covered by graded aggregate base material and had no signs of any rutting, depressions, tension cracks or other indications of settlement or shear failure, and appeared to be in satisfactory condition.

5.2.2 Upstream Slope

The upstream slope of the separation dike is mostly lined with rip rap and stone. Scarps, sloughs, depressions, bulging or other indications of slope instability or signs of erosion were not observed.



Figure 5.2.2a: Crest and Upstream Slope of ash pond's separation dike.

The upstream slope of the western dike is mostly lined with rip rap and stone. Scarps, sloughs, depressions, bulging or other indications of slope instability or signs of erosion were not observed.



Figure 5.2.2b: Upstream side of western dike

5.2.3 Downstream Slope and Toe

The downstream slope is mostly lined with rip rap and stone. Scarps, sloughs, depressions, bulging or other indications of slope instability or signs of erosion were not observed. Gravel had been placed at a few locations along the embankment as some regular maintenance. The toe of this slope is below the normal pool of the cooling water pond; therefore, visual assessment of seepage could not be performed.



Figure 5.2.3a: Crest and Downstream Slope of ash pond's separation dike.



Figure 5.2.3b: Gravel placed along downstream embankment which appeared to be routine maintenance



Figure 5.2.3c: Crest and Downstream Slope of ash pond's western dike.

5.2.4 Abutments and Groin Areas

The embankment consists of a raised dike system; therefore the earthen embankment does not abut existing hillsides, rock outcrops or other raised topographic features.

5.3 OUTLET STRUCTURES

5.3.1 Overflow Structure

The outlet structure was not in use; however, it visually appeared to be in good condition. Due to circulation and re-use of sluice water, the plant regulates the ash pond water surface elevation below the invert of the outlet works and has no record of the skimmer weir or the spillway ever being used.

5.3.2 Outlet Conduit

The spillway system was not in use at the time of the assessment; however, the visible portion of the outlet conduit had no apparent deterioration.

5.3.3 Emergency Spillway (If Present)

The emergency overflow spillway visually appeared to be in good condition.

5.3.4 Low Level Outlet

No low level outlet is present.

6.0 HYDROLOGIC/HYDRAULIC SAFETY

6.1 SUPPORTING TECHNICAL DOCUMENTATION

6.1.1 Floods of Record

No flood of record analysis was provided; however, design flow analyses described below indicate there would be no overtopping during floods. This is supported by the fact that the dikes were not reported to have been overtopped during past hurricanes, tropical storms and depressions.

6.1.2 Inflow Design Flood

According to FEMA Federal Guidelines for Dam Safety, current practice in the design of dams is to use the Inflow Design Flood (IDF) that is deemed appropriate for the hazard potential of the dam and reservoir, and to design spillways and outlet works that are capable of safely accommodating the flood flow without risking the loss of the dam or endangering areas downstream from the dam to flows greater than the inflow. The recommended IDF or spillway design flood for a significant hazard intermediate sized structure (See section 2.2), in accordance with the USACE Recommended Guidelines for Safety Inspection of Dams ER 1110-2-106 criteria is the 100-yr to $\frac{1}{2}$ PMF (See Table 6.1.2).

| Table 6.1.2: USACE Hydrologic Evaluation Guidelines Recommended Spillway Design floods | | |
|---|--------------|------------------------------|
| Hazard | Size | Spillway Design Flood |
| Low | Small | 50 to 100-yr frequency |
| | Intermediate | 100-yr to $\frac{1}{2}$ PMF |
| | Large | $\frac{1}{2}$ PMF to PMF |
| Significant | Small | 100-yr to $\frac{1}{2}$ PMF |
| | Intermediate | $\frac{1}{2}$ PMF to PMF |
| | Large | PMF |
| High | Small | $\frac{1}{2}$ PMF to PMF |
| | Intermediate | PMF |
| | Large | PMF |

The Probable Maximum Precipitation (PMP) is defined by American Meteorological Society as the theoretically greatest depth of precipitation for a given duration that is physically possible over a particular drainage area at a certain time of year. The National Weather Service (NWS) further states that in consideration of our limited knowledge of the complicated processes and interrelationships in storms, PMP values are identified as estimates. The NWS has published application procedures that can be used with PMP estimates to develop spatial and temporal characteristics of a Probable Maximum Storm (PMS). A PMS thus developed can be used with a precipitation-runoff simulation model to calculate a probable maximum flood (PMF) hydrograph.

In a stormwater capacity report provided by Southern Company (See Appendix A, Doc 19: Stormwater Capacity.pdf) the authors determined the Wansley Ash Pond can handle the following:

“A 24 hour rainfall runoff of : 1) 16.9 inches of rainfall runoff, which is 2.13 times the 100 year storm, at the level of the emergency spillway crest, and 2) 23.5 inches of rain which is 2.96 times the 100 year storm, at a level one foot below the crest of the dike.”

The Ash Pond is designed to safely pass the design storm corresponding to the $\frac{1}{2}$ PMP and is therefore in compliance with recommended federal guidelines. The 6-hour, 10 square mile PMP is 30.5 inches. Adequate freeboard exists to store the $\frac{1}{2}$ PMP event.

6.1.3 Spillway Rating

No spillway rating was provided. The outlet structure type is unregulated and given little change in the normal pool elevation the resulting discharge rate is expected to be relatively constant.

6.1.4 Downstream Flood Analysis

No downstream flood analysis was provided.

6.2 ADEQUACY OF SUPPORTING TECHNICAL DOCUMENTATION

Supporting technical documentation provided is sufficient.

6.3 ASSESSMENT OF HYDROLOGIC/HYDRAULIC SAFETY

Adequate capacity and freeboard exists to safely pass the design storm.

7.0 STRUCTURAL STABILITY

7.1 SUPPORTING TECHNICAL DOCUMENTATION

7.1.1 Stability Analyses and Load Cases Analyzed

A stability analysis report for the Fly Ash Pond, prepared in 1973, by Southern Services, Inc., with Geotechnical Testing performed by Law Engineering Testing Company, provides information on the stability analysis results and is presented in Section 7.1.4 Factors of Safety and Base Stresses. Drawings provided by Georgia Power dated 1973 also contains the critical data for the slop stability analysis. Both steady state (normal) loading and drawdown loading conditions were analyzed. See Appendix A (Doc 08: Separation Dike Analysis (1 of 3).pdf) for the drawing.

7.1.2 Design Properties and Parameters of Materials

Construction drawings for Plant Wansley's separation dike were prepared by the Georgia Power in conjunction with Southern Services, Inc. from 1973. The drawings include documentation of the shear strength design properties for the Fly Ash Pond, which is included in this report and is presented in the following section; see Appendix A (Doc 08: Separation Dike Analysis (1 of 3).pdf) for the drawing.

| TOTAL STRESS SOIL CHARACTERISTICS | | | | | | |
|--------------------------------------|--------------------------|-------------------|-----------------|---------------------------|-------------------|-----------------|
| TYPE SOIL | CONSTRUCTION | | | STEADY SEEPAGE & DRAWDOWN | | |
| | γ_m LBS/CU.FT. | ϕ DEGREES | C LBS/SQ.FT. | γ_m LBS/CU.FT. | ϕ DEGREES | C LBS/SQ.FT. |
| EMB. FILL (A) | 124 | 26.5 | 1200 | 124 | 19 | 1400 |
| FILTER (B) | 130 | 40 | 0 | 130 | 40 | 0 |
| RIP-RAP (C) | 130 | 38 | 0 | 130 | 38 | 0 |
| BEDROCK (D) | 150 | 40 | 3000 | 150 | 40 | 3000 |
| FILL-1 (E) | 112 | 8 | 550 | 112 | 12 | 700 |
| | | | | | | |

Design Shear Strength

The following items were noted on the Separation Dike Stability Analysis drawings:

- *Safety factors shown are the minimum for each condition. Complete computer results available from Southern Services, Inc.*
- *Safety factors do not include benefit from deposit of ash.*
- *Soil characteristics from Law Engineering and Testing Co. through Georgia Power.*
- *Materials recommended by LETCO for embankment fills are: a. Fine to medium sandy silt (west borrow); b. stiff to hard fine to medium sandy micaeous silt (north borrow); partially weathered rock (LETCO report No. 40 1972).*
- *Embankment fills shall be compacted to at least secure the design strength characteristics used in the analysis of slopes. Field control should ensure the design strength of the materials used in the design.*

The above referenced document is provided in Appendix A (Doc 08: Separation Dike Analysis (1 of 3).pdf).

A more recent study was performed in the 2010 and the results are found below. The soil weight and strength parameters used in the study are consistent with soils found in the Piedmont geological province. For the complete report see Appendix A, Doc 17: Slope Stability Analysis.pdf. There is no evidence that the dikes were built of or upon wet ash, slab, or other unsuitable materials.

| | Dry Unit Weight (pcf) | Moist Unit Weight (pcf) | Effective Stress Parameters | | Total Stress Parameters | |
|----------------------------|-----------------------|-------------------------|-----------------------------|----------------|-------------------------|----------------|
| | | | Internal Friction Angle | Cohesion (psf) | Internal Friction Angle | Cohesion (psf) |
| Embankment Fill | 102 | 123 | 32 | 140 | 29 | 400 |
| Foundation Soil | -- | 112 | 37 | 0 | 24 | 80 |
| Foundation (Gravel Filter) | -- | 130 | 40 | 0 | 40 | 0 |
| Sluiced Ash | -- | 80 | 10 | 0 | 10 | 0 |
| Rock | -- | 150 | 40 | 3000 | 40 | 3000 |

7.1.3 Uplift and/or Phreatic Surface Assumptions

The 1973 Separation Dike Stability Analysis drawings, prepared by Georgia Power and Southern Services, Inc., provides information on the phreatic surface as shown in Figure 7.1.3A and the drawings can be found in Appendix A (Doc 08: Separation Dike Analysis (1of3).pdf). A 2010 slope stability analysis was provided that shows the phreatic surface profiles (See Figure 7.1.3B through D). For the complete

report and drawings showing the phreatic surfaces see Appendix A, Doc 17: Slope Stability Analysis.pdf. Piezometric readings indicate that the phreatic surface has overall been stable and is consistent with the assumptions made in the slope stability models.

“The most recent levels for each pond along with the piezometer readings are summarized in the table below.




Figure 7.1.3a: Historic Piezometer Readings




Figure 7.1.3b: Phreatic Surface Profile (Steady State)

The locations of the piezometers are depicted in Figure 9.2.1, within the Instrumentation Plan Section. (See Appendix A Doc 1 through 5 for inspection reports showing historical piezometer data). Piezometer BB was damaged in 2008 and Georgia Power stated it was recently repaired.

The piezometer reading information generally indicates a steady and consistent trend. There appears to be a major drop in piezometer DD reading in 2004 which is unexplained.

The increased elevated readings of piezometer BB starting in 2008 were potentially caused from measurements being made from different reference points when the top of the pipe was broken off.

Internal drainage collection and discharge piping was not located by the dam assessors during the visual site inspection. However, Georgia Power provided documentation on internal drainage collection (drainage blankets) and discharge piping. See Appendix C (Doc 07: Ash Pond Profile.pdf) for the drawing.

7.1.4 Factors of Safety and Base Stresses

A stability analysis drawing for the separation dike prepared in 1973, by Georgia Power, with Southern Services, Inc. provides information on the factors of safety and is presented below. See Appendix A (Doc 08: Separation Dike Analysis (1of3).pdf) for the complete report.

The results of the stability analysis are summarized in the drawings below. The stability analyses were performed on the downstream slope of the separation dike, however, no information was provided for the western dike.

The safety factors presented in the drawings (Steady State = 1.56; Drawdown = 1.27) show that the slopes of the fly ash facility at Plant Wansley have satisfactory safety factors under static and drawdown conditions.




Figure 7.1.4a: Steady Seepage Profile




Figure 7.1.4b: Drawdown Profile

A slope stability analysis was performed in 2010 and the results are below. For the complete report please see Appendix A, Doc 17: Slope Stability Analysis.pdf.

Table 7.1.4: Factors of Safety

| Failure Conditions | Computed Factor of Safety | Required Minimum Factor of Safety ¹ |
|--|---------------------------|--|
| Downstream Steady State | 1.9 | 1.5 |
| Downstream Seismic | 1.2 | 1.1 |
| Downstream Maximum Surcharge Pool (Ash Pond) | 1.7 | 1.4 |
| Upstream Rapid Drawdown (Ash Pond) | 1.9 | 1.3 |
| Downstream Rapid Drawdown (Storage Pond) | 1.4 | 1.3 |

¹ US Corps of Engineers Manual EM 1110-2-1902, October 2003

Based on the results of the analyses presented in this report, all the dams and dikes that form the fly ash disposal facility at Plant Wansley were found to have stability safety factors at or above the minimum recommended values. Slope stability analysis were not provided for the western dike; however, foundation preparation, embankment soils and geometry are consistent. Performance of a separate slope stability analysis is not deemed critical.

On this basis, it is believed that the facility is performing as intended in its design. Routine maintenance and inspections should continue to enable the facility to perform as found in this evaluation.

7.1.5 Liquefaction Potential

A 2010 study was provided that showed the soils have a factor of safety of 1.4 against liquefaction. It was stated that from liquefaction potential analysis, that *“the separation dike soils are not subject to appreciable strength loss due to earthquake shaking.”* (See Appendix A, Doc 18: Liquefaction Potential.pdf).

A separate soil report stated the fill material came from native borrow sites and the typical soil in the surrounding area does not have liquefaction problems.

Original foundation soil conditions do not appear susceptible to support liquefaction.

7.1.6 Critical Geological Conditions and Seismicity

No critical geological conditions were noted.

An engineering report for Plant Wansley titled “Earth Embankments Final Report and Appendices” references the geological conditions of the site as follows:

“ The site geology and soil profile are typical of much of the Southeastern Piedmont. The plant area and embankments are within the Brevard Zone which is a pronounced geological lineament of deformed rocks extending from Alabama northeastward into North Carolina. The rocks at the site are biotite gneiss and schists, typically striking northeast with a southeast dip. Where sound and unweathered, they are highly competent, but because of the pronounced foliation, they break into flat particles when excavated and crushed. However, this characteristic is not sufficiently detrimental to prevent the rock from being entirely adequate for riprap, bedding material, sub-ballast, and road base. It was not used for concrete aggregate.

Upland soils throughout the site are residual from in-place weathering of underlying parent rock. These soils were used in the construction of dikes and dams, and are generally sandy, micaceous, silts and silty, micaceous, fine sand. The upper layer, however, was more clayey because of advanced weathering of the minerals, and is generally described as red-brown, sandy, silty, clay, sandy, clayey silts.

In the valleys of streams and smaller drainages features, alluvial soils cover the valley floors. These are primarily silts and fine sands, with pockets of soft, organic much soils which required removal before placing embankment. They were not used for embankment fills.”

See Appendix A (Doc 06: Earth Embankment Report.pdf) for the complete document.

Based on USGS Seismic-Hazard Maps for the Conterminous United States, dated 2005, the facility is located in an area anticipated to experience a 0.10g acceleration with a 2-percent probability of exceedance in 50-years.

7.2 ADEQUACY OF SUPPORTING TECHNICAL DOCUMENTATION

Structural stability documentation is adequate.

7.3 ASSESSMENT OF STRUCTURAL STABILITY

The structural stability of the ash pond appears to be satisfactory.

Based on the previous assessment reports/inspections provided by Georgia Safe Dams Program and Georgia Power, this assessment of the fly ash pond is generally consistent with historical observations.

8.0 MAINTENANCE AND METHODS OF OPERATION

8.1 OPERATIONAL PROCEDURES

Operational procedures are adequate. The facility is operated for reservoir sedimentation and sediment storage; specifically, fly ash, bottom ash, pyrites, boiler slag and flue emission control residuals. Coal combustion process waste water and stormwater runoff from the facility are discharged into the reservoir, inflow water is treated through gravity settling and deposition. The sluice water is re-circulated through the plant.

8.2 MAINTENANCE OF THE DAM AND PROJECT FACILITIES

Maintenance procedures are adequate. Grassed areas are routinely mowed and vegetation is removed from the rip-rap slopes. Spillways and outlets are maintained and debris is removed as needed. Deficiencies as noted in the surveillance & monitoring program are corrected and documented.

8.3 ASSESSMENT OF MAINTENANCE AND METHODS OF OPERATION

8.3.1 Adequacy of Operational Procedures

Operational procedures are adequate.

8.3.2 Adequacy of Maintenance

The maintenance program is adequate.

9.0 SURVEILLANCE AND MONITORING PROGRAM

9.1 SURVEILLANCE PROCEDURES

Georgia Power stated they have daily, weekly, monthly, quarterly and annual inspections for the ash pond. Only documentation was provided on the quarterly inspections.

Quarterly Inspections:

A quarterly inspection is conducted by plant personnel and at least one representative of Hydro Services. See Appendix A (Doc 01 through Doc 05) for copies of the 2008 & 2009 quarterly inspection reports.

9.2 INSTRUMENTATION MONITORING

9.2.1 Instrumentation Plan

The following data is based on inspection reports provided by American Electric Power:

An instrumentation plan was not provided, however piezometers have been installed to collect instrumental data. The piezometers are located around the separation dike. For piezometer readings, a water level indicator probe is used, which is lowered within the monitoring well until water is reached, and the distance is recorded. Profiles of the monitoring wells and piezometers are depicted in Figure 9.2.1. Please refer to Appendix A (Doc 11: Separation Dike Profiles.pdf) for piezometer profile drawings.

9.2.2 Instrumentation Monitoring Results

Instrumentation monitoring data has been provided and is discussed in Section 7.1.3 Uplift and/or Phreatic Surface Assumptions.

9.2.3 Evaluation

The historical data indicates that the embankment dams are performing adequately.

9.3 ASSESSMENT OF SURVEILLANCE AND MONITORING PROGRAM

9.3.1 Adequacy of Inspection Program

Inspection program is adequate.

9.3.2 Adequacy of Instrumentation Monitoring Program

The surveillance and monitoring programs should include additional monitoring of the emergency overflow spillway. As indicated previously, the overflow spillway is not in use; however, minor cracking is occurring and the potential for water to undermine the spillway slab exists.




Figure 9.2.1a: Separation Dam Cross Section




Figure 9.2.1b: Separation Dam Cross Section

Southern Company Generation
Bin 10193
241 Ralph McGill Boulevard NE
Atlanta, Georgia 30308-3374

Tel 404.506.7033



December 9, 2009

PLANT WANSLEY

Dam Safety Surveillance
Quarterly Report
REA No. WN-08900

Mr. J. P. Heilbron
Plant Manager
Georgia Power Co.
Plant Wansley

Dear Mr. Heilbron:

Attached is the 4th Quarter - 2009 report on Dam Safety Surveillance for Plant Wansley. The inspection of the dikes at the Main Storage Pond, Ash Pond, Separator Dike, Potable Water Pond, Detention Pond and Gypsum Storage Pond was performed on October 16, 2009 by Hugh Armitage of the SCG Hydro Services Group. A representative from Plant Wansley accompanied Mr. Armitage on the inspections.

This report includes:

- a) A review of the current instrumentation data;
- b) The *4th Quarter - 2009 Dam Safety Inspection Report* summarizing the current and previous recommendations, field observations, comments, and photographs made during the October 16, 2009, inspections;
- c) A copy of the current instrumentation plots;
- d) A copy of the finalized 1st Qtr report. This report was issued in Draft to plant personnel in April 2009.

The current recommendations from this 4th Quarter Inspection are described on the first page of the attached report. The description and status of recommendations from the previous quarterly inspection are also described on pages 1 and 2 of the attached report.

Should you have any questions, please contact Hugh Armitage at extension 8-506-7109.

Sincerely,

A handwritten signature in black ink that reads "Larry B. Wills".

Larry B. Wills
Principal Engineer, Hydro Services

WAN-API 058

/hha

Attachments

CONFIDENTIAL BUSINESS
INFORMATION

xc: **Georgia Power Company**

M. A. Leason (w/ attachment)
N. I. Dean (w/ attachment)
T. S. Lovvorn (w/ attachment)
G. C. Moncus (w/ attachment)
B. Harcrow (w/ attachment)

Southern Company Services

D. E. Jones (w/attachment)
E. B. Allison (w/ attachment)
J. H. Crisler (w/ attachment)
B. J. Peterson (w/attachments)
K. Furman (w/ attachments)

Hydro Service Wansley Notebook
Master File: WN-09900

Hydro Services Correspondence Notebook (w/attachments)

T:\Quarterly Reports\Fossil Plants\2009\WANSLEY\09-4th Qtr\1 - 09-Qtr 4 - Cover Letter.DOC

Instrumentation Data Review 4th Quarter – 2009

In the 3rd quarter of 2009, it was agreed that the level of the storage pond would be gradually reduced by usage to elevation 780 ft. in an effort to reduce the extent of the wet area on the lower downstream slope at Sta. 37+50. This issue has been discussed since the early 1980's. The pond level taken during the November instrumentation readings was reported to be elevation 781.0 feet.

A current assessment of instrumentation data reviewed up to the most recent readings at Plant Wansley is as follows.

Storage Pond:

Sta. 20+00: Piezometers are generally within their historic range and seem to be tracking the pond level.

Sta 37+50-1: Piezometers PP and TT3 experienced a significant drop in elevation in the spring. It is not known exactly why this occurred but may have been related to a delayed response to a decrease in the pond level late in 2008. The readings since July have returned to their historic levels.

Sta 37+50-2: All of these piezometers appear to be in their historic range. They generally are tracking the pond level.

Sta 37+50 Pipe Flows: These flows appear to be in their historic ranges. These flow rates will continue to be monitored to assess if any trends develop. They seem to be tracking the pond level. The flow rate is decreasing at most of the drains as the pond level is being lowered to elevation 780 ft.

Sta 47+50: The piezometers are within their historic range of measurement.

It is recommended that the flow rate at the toe drain at Station 39+00 be obtained at monthly intervals rather than the current 6 month schedule. This information will be useful when modifications to the drains at 37+50 are carried out.

Sta 58+00: The piezometer levels are Sta. 58+00 are within their historic range. The piezometer LLL was repaired this past summer when the drain valve was observed leaking earlier in the year.

Relief Wells: The relief wells appear to be discharging in their historic range, but also in response to the lower pond level. Dip in flow seems to have occurred when the seep was discovered in July.

Sta 65+00: Piezometric levels at C, E and MM are within their historic ranges.

Sta 70+00: All of these piezometers are reading in their historic ranges.

Weir and Pipe Flows: Weir measurements at Sta. 11+20 and 49+00 indicate a continuing trend to their historic range.

Separation Dike:

These piezometers are generally registering in their historic ranges. Although Piezometer BB continues to exhibit has recently exhibited an elevated water level and generally has followed the change in level of the ash pond. The piezometer was repaired after being damaged in 2008.

Potable Water Pond Dike:

These piezometers were registering in their historic ranges and appear to respond to the water level in the main pond level.

Plant Wansley

2009 - 4th Quarter Dam Safety Inspection Summary

Date of Inspection: October 16, 2009

Inspection by: H. Armitage - SCG Hydro Services

Weather: Overcast, windy

Daryl Clayton - Plant Security Officer

Temperature: -56° F

Rainfall (past 24 hrs): 0

SUMMARY

1. No major dam safety issues that would impact the safety of the structures were observed during this inspection. Recommendations to address current and previous inspection observations are summarized below. Many of the current recommendations are routine, on-going maintenance type activities.

ADDITIONAL COMMENTS

- Plant personnel did a very good job in completing many of the recommendations from previous quarterly inspections.
- A copy of the Plant Wansley instrumentation data and review comments are attached.

CURRENT RECOMMENDATIONS

| No. | Description | Location | Status - Open/Closed |
|-----|--|---|----------------------|
| 1 | Sign at Station 0+00 needs to be repaired & reinstalled. | Storage Pond - East Dike | Open |
| 2 | Weeds and grass need to be cut at toe of slope. | Storage Pond - East Dike | Open |
| 3 | Localized bare spots on slopes need to be re-grassed to prevent further erosion and silt washing into ditches. A manufactured grass matting product would be preferable to minimize erosion/wash-out during initial grass growth. | Storage Pond - Various locations along East and Southeast dikes (downstream slopes) | Open |
| 4 | Numerous rodent/animal burrow holes observed on downstream slopes. All require filling in. (Excerpt from FEMA Publication 473 - "Impact of Animals on Earthen Dams". Copy prev. forwarded to plant personnel, provides options for repair). | Storage Pond - Various locations along East & Southeast dikes (downstream slopes) | Open |
| 5 | Numerous ant mounds observed on downstream slopes. Treatment required for ant mounds by fumigants or chemical methods as described in FEMA Publication 473 - "Impact of Animals on Earthen Dams". Copy prev. forwarded to plant personnel, provides options for repair). | Storage Pond - Various locations along East & Southeast dike (downstream slopes) | Open |
| 6 | Clean out debris and dirt in concrete lined toe ditches | Storage Pond - East and Southeast Dikes - Various locations | Open |
| 7 | Localized holes in concrete need to be repaired (i.e. pressure grout) to prevent undermining of concrete. Water flowing out of holes. | Storage Pond - East Dike, Ash Pond Overflow Channel | Open |
| 8 | Mud and debris needs to be removed from behind weir. | Storage Pond - Sta 37+50 - Southeast Dike | Open |
| 9 | Truckload of #57 stone required at Emergency Aggregate stockpiles | Storage Pond - Southeast Dike | Open |
| 10 | Portion of rip rap spillway washed away should be repaired by replacing with a concrete slab or alternatively use Type 1 rip rap placed on a 16ounce/sq. yard non-woven geotextile. Some excavation will be required with rip-rap option so elevation of existing concrete and rip-rap match existing rip rap. | Ash Pond - Emergency Spillway | Open |
| 11 | Repair downstream end of channel using Type #1 rip-rap placed over a 16 oz/sy non-woven geotextile. Area of scour beside the channel should be repaired using type 1 rip rap placed on a 16 oz./sy non-woven geotextile. Alternatively, a concrete slab could be extended from the edge of the concrete channel to prevent future scour. | Ash Pond - Outflow Channel | Open |
| 12 | Eroded area of upstream (west side) to be repaired. Recommended repair procedure provided by SCG Hydro Services to Plant personnel. All vegetation and large rocks/boulders need to be removed from upstream approach channel to prevent future blockage of spillway during high flow conditions. | Potable Water Pond | Open |
| 13 | Fill in several potholes on road at crest of East Dike. | Storage Pond | Open |
| 14 | The measurement of flow from the toe drain at Sta. 39+00 should be done monthly and added to monthly instrumentation report that is sent to Hydro Services. | Storage Pond | Open |
| 15 | The measurement of flow from the new drain installed in July 2009 near the service water pump house should be done monthly and added to the monthly instrumentation report that is sent to Hydro Services. | Storage Pond | Open |

**CONFIDENTIAL BUSINESS
INFORMATION**

Plant Wansley

2009 - 4th Quarter Dam Safety Inspection Summary

STATUS OF PREVIOUS RECOMMENDATIONS

| No. | Location, Description & Action Required | Status - Open/Closed |
|-----|---|--|
| 1 | Storage/Potable Water and Detention Pond -Grassed areas on slope should be fertilized to promote healthy & more robust grass growth. | Ongoing |
| 2 | Storage Pond - Localized rutting on east dike from grass cutting equipment. Ruts to be filled in with soil and compacted and re-grassed | Closed - Repaired |
| 3 | Storage Pond - Localized bare spots on slopes need to be re-grassed to prevent further erosion and silt washing into ditches | Closed - Repaired - However new areas observed. See Current Recommendation 3 |
| 4 | Storage Pond - Various locations along east dike (downstream) - Numerous rodent/animal burrow holes observed on downstream slopes. All require filling in. (Excerpt from FEMA Publication 473 - "Impact of Animals on Earthen Dams" . Copy forwarded to plant personnel, provides options for repair). | Closed-Repaired (New ones since 1st Qtr - See Current Recommendation 4) |
| 5 | Storage Pond - Numerous ant mounds observed on downstream slopes. Treatment required for ant mounds by fumigants or chemical methods as described in FEMA Publication 473 - "Impact of Animals on Earthen Dams". Copy forwarded to plant personnel, provides options for repair) | Closed- Repaired (New ones since 1st Qtr - See Current Recommendation 5) |
| 6 | Storage Pond - A truckload of (a) GDOT #10 washed sand and (b) washed #89 stone is required to replace depleted stockpiles. | 6(a) - Closed 6(b) - Open |
| 7 | Storage Pond - East Dike - Various locations - Clean out debris and dirt in concrete lined toe ditches | Closed- New debris observed in Ditches (See Current Recommendation 6) |
| 8 | Storage Pond - East Dike -Lower Slope - Storage Pond - Sta 37+00 - Repair undermining at end of concrete lined ditch | Closed - Repaired (See Photo 10) |
| 9 | Storage Pond- East Dike - Sta 45+00 & 49+00, 54+00 and Sta 57+00. Clean out ditch behind weirs and inside of the ends of drainage pipes. | Closed - Completed |
| 10 | Ash Pond Emergency Overflow -Several holes observed in bottom of concrete lined ditch and water spouting out. Repair required to mitigate undermining of slab. | Closed - Replaced by Current Recommendation 7 |
| 11 | Ash Pond Emergency Overflow - End of concrete lined ditch is undermined. Needs to be repaired per recommendation in 5-28-08 inspection report (page 11 of 20). | Closed - Repaired (Undermined again during recent heavy rains - See Current Recommendation 11) |
| 12 | Storage Pond -Cracks in concrete lined ditches should be cleaned out and caulked - Pending completion | Open |
| 13 | Storage Pond - Downstream Slopes - Sta 19+00 & 22+00 and 37+50D - Drain pipes need to be cleaned out and repaired. - Pending Completion | Open |
| 14 | Storage Pond - Downstream Slope - Sta 37+50 - Hydro Services investigated wet area 1/29/09 and further options to address will be investigated. Plant personnel needs to monitor this area DAILY for any evidence of distress or unusual events, or movement of slope and contact Hydro Services immediately particularly when pool elev. 782-785 ft. Pending SCG Hydro Services continued monitoring and review. Hydro Services contacted Georgia Safe Dams Program for an extension of time to review possible repair options. | Open - Pending Further Review and Monitoring. Pond level being reduced to elev. 780 ft. to see if this reduces the extent of wet area. Area being monitored daily. |
| 15 | Storage Pond - Downstream Slope - approx. Sta 56+00 - Damaged marker pole for toe drain needs to be repaired. | Open |
| 16 | Storage Pond - Downstream Slope - approx. Sta 62+00 - Damaged concrete ditch needs to be fixed and accumulated silt removed. | Closed - Repaired |
| 17 | Storage Pond - Downstream Slope - Piezometer LLL - Piezometer leak at spigot connection needs to be repaired. Ground surface is wet around piezometer | Closed - Repaired |

OBSERVATIONS FOR 4th QUARTER INSPECTION

| I - Storage Pond - North Dike - (Road to Recreational Area) | | Storage Pond Elev. 782' (10-18-09) |
|---|---|------------------------------------|
| Observations - Comments | | Photograph No. |
| 1. Upstream Slope | | |
| a. Condition | Grass covered - Overall condition is good. No evidence of instability. Several ant mounds near crest that need to be treated with approved pesticide. (See Current Recommendation 5). | n/a |
| b. Erosion/Sloughing | Yes (X) No () - Minor localized bare spots. Need to be re-grassed. (See Current Recommendation 3). | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced - No distress or potholes in road surface observed. | n/a |
| 3. Downstream Slope | | |
| a. Condition | Good - Grass covered and length that permits good observation. | n/a |
| b. Seepage/Wet Spots | Yes () No (X) | n/a |
| c. Erosion/Sloughing | Yes () No (X) | n/a |

**CONFIDENTIAL BUSINESS
INFORMATION**

Plant Wansley

2009 - 4th Quarter Dam Safety Inspection Summary

| II - Storage Pond - East Dike (from North Dike to Spillway) | | |
|---|--|----------------|
| Observations - Comments | | Photograph No. |
| 1. Upstream Slope | | |
| a. Condition | Rip-rap on upstream face looks satisfactory and no dam safety issues observed. | n/a |
| b. Erosion/Sloughing | Yes () No (X) | n/a |
| 2. Crest | | |
| a. Condition | Good - Gravel surfaced. Several depressions on road need to be filled potholes in road surface observed. (See Current Recommendation 13) | 1 |
| 3. Downstream Slope | | |
| a. Condition | Good - Grass covered and at a length that permitted a good visual inspection. See other comments below. | |
| | 1. Station marker at 0+00 needs to be replaced. (See Current Recommendation 1). | 2 |
| | 2. Weeds and grass near toe of slope needs to be cut down (See Current Recommendation 2). | 3 |
| | 3. Numerous bare spots on slopes and areas adjacent to concrete lined ditch need to be re-grassed (i.e. grass matting product) to prevent further erosion and silt from washing into ditch (i.e. see Photo 4 @ Sta 6+10) - (See Current Recommendation 3). | 4 |
| | 4. Rodent holes observed at Sta. 7+00, 17+40. Need to be treated. (See Current Recommendation 4) | n/a |
| | 5. Localized ant mounds observed on slopes. Need to be treated. (See Current Recommendations 5) | n/a |
| b. Seepage/Wet Spots | Yes () No (X) - No seepage or wet spots observed on slope. | n/a |
| c. Erosion/Sloughing | Yes () No (X) - No evidence of instability. | n/a |
| d. Concrete-Lined Drainage Ditch | Concrete in good condition. See other comments below. | 5, 6 & 7 |
| | 1. Debris in drain pipe at Sta. 19+00 need to be cleaned out and new sections of pipe required at drains at Sta 19+00 and 22+00 to repair damaged/crushed outlets ends. (See Previous Recommendation 13). | n/a |
| | 2. Ditch needs to be cleaned out of debris between Sta 2+00 and Sta 19+00. (See Current Recommendation 6). | 5 & 6 |
| | 3. Hole in concrete ditch needs to be repaired (i.e. pressure grouted). (See Current Recommendation 7). | 7 |
| e. Emergency Aggregate Stockpiles | Yes (X) No () - Needs tandem truckload of GDOT #89 stone. (See Previous Recommendation 6 (b)). | n/a |
| III - Storage Pond - Spillway | | |
| Observations - Comments | | Photograph No. |
| 1. Spillway Abutment/Deck | | |
| a. Condition | Concrete condition is satisfactory. | n/a |
| 2. Spillway Floor | | |
| a. Condition | Concrete satisfactory. Localized areas where caulking required to fill open joints. (See Previous Recommendation 12). | n/a |
| 3. Spillway Walls | | |
| a. Condition | Concrete satisfactory | n/a |
| 4. Spillway Gates | | |
| a. Condition | Looked satisfactory. Gate seals appear okay. | n/a |
| 5. Downstream of Spillway (Channel) | | |
| a. Condition | Satisfactory. | n/a |
| IV - Storage Pond - Southeast Dike (Spillway to Separator Dike) | | |
| Observations - Comments | | Photograph No. |
| 1. Upstream Slope | | |
| a. Condition | Rip-rap is satisfactory. No instability or beaching evident. | n/a |
| b. Erosion/Sloughing | Yes () No (X) | n/a |
| 2. Crest | | |
| a. Condition | Satisfactory - Gravel surfaced/Railway tracks - No distress observed along road surface . | n/a |
| 3. Downstream Slope | | |
| 3a - Upper Slope | | |
| a. Condition | Satisfactory - Grass covered. Rodent hole observed above concrete ditch. Near Sta. 41+00. (See Current Recommendation 4). | 8 |
| b. Seepage/Wet Spots | Yes () No (X) | n/a |
| c. Erosion/Sloughing | Yes () No (X) - No evidence of instability. | n/a |

CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley

2009 - 4th Quarter Dam Safety Inspection Summary

| | | |
|--|---|------------------------------|
| 3b - Mid-Slope Road & Drainage Ditch | | |
| a. Road Condition | Gravel surfaced - looks good. No distress or potholes in road surface observed. | n/a |
| b. Concrete-Lined Drainage Ditch | Concrete in good condition. Cleanout debris in concrete lined ditches. (See Current Recommendation 6). | n/a |
| 3c - Middle Slope | | |
| a. Condition | Satisfactory. Grass covered. Recent rodent holes observed, near Sta 40+00 at edge of concrete ditch. (See Current Recommendation 4). | n/a |
| b. Seepage/Wet Spots | Yes () No (X) | n/a |
| c. Erosion/Sloughing | Yes () No (X) | n/a |
| 3d. Lower Road & Drainage Ditch | | |
| a. Road Condition | Gravel surfaced - looks good. No distress or potholes in road surface observed. | n/a |
| b. Concrete-Lined Drainage Ditch | Concrete condition is acceptable | n/a |
| 3e - Lower Slope | | |
| a. Condition | Satisfactory - Grass covered - Grass at a length that permitted a good visual examination. See other comments below. | n/a |
| | 1. Several bare areas require repair. (See Current Recommendation 3) | n/a |
| | 2. Treat ant mounds and rodent holes at various locations. (See Current Recommendations 4 and 5). | n/a |
| b. Seepage/Wet Spots | Yes (X) No () - See other comments below. | n/a |
| | 1. Ground surface in the area of Sta 37+50 is wet. Operating level of pond is at 782 ft. and is gradually being lowered to Elev. 780 ft. in an effort to "dry up" this area. This area will continued to be monitored. | n/a |
| | 2. Sta 37+50 - Mud and debris needs to be cleaned out from behind weir (See Current Recommendation 8). | 9 |
| | 3. Large area of ground subsidence/loss was observed near the downslope concrete drainage ditch. This ground loss occurred presumably because of water migrating beside/beneath the concrete ditch as a result of water flowing into a hole in the bottom of a road crossing culvert that discharges into the concrete drainage ditch (Photo 10). Plant personnel mobilized contractor during the inspection to repair the area per instructions provided by Hydro Services. Hole was backfilled with #89 stone and then covered with clayey soil and grass seed and hay mulch placed at ground surface. Plant subsequently mobilized Civil Field Services to grout the holes in the corroded culvert and also grout in the area of the repair. | 11 |
| | 4. Flow measurement at the toe drain at Station 39+00 should be made monthly and sent to Hydro Services (See Current Recommendation 14) | n/a |
| c. Erosion/Sloughing | Yes () No (X) - No evidence of instability. Some recent bare on slope areas require re-seeding. (See Current Recommendation 3). | n/a |
| d. Concrete Drainage Ditch | Concrete condition is good. Ditches need to be cleaned out of mud and other debris. (See Current Recommendation 6). | n/a |
| e. Concrete Drainage Channel at 37+50 | Concrete condition is good. Rip-rap has been replaced satisfactorily at end on concrete channel. | 10 |
| f. Emergency Aggregate Stockpiles | Yes (X) No () - Need one truckload of GDOT washed # 57 stone (See Current Recommendation 9) | n/a |
| 3f - Lower Concrete-Lined Drainage Ditch | | |
| a. Condition | Acceptable | n/a |
| V - Storage Pond/Ash Pond - Separator Dike | | Ash Pond Elev. 795 ft |
| Observations- Comments | | Photograph No. |
| 1. Upstream Slope (Storage Pond) | | |
| a. Condition | Rip-Rap - Looks satisfactory. No evidence of instability. | n/a |
| b. Erosion/Sloughing | Yes () No (X) | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced and in good condition. | n/a |
| 3. Downstream Slope (Ash Pond) | | |
| 3a. North End | | |
| a. Condition | Rip-Rap - Looks satisfactory. No evidence of instability | n/a |
| b. Erosion/Sloughing | Yes () No (X) | n/a |
| 3b. South End - (No longer applicable due to Gypsum Pond/berm construction) | | |

CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley

2009 - 4th Quarter Dam Safety Inspection Summary

| V - Ash Pond Emergency Overflow & Spillway | | Ash Pond Elev. 795 ft |
|---|--|--------------------------------------|
| Observations- Comments | | Photograph No. |
| 1. Upstream Slope | | |
| a. Condition | Rip-Rap - Looks satisfactory. Grass portion of slope generally looks satisfactory. | n/a |
| b. Erosion/Sloughing | Yes (X) No () - Minor erosion at toe of grassed portion of slope. Not serious at this time but condition should be monitored to assess whether condition deteriorate which will require repair. | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced and in good condition. | n/a |
| 3. Downstream Slope | | |
| a. Condition | Rip-Rap - Looks satisfactory. No evidence of instability | n/a |
| b. Erosion/Sloughing | Yes () No (X) | n/a |
| 4. Concrete Lined Emergency Spillway | | |
| a. Condition | Concrete in good condition. Part of the rip rap of spillway was washed away during heavy rainstorms in September. This area should be repaired. . (See Current Recommendation 10) | n/a |
| 5. Concrete Lined Overflow Channel | | |
| a. Condition | Concrete in good condition. See other comments below. | 15 & 16 |
| | 1. Several localized areas where hole in concrete have water spouting out. Repair option - pressure grouting. (See Current Recommendation 7). | n/a |
| | 2. Downstream outlet end of concrete lined ditch is undermined following heavy September rains. Needs to be repaired. (photo 15). (See Current Recommendation 11). | 15 |
| | 3. Area adjacent to channel (photo 16), was scoured during heavy September rains and overflow of channel. Area needs to be repaired to prevent further erosion/scour. (See Current Recommendation 11). | 16 |
| VII- Potable Water Pond | | Potable Water Pond Elev. 801' |
| Observations - Comments | | Photograph No. |
| 1. Upstream Dike Slope (Potable Water) | | |
| a. Condition | Rip-rap on upstream face looks good. | n/a |
| b. Erosion/Sloughing | Yes (X) No () - Localized, minor surface erosion. | n/a |
| c. Concrete Drainage Ditch | Concrete in good condition. No obstructions in channel observed. | n/a |
| 2. Crest | | |
| a. Condition | Satisfactory - Gravel surfaced. No distress or potholes in road surface observed. | n/a |
| 3. Downstream Dike Slope (Storage Pond) | | |
| a. Condition | Grass covered portion- Satisfactory. Rip Rap covered portion - Satisfactory | n/a |
| b. Seepage/Wet Spots | Yes () No (X) - No seepage or wet spots observed on slope. | n/a |
| c. Erosion/Sloughing | Yes (X) No () - Localized, minor surface erosion. Re-seeding and mulching done and grass starting to grow. | n/a |
| d. Concrete Drainage Ditch | Yes () No (X) - Condition of concrete satisfactory. | n/a |
| 4. Spillway Approach Channel | | |
| a. Condition-General | Portion of the upstream approach embankment washed out during heavy rains in September. SCG Hydro Services provided plant with written repair options. Remaining weeds and large rocks/boulders in approach channel need to be removed. (See Current Recommendation 12). | 17 & 18 |
| b. Condition-Rip-Rap | Good. No evidence of instability. | n/a |
| c. Condition-Concrete | Good. | n/a |
| 5. Spillway Structure - Abutments/Deck | | |
| a. Condition | Concrete in good condition. | n/a |
| 6. Spillway Structure - Floor | | |
| a. Condition | Concrete in good condition | n/a |
| 7. Spillway Structure - Walls | | |
| a. Condition | Concrete - Good | n/a |

CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley

2009 - 4th Quarter Dam Safety Inspection Summary

VIII - Detention Pond


| Observations- Comments | | Photograph No. |
|---|---|----------------|
| 1. Upstream Dike Slope | | |
| a. Condition | Rip-rap in good condition. | n/a |
| b. Erosion/Sloughing | Yes () No (X) - Slope looks satisfactory, no visible instability observed | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced and in good condition. No distress or potholes observed. | n/a |
| 3. Downstream Dike Slope | | |
| a. Condition | Satisfactory Grass-covered. Needs cutting. No visible evidence of instability observed | n/a |
| b. Seepage/Wet Spots | Yes (X) No () - Localized, minor wet water beyond toe of slope. Will continue to be monitored. | n/a |
| c. Erosion/Sloughing | Yes () No (X) | n/a |
| 4. Concrete Spillway Channel | | |
| a. Concrete Condition | Concrete is in good condition | n/a |
| 5. Spillway Outlet Channel | | |
| a. Condition | Rip-rap at outfall and outlet channel is in good condition. No issues observed. | n/a |
| VIII - Gypsum Pond Dikes (No fluid in ponds) | | |
| Observations- Comments | | Photograph No. |
| 1. Upstream Dike Slopes | | |
| a. Condition | Good. | n/a |
| b. Erosion/Sloughing | Yes () No (X) | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced and in good condition. | n/a |
| 3. Downstream Dike Slope | | |
| a. Condition | Grass-covered. Good condition. | n/a |
| b. Seepage/Wet Spots | Yes () No (X) | n/a |
| c. Erosion/Sloughing | Yes () No (X) | n/a |

[Signature]

Hugh H. Armitage - Sr. Engineer

SCG - Hydro Services

Location Plan
Storage Pond and Potable Water Pond







CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley

2009 - 4th Quarter Inspection Photographs - October 16, 2009





(See accompanying report attached)

| Photo No. | Description | |
|-----------|---|--|
| 1 | Storage Pond - East Dike - Crest - Localized depressions at crest should be filled with Graded Aggregate Base (GAB). |  |
| 2 | Storage Pond - East Dike - Marker pole at Sta 0-00 needs to be re-installed. Has been broken off at ground level |  |
| 3 | Storage Pond - East Dike - Cut grass/brush down along toe of dike. |  |
| 4 | Storage Pond - East Dike - Bare areas need to be re-grassed. (Use of a grass mat type product will minimize erosion/wash out during initial growth of grass) |  |

Plant Wansley

2009 - 4th Quarter Inspection Photographs - October 16, 2009





(See accompanying report attached)

| Photo No. | Description | |
|-----------|---|--|
| 5 | Storage Pond - East Dike - Remove mud/debris from drainage ditches, along east dike. |  |
| 6 | Storage Pond - East Dike -Toe Ditch - Remove overgrowth from drainage ditch |  |
| 7 | Storage Pond - East Dike -Toe Ditch - Localized holes in concrete ditch need to be grouted to prevent water flow beneath concrete and potential ground loss |  |
| 8 | Storage Pond- Southeast Dike - Rodent holes on slope need to be filled in. |  |

Plant Wansley

2009 - 4th Quarter Inspection Photographs - October 16, 2009





(See accompanying report attached)

| Photo No. | Description | |
|-----------|---|--|
| 9 | Storage Pond - Southeast Dike - Lower Slope - Sta 37+50. Clear mud/rocks from behind weir. |  |
| 10 | Storage Pond - Southeast Dike - Lower Slope - Sta 37+00 - Undermined area at end of concrete lined ditch fixed satisfactorily. |  |
| 11 | Storage Pond - Southeast Dike-Downstream-Lower Slope -Sta 37+50 - Ground loss resulting from defective/leaking (corroded) culvert allowing water to flow beneath and beside concrete ditch. Both items have been repaired since inspection on 10-16-09. |  |
| 12 | Storage Pond- Southeast Dike - Mid-slope Ditch - Mud and vegetation needs to be removed from ditches. |  |

Plant Wansley

2009 - 4th Quarter Inspection Photographs - October 16, 2009



(See accompanying report attached)

| Photo No. | Description | |
|-----------|---|--|
| 13 | Storage Pond- Southeast Dike - Lower Slope - Toe Ditch - Mud needs to be removed from ditches. |  |
| 14 | Ash Pond- Emergency Overflow - Downstream - Scour adjacent to concrete channel which occurred during Sept-09 heavy rainfall at site. Requires repair. |  |
| 15 | Ash Pond- Emergency Overflow - End of Concrete Channel - Rip-rap has been scoured from beneath end of concrete channel following 09-09 heavy rainfall at site. |  |
| 16 | Ash Pond- Emergency Overflow - Spillway - Rip-rap was scoured due to high flows in adjacent concrete channel following 09-09 rain event |  |


Plant Wansley

2009 - 4th Quarter Inspection Photographs - October 16, 2009

(See accompanying report attached)


| Photo No. | Description | |
|-----------|--|---|
| 17 | Potable Water Pond- Spillway - Upstream - Left, upstream spillway approach embankment needs to be repaired. Hydro Services has provided plant personnel with repair procedure. |  |
| 18 | Potable Water Pond - Spillway (Upstream) - Rip-rap was scoured due to high flows in adjacent concrete channel following Sept-09 rain event. |  |

Wansley Storage Pond Pz's at Sta. 20+00




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Pz's at Sta. 37+50-1




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Pz's at Sta. 37+50-2




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Pipe Flows




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 47+50




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 58+00




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Well Flows




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 65+00




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 70+00




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Weir and Pipe Flows




Wansley Separation Dike Pz's BB and DD



CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Potable Pond Piezometers



CONFIDENTIAL BUSINESS
INFORMATION

Southern Company Generation
Bin 10193
241 Ralph McGill Boulevard NE
Atlanta, Georgia 30308-3374

Tel 404.506.7033



August 14, 2009

PLANT WANSLEY

Dam Safety Surveillance
Quarterly Report
REA No. WN-08900

Mr. J. P. Heilbron
Plant Manager
Georgia Power Co.
Plant Wansley

Dear Mr. Heilbron:

Attached is the 1st Quarter 2009 report on Dam Safety Surveillance for Plant Wansley. The inspection of the Main Storage Pond, Ash Pond Separator Dike, Potable Water Pond and Detention Pond was performed on March 17 and 30, 2009 by Hugh Armitage of the SCG Hydro Services Group. Representatives for Plant McDonough accompanied Mr. Armitage on the inspections.

This report includes:

- a) A review of the current instrumentation data;
- b) The *1st Quarter – 2009 Dam Safety Inspection Report* summarizing the field observations and comments made during the March 17 and 30, 2009 inspections, and;
- c) A copy of the current instrumentation plots.

The current recommendations from the 1st Quarter Inspection are described on the first page of the attached report. The description and status of recommendations from the previous quarterly inspection are also described on pages 1 and 2 of the attached report.

Should you have any questions, please contact Hugh Armitage at extension 8-506-7109.

Sincerely,

A handwritten signature in black ink that reads "Joel Galt".

Joel Galt
Hydro Services Supervisor

WAN-API 057

/hha

Attachments

xc: **Georgia Power Company**

S. J. Winston (w/ attachment)
N. I. Dean (w/ attachment)
B. Harcrow (w/ attachment)

Southern Company Services

D. E. Jones (w/attachment)
E. B. Allison (w/ attachment)
J. H. Crisler (w/ attachment)
B. J. Peterson (w/attachments)
K. Friedel (w/ attachments)

Hydro Service Wansley Notebook
Master File: WN-09900

Hydro Services Correspondence Notebook (w/attachments)

T:\Quarterly Reports\Fossil Plants\2009\WANSLEY\09-1st Qtr\1 - 09-Qtr 1 - Cover Letter.DOC2

Instrumentation Data Review

1st Quarter – 2009

A current assessment of instrumentation data reviewed up to the most recent readings of , at Plant Wansley is as follows.

Storage Pond:

Sta. 20+00: Piezometers are generally within their historic range and seem to be tracking the pond level.

Sta 37+50-1: Piezometers PP and TT3 experienced a significant drop in elevation in the spring. It is not known why this occurred, but the readings for July have returned to their historic levels. All of these piezometers appear to be in their historic range. All generally are tracking the pond level.

Sta 37+50-2: All of these piezometers appear to be in their historic range. They generally are tracking the pond level although most have not yet responded to the recent, modest (November, 2008) increase in elevation

Sta 37+50 Pipe Flows: These flows appear to be in their historic ranges. These flow rates will continue to be monitored to assess if any trends develop. They seem to be tracking the pond level.

Sta 47+50: The piezometers are within their historic range of measurement.

It is recommended that the flow rate at the toe drain at Station 39+00 be obtained at monthly intervals rather than the current 6 month schedule. This information will be useful when modifications to the drains at 37+50 are carried out.

Sta 58+00: The level at piezometer LLL has dropped to more a more consistent historic level, which may be in part related to the decrease in pond level. Repair of a leaking valve, as noted in the attached quarterly report, is required for piezometer LLL.

Relief Wells: The relief wells appear to be discharging in their historic range, but also in response to the lower pond level.

Sta 65+00: Piezometric levels at C, E and MM are within their historic ranges.

Sta 70+00: All of these piezometers are reading in their historic ranges.

Weir and Pipe Flows: Weir measurements at Sta. 11+20 and 49+00 indicate a return to their historic range since the last quarterly inspection report.

Separation Dike:

These piezometers are generally registering in their historic ranges. Piezometer BB has recently exhibited an elevated water level. In discussions with plant personnel, we understand that piezometer BB was covered over during construction of the gypsum ponds this year. The piezometer pipe appears to have been broken off at some point when it was uncovered. This may explain the “apparent” elevated water level,

particularly if the measurements have been made from a lower reference elevation than previous measurements. Plant personnel are investigating and will advise Hydro Services.

Potable Water Pond Dike:

These piezometers were registering in their historic ranges and appear to respond to the decrease in the main pond level.

Plant Wansley

2009 - 1st Quarter Dam Safety Inspection Summary

Date of inspection: March 17 & March 30, 2009

Inspection by: H. Armitage

Weather: 3-17-09 - Sunny, light breeze 3-30-09 - Sunny

Tracy Duke (Flour - 3-17-09)

Temperature: 3-17-09 - '50° F 3-30-09 - 40° F

Brandon Harcrow (GPC-3-30-09)

Rainfall (past 24 hrs):

Russell Poole (Flour- 3-30-09)

SUMMARY

1. No major dam safety issues that would impact the safety of the structures were observed during this inspection. Recommendations to address current and previous inspection observations are summarized below. Many of the current and previous recommendations are routine, on-going maintenance type activities.

ADDITIONAL COMMENTS

1. Plant personnel did a very good job in completing most of the recommendations from previous quarterly inspections.
2. A copy of the Plant Wansley instrumentation data and review comments are attached.

CURRENT RECOMMENDATIONS

| No. | Description | Location | Status - Open/Closed |
|-----|--|---|----------------------|
| 1 | Grassed areas on slope should be fertilized to promote healthy & more robust grass growth. | Storage/Potable Water and Detention Pond | Open |
| 2 | Localized rutting on east dike from grass cutting equipment. Ruts to be filled in with soil and compacted and re-grassed | Storage Pond | Open |
| 3 | Localized bare spots on slopes need to be re-grassed to prevent further erosion and silt washing into ditches | Storage Pond | Open |
| 4 | Numerous rodent/animal burrow holes observed on downstream slopes (upstream slope at Detention Pond I). All require filling in. (Excerpt from FEMA Publication 473 - "Impact of Animals on Earthen Dams". Copy forwarded to plant personnel, provides options for repair). | Storage Pond - Various locations along east dike (downstream) | Open |
| 5 | Numerous ant mounds observed on downstream slopes. Treatment required for ant mounds by fumigants or chemical methods as described in FEMA Publication 473 - "Impact of Animals on Earthen Dams". Copy forwarded to plant personnel, provides options for repair) | Storage Pond | Open |
| 6 | A truckload of a). GDOT #10 washed sand and b). washed #89 stone is required to replace depleted stockpiles. | Storage Pond | Open |
| 7 | Clean out debris and dirt in concrete lined toe ditches | Storage Pond - East Dike - Various locations | Open |
| 8 | Storage Pond - Sta 37+00 - Repair undermining at end of concrete lined ditch | Storage Pond - East Dike -Lower Slope | Open |
| 9 | Sta 45+00 & 49+00, 54+00 and Sta 57+00. Clean out ditch behind weirs and inside of the ends of drainage pipes. | Storage Pond- East Dike | Open |
| 10 | Several holes observed in bottom of concrete lined ditch and water spouting out. Should be investigated further. Repair may be required to mitigate undermining of slab. | Ash Pond Emergency Overflow | Open |
| 11 | End of concrete lined ditch is undermined. Needs to be repaired per recommendation in 5-28-08 inspection report (page 11 of 20). | Ash Pond Emergency Overflow | Open |

STATUS OF PREVIOUS RECOMMENDATIONS

| No. | Location, Description & Action Required | Status - Open/Closed |
|-----|---|----------------------|
| 1 | Storage Pond - Spillway - Downstream of end of spillway requires trees and bushes to be cut down so that flows are not restricted during flow. Completed Satisfactorily | Closed |
| 2 | Detention Pond - Downstream Slope - Small bushes and trees on downstream slope need to be cut down. Completed satisfactorily | Closed |
| 3 | Storage Pond -Cracks in concrete lined ditches should be cleaned out and caulked - Pending completion | Open |
| 4 | Storage Pond - Downstream Slopes - Rodent holes to be filled and fire ant mounds to be treated. (See Current Recommendations 4 & 5) | Closed |
| 5 | Storage Pond - Downstream Slopes - Sta 19+00 & 22+00 and 37+50D - Drain pipes need to be cleaned out and repaired. - Pending Completion | Open |

CONFIDENTIAL BUSINESS INFORMATION

Plant Wansley

2009 - 1st Quarter Dam Safety Inspection Summary

STATUS OF PREVIOUS RECOMMENDATIONS (con't)

| No. | Location, Description & Action Required | Status - Open/Closed |
|-----|---|----------------------|
| 6 | Storage Pond - Downstream Slope - Sta 37+50 - Hydro Services investigated wet area 1/29/09 and further options to address will be investigated. Plant personnel needs to monitor this area DAILY for any evidence of distress or unusual events, or movement of slope and contact Hydro Services immediately particularly when pool elev. 782-785 ft. Pending Completion. Hydro Services has contacted Georgia Safe Dams Program to request an extension of time to review possible repair options. | Open |
| 7 | Storage Pond - Downstream Slope - approx. Sta 56+00 - Damaged marker pole for toe drain needs to be repaired. | Open |
| 8 | Storage Pond - Downstream Slope - approx. Sta 62+00 - Damaged concrete ditch needs to be fixed and accumulated silt removed. | Open |
| 9 | Storage Pond - Downstream Slope - Piezometer LLL - Piezometer leak at spigot connection needs to be repaired. Ground surface is wet around piezometer - Pending Completion. | Open |

OBSERVATIONS FOR 1st QUARTER INSPECTION

| I - Storage Pond - North Dike - (Road to Recreational Area) | | Storage Pond Elev. 785' (3-30-09) |
|--|---|-----------------------------------|
| Observations - Comments | | Photograph No. |
| 1. Upstream Slope | | |
| a. Condition | Grass covered - Overall condition is good. No evidence of instability. | n/a |
| b. Erosion/Sloughing | Yes () No (X) | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced - No distress or potholes in road surface observed. | n/a |
| 3. Downstream Slope | | |
| a. Condition | Grass covered - Overall condition is good. No evidence of instability. | n/a |
| b. Seepage/Wet Spots | Yes () No (X) - No seepage or wet spots observed on slope. | n/a |
| c. Erosion/Sloughing | Yes () No (X) | n/a |
| II - Storage Pond - East Dike (North Dike to Spillway) | | |
| Observations - Comments | | Photograph No. |
| 1. Upstream Slope | | |
| a. Condition | Rip-rap on upstream face looks satisfactory and no dam safety issues observed. | n/a |
| b. Erosion/Sloughing | Yes () No (X) - No evidence of instability observed | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced - No distress or potholes in road surface observed. | n/a |
| 3. Downstream Slope | | |
| a. Condition | Grass covered and at a length that permitted a good visual inspection. Ruts from grass cutting equipment need to be repaired i.e. see Photo 1 @ Sta 0+00 . Numerous bare spots on slopes and areas adjacent to concrete lined ditch need to be re-grassed to prevent further erosion and silt from washing into ditch (i.e. see Photo 2 @ Sta 6+10). Place soil (where necessary), compact and re-establish grass. Rodent holes observed at Sta. 7+00, 17+40 (i.e. see Photo 3 @ Sta 7+00). Localized ant mounds observed on slopes. Need to be treated. All flagged for repair by plant personnel. (See Recommendations 1, 2, 3, 4 and 5) | 1, 2 and 3 |
| b. Seepage/Wet Spots | Yes () No (X) - No seepage or wet spots observed on slope. | n/a |
| c. Erosion/Sloughing | Yes () No (X) - No evidence of instability. | n/a |
| d. Concrete-Lined Drainage Ditch | Concrete in good condition. Drain pipe at Sta. 19+00 need to be cleaned out still. New sections drain pipe required at drains at 19+00 and 22+00 to repair damaged/crushed outlets ends. (See Previous Recommendation 7) | n/a |
| e. Emergency Aggregate Stockpiles | Yes (X) No () - Needs tandem truckload of GDOT #10 washed sand and #89 stone. (See Current Recommendations 6a) and 6b) | n/a |
| III - Storage Pond - Spillway | | |
| Observations - Comments | | Photograph No. |
| 1. Spillway Abutment/Deck | | |
| a. Condition | Concrete condition is satisfactory. | n/a |
| 2. Spillway Floor | | |
| a. Condition | Concrete satisfactory | n/a |
| 3. Spillway Walls | | |
| a. Condition | Concrete satisfactory | n/a |
| 4. Spillway Gates | | |
| a. Condition | Looked satisfactory. Slight water flow on RHS of RHS gate at bottom. Possible a leaky seal. Plant to investigate when gates opened. | 4 |
| 5. Downstream of Spillway (Channel) | | |
| a. Condition | Vegetation downstream of spillway has been cleaned out satisfactorily. | n/a |

CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley

2009 - 1st Quarter Dam Safety Inspection Summary

IV - Storage Pond - Southeast Dike (Spillway to Separator Dike)

| Observations - Comments | | Photograph No. |
|---|--|----------------|
| 1. Upstream Slope | | |
| a. Condition | Rip-rap looks acceptable. No instability or beaching evident. | n/a |
| b. Erosion/Sloughing | Yes () No (X) | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced/Railway tracks - No distress observed along road surface . | n/a |
| 3. Downstream Slope | | |
| 3a - Upper Slope | | |
| a. Condition | Grass covered - looks satisfactory. | n/a |
| b. Seepage/Wet Spots | Yes () No (X) | n/a |
| c. Erosion/Sloughing | Yes () No (X) - No evidence of instability. | n/a |
| 3b - Mid-Slope Road & Drainage Ditch | | |
| a. Road Condition | Gravel surfaced - looks good. No distress or potholes in road surface observed. | n/a |
| b. Concrete-Lined Drainage Ditch | Concrete in good condition. Cleanout debris in concrete lined ditches. | 5 |
| 3c - Middle Slope | | |
| a. Condition | Grass covered. Satisfactory. No visual evidence of instability. Rodent hole near head wall in 4th Qtr 2008 has been repaired. | n/a |
| b. Seepage/Wet Spots | Yes () No (X) | n/a |
| c. Erosion/Sloughing | Yes () No (X) | n/a |
| 3d. Lower Road & Drainage Ditch | | |
| a. Road Condition | Gravel surfaced - looks good. No distress or potholes in road surface observed. | n/a |
| b. Concrete-Lined Drainage Ditch | Concrete condition is acceptable | n/a |
| 3e - Lower Slope | | |
| a. Condition | Grass covered - Grass at a length that permitted a good visual examination. Several bare areas where require repair and treat ant mound and rodent holes at various locations. (See Current Recommendations 1, 3, 4 and 5) | 6 |
| b. Seepage/Wet Spots | Yes (X) No () 1. Ground surface in the area of Sta 37+50 is wet. No change from 4th Qtr visit. Safe Dams requested a report and repairs be done to address this area by 6-30-09. SCG Hydro Services to request extension to complete investigation and repairs (See photo 7). 2. Rodent hole flagged by plant personnel for repair near Sta 37+50. 3. The area beneath Drain 37+50D was repaired - okay. 4. The area beneath the end of the concrete drainage ditch was repaired but is undermined again. Needs to be repaired per recommendation in 5-28-08 inspection report (page 11 of 20) (See photo 8). 5. The marker sign for the toe drain near approx Sta 56+00 needs to be fixed. 6. Area around Piezometer LL is wet. Appears that the valve is leaking and needs to be fixed. (See Previous Recommendations 6, 7 and 9 and Current Recommendations 7 and 8) | 7 and 8 |
| c. Erosion or Sloughing | Yes () No (X) - No evidence of instability. Some of the localized bare spots in grass cover have been re-seeded, however several other bare areas require same repair. | n/a |
| d. Concrete Drainage Ditch | Concrete condition is good. Sta 45+00, 49+00, 54+00 and 57+00 - Clean-out of debris/leaves in drain pipe, ditch and behind weir is required. (See Current Recommendations 9) | n/a |
| e. Emergency Aggregate Stockpiles | Yes (X) No () - Need one truckload of GDOT washed # 89 stone (See Current Recommendation 6b.) | n/a |
| 3f - Lower Concrete-Lined Drainage Ditch | | |
| a. Condition | Sta 62+00 - Portion of concrete channel is broken and needs to be repaired. Localized portion of concrete ditch needs to be cleaned out of silt and sandy material - (See photo 9 and Previous Recommendation 8) | 9 |

CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley

2009 - 1st Quarter Dam Safety Inspection Summary

| V - Storage Pond/Ash Pond - Separator Dike | | Ash Pond Elev. Not measured |
|---|--|--------------------------------------|
| Observations- Comments | | Photograph No. |
| 1. Upstream Slope (Storage Pond) | | |
| a. Condition | Rip-Rap - Looks satisfactory. No evidence of instability. | n/a |
| b. Erosion/Sloughing | Yes () No (X) | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced and in good condition. A few minor ruts that should be monitored and repaired if condition worsens | n/a |
| 3. Downstream Slope (Ash Pond) | | |
| 3a. North End | | |
| a. Condition | Rip-Rap - Looks satisfactory. No evidence of instability | n/a |
| b. Erosion/Sloughing | Yes () No (X) | n/a |
| 3b. South End - (No longer applicable due to Gypsum Pond/berm construction.) | | |
| a. Condition | Concrete generally in good condition. Several localized areas where water flowing out of joints and holes in concrete. | n/a |
| V - Ash Pond Emergency Overflow | | Ash Pond Elev. 799.5' |
| Observations- Comments | | Photograph No. |
| 1. Upstream Slope | | |
| a. Condition | Rip-Rap - Looks satisfactory. Grass portion of slope generally looks satisfactory, | n/a |
| b. Erosion/Sloughing | Yes (X) No () - Minor erosion at toe of grassed portion of slope. Not serious at this time but condition should be monitored to assess whether condition deteriorate which will require repair. | 10 |
| 2. Crest | | |
| a. Condition | Gravel surfaced and in good condition. | n/a |
| 3. Downstream Slope | | |
| a. Condition | Rip-Rap - Looks satisfactory. No evidence of instability | n/a |
| b. Erosion/Sloughing | Yes () No (X) | n/a |
| 4. Concrete Lined Emergency Spillway | | |
| a. Condition | Concrete in good condition. | n/a |
| 5. Concrete Lined Overflow Ditch | | |
| a. Condition | Concrete in good condition. Several localized areas where hole in concrete have water spouting out (See photo 11). See Current Recommendation 10. Downstream outlet end of concrete lined ditch is undermined. Needs to be repaired per recommendation in 5-28-08 inspection report (page 11 of 20) (See photo 12). See Current Recommendation 11. | 11 & 12 |
| VII- Potable Water Pond | | Potable Water Pond Elev. 801' |
| Observations - Comments | | Photograph No. |
| 1. Upstream Dike Slope (Potable Water) | | |
| a. Condition | Rip-rap on upstream face looks good. | n/a |
| b. Erosion or Sloughing | Yes (X) No () - Localized, minor surface erosion. Re-seeding and mulching has been done and grass is growing. | n/a |
| c. Concrete Drainage Ditch | Concrete in good condition. No obstructions in channel observed. | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced - looks good. No distress or potholes in road surface observed. | n/a |
| 3. Downstream Dike Slope (Storage Pond) | | |
| a. Condition | Grass covered - Overall - looks good. No evidence of instability | n/a |
| b. Seepage/Wet Spots | Yes () No (X) - No seepage or wet spots observed on slope. | n/a |
| c. Erosion or Sloughing | Yes (X) No () - Localized, minor surface erosion. Re-seeding and mulching done and grass starting to grow. | n/a |
| d. Concrete Drainage Ditch | Yes () No (X) - Condition of concrete satisfactory. | n/a |
| 4. Spillway Approach Channel | | |
| a. Condition - General | Small bushes/trees removed. | n/a |
| b. Condition - Rip-Rap | Good. No evidence of instability. | n/a |
| c. Condition - Concrete | Good. | n/a |
| 5. Spillway Structure - Abutments/Deck | | |
| a. Condition | Concrete in good condition. | n/a |
| 6. Spillway Structure - Floor | | |
| a. Condition | Concrete in good condition | n/a |
| 7. Spillway Structure - Walls | | |
| a. Condition | Concrete - Good | n/a |


CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley

2009 - 1st Quarter Dam Safety Inspection Summary

VIII - Detention Pond


| Observations- Comments | | Photograph No. |
|-------------------------------------|--|----------------|
| 1. Upstream Dike Slope | | |
| a. Condition | Rip-rap in good condition. | n/a |
| b. Erosion/Sloughing | Yes () No (X) - Slope looks satisfactory, no visible instability observed | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced and in good condition. No distress or potholes observed. | n/a |
| 3. Downstream Dike Slope | | |
| a. Condition | Grass-covered. Small bushes/trees have been cut down and grass has been cut. Looks satisfactory. No visible evidence or instability observed | n/a |
| b. Visible Seepage or Wet Spots | Yes (X) No () - Localized, minor ponded water beyond toe of slope | n/a |
| c. Erosion/Sloughing | Yes () No (X) | n/a |
| 4. Concrete Spillway Channel | | |
| a. Concrete Condition | Concrete is in good condition | n/a |
| 5. Spillway Outlet Channel | | |
| a. Condition | Rip-rap at outfall and outlet channel is in good condition. No issues observed. | n/a |



Hugh H. Armitage - Sr. Engineer

SCG - Hydro Services





Location Plan
Storage Pond and Potable Water Pond



Plant Wansley

2009 - 1st Quarter Inspection Photographs - March 17 and 30, 2009





(See accompanying report attached)

| Photo No. | Description | |
|-----------|--|--|
| 1 | Storage Pond - East Dike - Localized wheel ruts/erosion need to be repaired on slope. |  <p>Wheel ruts and minor erosion</p> |
| 2 | Storage Pond - East Dike - Localized erosion and bare areas on dike slope and adjacent to toe ditch. Re-establish grass cover. |  |
| 3 | Storage Pond - East Dike - Localized rodent holes observed on slope need to be filled in. |  <p>Rodent Hole</p> |
| 4 | Storage Pond - Spillway Gates - Slight gap between wall and edge of gate allowing water through. Plant to investigate. |  |

**CONFIDENTIAL BUSINESS
INFORMATION**

Plant Wansley

2009 - 1st Quarter Inspection Photographs - March 17 and 30, 2009 (See accompanying report attached)





| Photo No. | Description | |
|-----------|---|--|
| 5 | Storage Pond - East Dike -Toe Ditch - Mid-slope - Bare spots on slope need to be re-graseed. |  |
| 6 | Storage Pond - East Dike -Lower Slope - Bare spots on slope need to be re-graseed. |  |
| 7 | Storage Pond - East Dike - Lower Slope - Sta 37+50. Condition unchanged from previous 4th Qtr visit. |  |
| 8 | Storage Pond - East Dike -Lower Slope - Sta 37+00 - Repair undermining at end of concrete lined ditch |  |

**CONFIDENTIAL BUSINESS
INFORMATION**

Plant Wansley


2009 - 1st Quarter Inspection Photographs - March 17 and 30, 2009

(See accompanying report attached)

| Photo No. | Description | |
|-----------|---|--|
| 9 | Storage Pond - Southeast Dike - Downstream-Lower Slope -Sta 62+00 - Damaged concrete needs repair and removal of silt removal at bottom of ditch. |  |
| 10 | Ash Pond- Emergency Overflow - Upstream - Minor erosion at toe of slope at waterline. Should be monitored for further deterioration that will require repair |  |
| 11 | Ash Pond- Emergency Overflow - Bottom of Concrete Ditch - Several holes in concrete and water spouting from hole. Needs to be investigated and repaired. |  |
| 12 | Ash Pond- Emergency Overflow - Downstream End - Erosion at end of ditch resulting in undermining of concrete. Needs to be repaired. |  |


**CONFIDENTIAL BUSINESS
INFORMATION**

Wansley Storage Pond Pz's at Sta. 20+00




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Pz's at Sta. 37+50-1




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Pz's at Sta. 37+50-2




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Pipe Flows




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 47+50




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 58+00




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Well Flows




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 65+00




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 70+00




Plant Wansley Weir and Pipe Flows




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Potable Pond Piezometers



CONFIDENTIAL BUSINESS
INFORMATION

Wansley Separation Dike Pz's BB and DD



CONFIDENTIAL BUSINESS
INFORMATION

Southern Company Generation
Bin 10193
241 Ralph McGill Boulevard NE
Atlanta, Georgia 30308-3374
Tel 404.506.7033



January 12, 2009

PLANT WANSLEY

Dam Safety Surveillance
Quarterly Report
REA No. WN-08900

Mr. J. P. Heilbron
Plant Manager
Georgia Power Co.
Plant Wansley

Dear Mr. Heilbron:

Attached is the 4th Quarter 2008 report on Dam Safety Surveillance for Plant Wansley. The inspection of the Main Storage Pond, Ash Pond Separator Dike, Potable Water Pond and Detention Pond was performed on November 12, 2008 by Hugh Armitage of the SCG Hydro Services Group. This inspection coincided with the annual inspection of the Storage Pond Main Dike by the Georgia Department of Natural Resources, Environmental Protection Division, Safe Dams Program (SDP). The inspections were coordinated with Mr. T. E. Wilson of Plant Wansley.

This report includes:

**CONFIDENTIAL BUSINESS
INFORMATION**

- a) A review of the current instrumentation data;
- b) A table summarizing visual observations made during the November 12, 2008 inspections. This report is supplemented with relevant site photographs; and
- c) A copy of the current instrumentation data.

As a result of the 4th quarterly inspection, the following recommendations have been discussed with plant personnel and are shown in Table 1. The status for corrective action for previous 2008 recommendations are noted in Table 2.

TABLE -1 Recommendations from 4th Quarter Inspections

WAN-API 056

| No. | Location and Description |
|-----|---|
| 1 | Storage Pond - Downstream Slopes - Rodent holes to be filled and fire ant mounds to be treated. Locations flagged in field by plant personnel |
| 2 | Storage Pond - Downstream Slopes - Sta 19+00 & 22+00 and 37+50D - Drain pipes need to be cleaned out and repaired. Undermined concrete ditch to be repaired (per Hydro Services 5-28-08 letter). |

| No. | Location and Description |
|-----|--|
| 3 | Storage & Potable Water Ponds - Downstream Slopes - Sta 62+00 & other localized areas on slopes. This is an on-going maintenance item. |
| 4 | Storage Pond - Downstream Slope - Sta 37+50 - Hydro Services to investigate wet area in 1st Qtr 2009. Plant personnel needs to monitor this area WEEKLY for any evidence of movement of slope and contact Hydro Services immediately if observed. |
| 5 | Storage Pond - Downstream Slope - approx. Sta 56+00 - Damaged marker pole for toe drain needs to be repaired. |
| 6 | Storage Pond - Downstream Slope - approx. Sta 62+00 - Damaged concrete ditch needs to be fixed and accumulated silt removed. |
| 7 | Storage Pond - Downstream Slope - Piezometer LLL - Piezometer leak at spigot connection needs to be repaired. Ground surface is wet around piezometer |
| 9 | Detention Pond - Downstream Slope - Small bushes and trees on downstream slope need to be cut down. Grass on slope needs to be cut. Source of ponded water downstream of toe needs to be investigated. |

Table 2 - Recommendations from Previous 2008 Quarterly Inspections

| No. | Location, Description & Action | Status Open/Closed |
|-----|---|-----------------------|
| 1 | Storage Pond - Spillway - Downstream of end of spillway requires trees and bushes to be cut down so that flows are not restricted during flow. - Pending Completion | Open |
| 2 | Detention Pond - Downstream Slope - Small bushes and trees on downstream slope need to be cut down. Grass on slope needs to be cut - Pending Completion | Open |
| 3 | Various Locations -Cracks in concrete lined ditches should be cleaned out and caulked - Pending completion | Open |

Should you have any questions, please contact Hugh Armitage at extension 8-506-7109.

Sincerely,



Joel Galt
Hydro Services Supervisor

CONFIDENTIAL BUSINESS
INFORMATION

/hha

Attachments

xc: **Georgia Power Company**
T. E. Wilson (w/ attachment)
N. I. Dean (w/ attachment)

Southern Company Services
E. B. Allison (w/ attachment)
J. H. Crisler (w/ attachment)
F. J. Pryor (w/ attachment)

Hydro Service Wansley Notebook
Master File: WN-08900

Hydro Services Correspondence Notebook (w/attachments)

T:\Quarterly Reports\Fossil Plants\2008\Wansley\08-4th Qtr\1 - 08-Qtr 4 - Cover Letter.DOC

**CONFIDENTIAL BUSINESS
INFORMATION**

Instrumentation Data Review 4th Quarter – 2008

A current assessment of instrumentation data reviewed up to the most recent readings of November 18, 2008, at Plant Wansley is as follows.

Storage Pond:

Sta. 20+00: Piezometers are generally within their historic range and seem to be tracking the pond level.

Sta 37+50-1: All of these piezometers appear to be in their historic range. All generally are tracking the pond level.

Sta 37+50-2: All of these piezometers appear to be in their historic range. They generally are tracking the pond level although most have not yet responded to the recent, modest (November, 2008) increase in elevation

Sta 37+50 Pipe Flows: These flows appear to be in their historic ranges. These flow rates will continue to be monitored to assess if any trends develop. They seem to be tracking the pond level.

Sta 47+50: The piezometers are within their historic range of measurement.

It is recommended that the flow rate at the toe drain at Station 39+00 be obtained at monthly intervals rather than the current 6 month schedule. This information will be useful when modifications to the drains at 37+50 are carried out.

Sta 58+00: The level at piezometer LLL has dropped to more a more consistent historic level, which may be in part related to the decrease in pond level. Repair of a leaking valve, as noted in the attached quarterly report, is required for piezometer LLL.

Relief Wells: The relief wells appear to be discharging in their historic range, but also in response to the lower pond level.

Sta 65+00: Piezometric levels at C, E and MM are within their historic ranges.

Sta 70+00: All of these piezometers are reading in their historic ranges.

Weir and Pipe Flows: Weir measurements at Sta. 11+20 and 49+00 indicate a return to their historic range since the last quarterly inspection report.

**CONFIDENTIAL BUSINESS
INFORMATION**

Separation Dike:

These piezometers are generally registering in their historic ranges. Piezometer BB has recently exhibited an elevated water level. In discussions with plant personnel, we understand that piezometer BB was covered over during construction of the gypsum ponds this year. The piezometer pipe appears to have been broken off at some point when it was uncovered. This may explain the “apparent” elevated water level, particularly if the measurements have been made from a lower reference elevation than

previous measurements. Plant personnel are investigating and will advise Hydro Services.

Potable Water Pond Dike:

These piezometers were registering in their historic ranges and appear to respond to the decrease in the main pond level.

**CONFIDENTIAL BUSINESS
INFORMATION**

Plant Wansley

2008 - 4th Quarter Inspection Summary

Dam Safety Surveillance

Date of Inspection: November 12, 2008

Inspection by: H. Armitage

Weather: Cloudy

(Storage Pond Inspection) T. Wilson - GPC

Temperature: ~48° to 64° F

**CONFIDENTIAL BUSINESS
INFORMATION**

T. Tucker - Fluor

Rainfall (past 24 hrs): 0

A. Murray, S. Madichetty - Ga SDP

SUMMARY

1. No major dam safety issues that would impact the safety of the structures were observed during this inspection. Recommendations to address current and previous inspection observations are summarized below. Many of the current and previous recommendations are routine, on-going maintenance type activities.

ADDITIONAL COMMENTS

1. Plant personnel did a very good job in completing most of the recommendations from previous quarterly inspections.
2. 4th Quarter Inspection done in conjunction with GA EPD Safe Dams Program 2009 Annual Inspection
3. A representative from the plant accompanied the inspectors and Hydro Services on the Storage Pond surveillance. The representative placed small flags where items that need to be corrected.
4. A copy of the Plant Wansley instrumentation data and review comments are attached.

CURRENT RECOMMENDATIONS - 4th Quarter Inspection

| No. | Location and Description | Photo No. |
|-----|---|---------------|
| 1 | Storage Pond - Downstream Slopes - Rodent holes to be filled and fire ant mounds to be treated. Locations flagged in field by plant personnel | 3, 9 & 13 |
| 2 | Storage Pond - Downstream Slopes - Sta 19+00 & 22+00 and 37+50D - Drain pipes need to be cleaned out and repaired. Undermined concrete ditch to be repaired (per Hydro Services 5-28-08 letter) | 5, 6, 14 & 15 |
| 3 | Storage & Potable Water Ponds - Downstream Slopes - Sta 62+00 & other localized areas on slopes. This is an on-going maintenance item. | 11 & 22 |
| 4 | Storage Pond - Downstream Slope - Sta 37+50 - Hydro Services to investigate wet area in 1st Qtr 2009. Plant personnel needs to monitor this area WEEKLY for any evidence of movement of slope and contact Hydro Services immediately if observed. | 12 |
| 5 | Storage Pond - Downstream Slope - approx. Sta 56+00 - Damaged marker pole for toe drain needs to be repaired. | 16 |
| 6 | Storage Pond - Downstream Slope - approx. Sta 62+00 - Damaged concrete ditch needs to be fixed and accumulated silt removed. | 17 |
| 7 | Storage Pond - Downstream Slope - Piezometer LLL - Piezometer leak at spigot connection needs to be repaired. Ground surface is wet around piezometer | 18 |
| 9 | Detention Pond - Downstream Slope - Small bushes and trees on downstream slope need to be cut down. Grass on slope needs to be cut. Source of ponded water downstream of toe needs to be investigated. | 23 & 24 |

STATUS OF PREVIOUS RECOMMENDATIONS

| No. | Location, Description & Action | Status Open/Closed |
|-----|---|-----------------------|
| 1 | Storage Pond - Spillway - Downstream of end of spillway requires trees and bushes to be cut down so that flows are not restricted during flow. - Pending Completion | Open |
| 2 | Detention Pond - Downstream Slope - Small bushes and trees on downstream slope need to be cut down. Grass on slope needs to be cut - Pending Completion | Open |
| 3 | Various Locations - Cracks in concrete lined ditches should be cleaned out and caulked - Pending completion | Open |
| 4 | Storage Pond - North Dike - Warning sign needs to be re-mounted on pole - Fixed - Okay | Closed |

Plant Wansley

2008 - 4th Quarter Inspection Summary

STATUS OF PREVIOUS RECOMMENDATIONS (continued)

| No. | Location, Description & Action | Status Open/Closed |
|-----|---|-----------------------|
| 5 | Storage Pond & Potable Water Pond - General - Localized bare spots on grass covered slopes need repair. Re-seeding and mulching required to prevent further surface erosion. Many areas have been reseeded. This is an on-going maintenance item. | Closed |
| 6 | Storage Pond - East and SE Dike - Concrete Lined Ditches & Toe Drains - Localized vegetation growth and debris needs to be removed from ditches so that flow isn't restricted from approx. Sta. 1+60 to 3+50 and Sta. 5+00 to 23+50. Drains at Sta 73+00 & 74+00 need to be cleaned of silt and debris. - Completed | Closed |
| 7 | Storage Pond - SE Dike (Southwest End) and Potable Water Pond (U/S Slope) - Trees and bushes need to be cut down at toe of slopes to mitigate root growth (seepage path) into embankment - Corrected | Closed |
| 8 | Storage Pond - SE Dike- Lower Slope - Rodent holes on lower slope near Sta. 67+60 and 68+40 need to be filled in. - Repaired | Closed |
| 9 | Separator Dike - Upstream & Downstream Slopes - Localized erosion rills/gullies need to be repaired to mitigate further erosion. - Fixed | Closed |
| 10 | Potable Water Pond Spillway - Upstream end of spillway. (Approach channel) requires trees and bushes to be cut down and cleared so that flows are not restricted - Larger trees/bushes have been cut down | Closed |
| 11 | General Comment & Sta 1+00 to 8+00 - Remove accumulated vegetation from within concrete lined channels -Completed | Closed |
| 12 | Sta. 75+00, 76+00 & 77+00 - Clean out end of finger drains - Completed | Closed |
| 13 | Multiple Locations on slopes -Fill in animal burrows - Rodent holes observed in 1st Qtr filled or could not be found during current inspection - See Current Reco. 6 above | Closed |
| 14 | Sta 73+00 & 74+00 - Bare spots on slope need to be re-seeded. - Some area have become grown over with grass cover satisfactorily. See Current Reco. 2 above | Closed |
| 15 | Sta. 66+00, 70+00 & 72+50 - Repair end of damaged toe drains - The ends have been fixed. | Closed |
| 16 | Sta 62+00 - Clean Silt behind Weir - Cleaned out | Closed |
| 17 | Separator Dike - Runoff erosion at crest of upstream slope repaired | Closed |
| 18 | Localized bare spots on slope to be re-seeded (or covered with small rip-rap). | Closed |
| 19 | Upstream Toe of Slope - Vegetation needs to be cut down - Bushes and trees cut down - ok | Closed |

CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley

2008 - 4th Quarter Inspection Summary

OBSERVATIONS FOR 4th QUARTER INSPECTION

| I - Storage Pond - North Dike - (Road to Recreational Area) | | Storage Pond Elev. 778.1' |
|--|---|----------------------------------|
| Observations - Comments | | Photograph No. |
| 1. Upstream Slope | | |
| a. Condition | Grass covered - Overall condition is good. No evidence of instability. | n/a |
| b. Erosion/Sloughing | Yes () No (X) | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced - No distress or potholes in road surface observed. Sign has been re-mounted on post | 1 |
| 3. Downstream Slope | | |
| a. Condition | Grass covered - Overall condition is good. No evidence of instability. | n/a |
| b. Seepage/Wet Spots | Yes () No (X) - No seepage or wet spots observed on slope. | n/a |
| c. Erosion/Sloughing | Yes () No (X) | n/a |
| II - Storage Pond - East Dike (North Dike to Spillway) | | |
| Observations - Comments | | Photograph No. |
| 1. Upstream Slope | | |
| a. Condition | Rip-rap on upstream face looks satisfactory and no dam safety issues observed. | n/a |
| b. Erosion/Sloughing | Yes () No (X) - No instability observed | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced - No distress or potholes in road surface observed. | n/a |
| 3. Downstream Slope | | |
| a. Condition | Grass covered - Overall - Grass has been cut. Localized bare spots noted on previous inspections have been re-seeded & straw placed over seed. Grass starting to grow in some places. (On-going maintenance issue). Rodent hole at Sta. 7+00 (photo 3), localized fire ant mounds. All flagged for repair by plant personnel. | 2, 3 |
| b. Seepage/Wet Spots | Yes () No (X) - No seepage or wet spots observed on slope. | n/a |
| c. Erosion/Sloughing | Yes () No (X) - No evidence of instability. | n/a |
| d. Concrete-Lined Drainage Ditch | Concrete in good condition. Localized vegetation growth and debris has been removed from ditches (photo 4). Good job done. Drain pipes at Sta. 19+00 and 22+00 need to be cleaned out and repaired (photos 4 and 5) | 4, 5 & 6 |
| e. Emergency Aggregate Stockpiles | Yes (X) No () | |
| III - Storage Pond - Spillway | | |
| Observations - Comments | | Photograph No. |
| 1. Spillway Abutment/Deck | | |
| a. Condition | Concrete condition is satisfactory. Per Ga SDP letter 4-3-08, spall at left abutment has been repaired. | 7 |
| 2. Spillway Floor | | |
| a. Condition | Concrete satisfactory | n/a |
| 3. Spillway Walls | | |
| a. Condition | Concrete satisfactory | n/a |
| 4. Downstream of Spillway (Channel) | | |
| a. Condition | Vegetation downstream of spillway still needs to be cleared to prevent blockage/restriction of flow capacity of channel - Pending activity. | n/a |

CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley

2008 - 4th Quarter Inspection Summary

CONFIDENTIAL BUSINESS
INFORMATION

IV - Storage Pond - Southeast Dike (Spillway to Separator Dike)

| Observations - Comments | | Photograph No. |
|---|--|--------------------------|
| 1. Upstream Slope | | |
| a. Condition | Rip-rap (size varies) on upstream slope looks acceptable. No instability or beaching evident. (SCG sent response to GA EPD-SDP letter 4/3/08. SCG will continue ongoing monitoring of rip-rap). Bushes and trees at toe of slope adjacent to separator dike have been cut down satisfactorily (See Photo 8). | 8 |
| b. Erosion/Sloughing | Yes () No (X) | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced/Railway tracks - No distress observed along road surface . | n/a |
| 3. Downstream Slope | | |
| 3a - Upper Slope | | |
| a. Condition | Grass covered - looks satisfactory. Grass recently cut so good visual examination possible. | n/a |
| b. Seepage/Wet Spots | Yes () No (X) | n/a |
| c. Erosion/Sloughing | Yes () No (X) - No evidence of instability. | n/a |
| 3b - Mid-Slope Road & Drainage Ditch | | |
| a. Road Condition | Gravel surfaced - looks good. No distress or potholes in road surface observed. | n/a |
| b. Concrete-Lined Drainage Ditch | Concrete in good condition. Vegetation in ditch/around drain at Sta. 73+00 has been removed satisfactorily. | n/a |
| 3c - Middle Slope | | |
| a. Condition | Grass covered. Satisfactory. No visual evidence of instability. New rodent hole encountered near head wall and was flagged by plant personnel. | 9 |
| b. Seepage/Wet Spots | Yes () No (X) | n/a |
| c. Erosion/Sloughing | Yes () No (X) | n/a |
| 3d. Lower Road & Drainage Ditch | | |
| a. Road Condition | Gravel surfaced - looks good. No distress or potholes in road surface observed. | n/a |
| b. Concrete-Lined Drainage Ditch | Concrete condition is acceptable | n/a |
| 3e - Lower Slope | | |
| a. Condition | Grass covered - Grass has recently been cut. Overall good coverage. Localized re-seeding has been carried out to fix bare spots Several additional areas require repair. | 10 & 11 |
| b. Seepage/Wet Spots | Yes (X) No () 1. Ground surface in the area of Sta 37+50 is wet. Minor and localized visible water ponded. (photo 12). EPD inspector stated that corrective action be taken to address wet area by 6-2009. This issue was addressed in response letter to EPD dated 10-28-08. 2. Rodent hole flagged by plant personnel for repair near Sta 37+50 (photo 13). 3. The area beneath Drain D is undermined and needs to be repaired (photo 14). 4. The area beneath the end of the concrete drainage ditch is undermined and needs to be repaired (photo 15). 5. The marker sign for the toe drain near approx Sta 56+00 needs to be fixed. Has been damaged. (photo 16). 6. Area around Piezometer LL is wet. Appears that the valve is leaking and needs to be fixed (photo 17). | 12, 13, 14 15, 16 and 17 |
| c. Erosion or Sloughing | Yes () No (X) - No evidence of instability. Some of the localized bare spots in grass cover have been re-seeded, however several other bare areas require same repair. | n/a |
| d. Concrete Drainage Ditch | Concrete condition is good. Sta 49+00 - Clean-out of debris/leaves in drain pipe, ditch and behind weir is required. | n/a |
| e. Emergency Aggregate Stockpiles | Yes (X) No () | n/a |
| 3f - Lower Concrete-Lined Drainage Ditch | | |
| a. Condition | Sta 62+00 - Portion of concrete channel is broken and needs to be repaired. Localized portion of concrete ditch needs to be cleaned out of silt and sandy material | 18 |

Plant Wansley

2008 - 4th Quarter Inspection Summary

| V - Storage Pond/Ash Pond - Separator Dike | | Ash Pond Elev. 799.5' |
|---|---|--------------------------------------|
| Observations- Comments | | Photograph No. |
| 1. Upstream Slope (Storage Pond) | | |
| a. Condition | Rip-Rap - Looks satisfactory. Size of stone on surface of slope varies. No evidence of instability. | n/a |
| b. Erosion or Sloughing | Yes (X) No () - Localized, shallow erosion rills/gullies have been repaired (filled in with stone/rip-rap). | 19 |
| 2. Crest | | |
| a. Condition | Gravel surfaced and in good condition. New gravel has been placed on roadway. | n/a |
| 3. Downstream Slope (Ash Pond) | | |
| 3a. North End | | |
| a. Condition | Rip-Rap - Looks satisfactory. No evidence of instability | n/a |
| b. Erosion or Sloughing | Yes (X) No () - Localized, shallow erosion rills/gullies have been repaired (filled in with stone/rip-rap). | n/a |
| 3b. South End - (No longer applicable due to Gypsum Pond/berm construction) | | |
| a. Condition | N/A - Recently constructed gypsum storage pond dike now abuts the south end of the separator dike. | n/a |
| VII- Potable Water Pond | | Potable Water Pond Elev. 801' |
| Observations - Comments | | Photograph No. |
| 1. Upstream Dike Slope (Potable Water) | | |
| a. Condition | Rip-rap on upstream face looks good. Small trees and bushes at toe have been cut down. | 20 |
| b. Erosion or Sloughing | Yes (X) No () - Localized, minor surface erosion. Re-seeding and mulching has been done to reestablish grass growth in bare areas. | 21 |
| c. Concrete Drainage Ditch | Concrete in good condition. No obstructions in channel observed. | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced - looks good. No distress or potholes in road surface observed. | n/a |
| 3. Downstream Dike Slope (Storage Pond) | | |
| a. Condition | Grass covered - Overall - looks good. No evidence of instability | n/a |
| b. Seepage/Wet Spots | Yes () No (X) - No seepage or wet spots observed on slope. | n/a |
| c. Erosion or Sloughing | Yes (X) No () - Localized, minor surface erosion. Re-seeding and mulching required to re-establish vegetative growth. | 22 |
| d. Concrete Drainage Ditch | Yes () No (X) - Condition of concrete satisfactory. | n/a |
| 4. Spillway Approach Channel | | |
| a. Condition - General | Small bushes/trees removed. | n/a |
| b. Condition - Rip-Rap | Good. No evidence of instability. | n/a |
| c. Condition - Concrete | Good. | n/a |
| 5. Spillway Structure - Abutments/Deck | | |
| a. Condition | Concrete in good condition. | n/a |
| 6. Spillway Structure - Floor | | |
| a. Condition | Concrete in good condition | n/a |
| 7. Spillway Structure - Walls | | |
| a. Condition | Concrete - Good | n/a |

CONFIDENTIAL BUSINESS
INFORMATION


Plant Wansley

2008 - 4th Quarter Inspection Summary


VIII - Detention Pond

| Observations- Comments | | Photograph No. |
|-------------------------------------|--|----------------|
| 1. Upstream Dike Slope | | |
| a. Condition | Rip-rap in good condition. | n/a |
| b. Erosion/Sloughing | Yes () No (X) - Slope looks satisfactory, no visible instability observed | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced and in good condition. No distress or potholes observed. | n/a |
| 3. Downstream Dike Slope | | |
| a. Condition | Grass-covered. Central area of slope has small bushes/trees that need to be removed. Grass requires cutting. No visible evidence or instability observed | 23 |
| b. Visible Seepage or Wet Spots | Yes (X) No () - Localized, minor ponded water beyond toe of slope | 24 |
| c. Erosion or Sloughing | Yes () No (X) | n/a |
| 4. Concrete Spillway Channel | | |
| a. Concrete Condition | Concrete is in good condition | n/a |
| 5. Spillway Outlet Channel | | |
| a. Condition | Rip-rap at outfall and outlet channel is in good condition. No issues observed. | n/a |

CONFIDENTIAL BUSINESS
INFORMATION


Hugh H. Armitage - Sr. Engineer
SCG - Hydro Services





Location Plan
Storage Pond and Potable Water Pond



Plant Wansley

2008 - 4th Quarter Inspection Photographs - November 12, 2008





(See accompanying report attached)

| Photo No. | Description | |
|-----------------------------------|---|--|
| 1 | Storage Pond - N Dike - Near Rec. Center Entrance - Notice sign re-mounted on post |  |
| 2 | Storage Pond - East Dike - Localized areas have been re-seeded to re-establish grass on former bare areas |  |
| 3 | Storage Pond - East Dike - Localized rodent holes to be filled in and fire ant mounds to be treated. The rodent holes and fire ant mounds were flagged by plant personnel |  |
| 4 | Storage Pond - East Dike - Ditches cleaned out of debris/silt |  |
| CONFIDENTIAL BUSINESS INFORMATION | | |

Plant Wansley

2008 - 4th Quarter Inspection Photographs - November 12, 2008

(See accompanying report attached)

| Photo No. | Description | |
|-----------------------------------|--|--|
| 5 | Storage Pond - East Dike - Drain pipe at Station 19+00 needs to be cleaned out. Drain needs to be extended to prevent future clogging |  |
| 6 | Storage Pond - East Dike - Drain pipe at Station 22+00 needs to be fixed. Crushed end to be replaced/repaired |  |
| 7 | Storage Pond - Spillway - Concrete spill on downstream wall has been fixed. |  |
| 8 | Storage Pond - Southeast Dike - Upstream - Bushes and trees have been removed at toe of slope. |  |
| CONFIDENTIAL BUSINESS INFORMATION | | |

Plant Wansley

2008 - 4th Quarter Inspection Photographs - November 12, 2008





(See accompanying report attached)

| Photo No. | Description | |
|-----------------------------------|---|--|
| 9 | Storage Pond- Southeast Dike - Downstream - Sta 64+00 - Rodent Hole to be repaired. |  |
| 10 | Storage Pond- Southeast Dike - Downstream - Sta 64+00 - Areas of slope have been repaired by re-seeding to re-establish grass cover. |  |
| 11 | Storage Pond- Southeast Dike - Downstream - Near Sta 62+00 - Bare area on slope to be seeded to re-establish grass cover. |  |
| 12 | Storage Pond - Southeast Dike - Downstream- Lower Slope at Sta 37+ 50. - EPD Safe Dams Program stated that a repair of wet area required by June 2009 |  |
| CONFIDENTIAL BUSINESS INFORMATION | | |

Plant Wansley

2008 - 4th Quarter Inspection Photographs - November 12, 2008





(See accompanying report attached)

| Photo No. | Description | |
|-----------------------------------|--|--|
| 13 | Storage Pond - Southeast Dike - Downstream-Lower Slope at Sta 37+ 50. Rodent hole to be repaired. Flagged by field personnel. |  |
| 14 | Storage Pond - Southeast Dike - Downstream-Lower Slope at Sta 37+ 50 Drain D - Undermining at end of concrete drainage pipe requires repair. |  |
| 15 | Storage Pond - Southeast Dike - Downstream-Lower Slope at Sta 37+ 50 - Undermining at end of concrete drainage ditch requires repair. (See repair procedure in letter of May 28, 2008) |  |
| 16 | Storage Pond - Southeast Dike - Downstream - Lower Slope at Sta 56+00 - Damaged drain marker to be replaced |  |
| CONFIDENTIAL BUSINESS INFORMATION | | |

Plant Wansley

2008 - 4th Quarter Inspection Photographs - November 12, 2008





(See accompanying report attached)

| Photo No. | Description | |
|-----------------------------------|--|--|
| 17 | Storage Pond - Southeast Dike - Downstream - Lower Slope - Wet area around Piezometer LLL. Appears that drain valve is leaking. Needs to be repaired. |  |
| 18 | Storage Pond - Southeast Dike - Downstream- Lower Slope -Sta 62+00 - Damaged concrete needs repair and removal of silt removal at bottom of ditch. |  |
| 19 | Storage Pond - Spearator Dike- Upstream and Downstream - Erosion gullies have been repaired with stone/rip-rap |  |
| 20 | Potable Water Pond- Upstream Slope - Small trees and bushes have been cut down at downstream toe. |  |
| CONFIDENTIAL BUSINESS INFORMATION | | |
| | | |


Plant Wansley

2008 - 4th Quarter Inspection Photographs - November 12, 2008

(See accompanying report attached)


| Photo No. | Description | |
|-----------------------------------|---|---|
| 21 | Potable Water Pond- Upstream Slope - Localized bare areas have been re-seeded and grass is starting to grow. |  A photograph showing a grassy slope next to a body of water. A circular area of re-seeded grass is highlighted with a black circle. The date 11/12/2008 is visible in the bottom right corner. |
| 22 | Potable Water Pond- Downstream Slope - Localized bare areas need to re-seeded and grass reestablished |  A photograph showing a downstream slope with several localized bare areas highlighted by black circles and a rectangle. The date 11/12/2008 is visible in the bottom right corner. |
| 23 | Detention Pond - Downstream Slope. Small trees to be removed. Grass and weeds to be cut. |  A photograph showing a downstream slope with tall grass and weeds. The date 11/12/2008 is visible in the bottom right corner. |
| 24 | Detention Pond- Downstream - Localized wet areas downstream of toe of slope. Need to investigate source of water. Plant to coordinate with Hydro Services. |  A photograph showing a downstream slope with wet areas. In the background, industrial structures are visible. The date 11/12/2008 is visible in the bottom right corner. |
| CONFIDENTIAL BUSINESS INFORMATION | | |

Wansley Storage Pond Pz's at Sta. 20+00




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Pz's at Sta. 37+50-1




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Pz's at Sta. 37+50-2




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Pipe Flows




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 47+50




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 58+00




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Well Flows




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 65+00




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 70+00




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Weir and Pipe Flows




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Potable Pond Piezometers




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Separation Dike Pz's BB and DD



Plant Wansley Potable Pond Piezometers



CONFIDENTIAL BUSINESS
INFORMATION

Southern Company Generation
Bin 10193
241 Ralph McGill Boulevard NE
Atlanta, Georgia 30308-3374
Tel 404.506.7033



September 9, 2008

PLANT WANSLEY

Dam Safety Surveillance
Quarterly Report
REA No. WN-08900

Mr. J. P. Heilbron
Plant Manager
Georgia Power Co.
Plant Wansley

Dear Mr. Heilbron:

Attached is the 3rd quarter 2008 report on Dam Safety Surveillance for Plant Wansley. The inspection of the main Storage Pond, Ash Pond Separator Dike, Potable Water Pond and Detention Pond was performed on July 22, 2008 by Hugh Armitage of the SCG Hydro Services Group. The inspections were coordinated with Mr. T. E. Wilson and Mr. N. I. Dean of Plant Wansley.

This report includes:

- a) A review of the current instrumentation data;
- b) A table summarizing visual observations made during the July 22, 2008 inspections. The table includes current recommendations and a status update for recommendations contained in the previous quarterly report. This report is supplemented with relevant site photographs; and
- c) A copy of the current instrumentation data.

Should you have any questions, please contact Hugh Armitage at extension 8-506-7109.

Sincerely,

A handwritten signature in black ink that reads "Joel Galt".

Joel Galt
Hydro Services Supervisor

WAN-API 055

**CONFIDENTIAL BUSINESS
INFORMATION**

/hha

Attachments

xc: **Georgia Power Company**

T. E. Wilson (w/ attachment)

N. I. Dean (w/ attachment)

Southern Company Services

D. E. Jones (w/attachment)

E. B. Allison (w/ attachment)

J. H. Crisler (w/ attachment)

F. J. Pryor (w/ attachment)

Hydro Service Wansley Notebook

Master File: WN-08900

Hydro Services Correspondence Notebook (w/attachments)

T:\Quarterly Reports\Fossil Plants\2008\Wansley\08-3rd Qtr\1- 08 Qtr 3 - Cover Letter .DOC

**CONFIDENTIAL BUSINESS
INFORMATION**

Instrumentation Data Review 3rd Quarter – 2008

A current assessment of instrumentation data reviewed up to the most recent readings of July 31, 2008 at Plant Wansley, is as follows.

Storage Pond:

Sta. 20+00: Piezometers are within their historic range. Both seem to track the pond level.

Sta 37+50: All of these piezometers appear to be in their historic range. All generally seem to track the pond level.

Sta 37+50 Pipe Flows: These flows appear to be in their historic ranges. These flow rates will continue to be monitored to assess if any trends develop.

Sta 47+50: With the exception of L, the other piezometers are within their historic range of measurement. Piezometer L experienced a sharp decline at the end of July 2008. However, a reading taken on September 8, 2008, indicated that the level is back to within its historic range. Piezometer K re-bounded to its more historic value in July 2008.

It is recommended that the flow rate at the toe drain at Station 39+00 be obtained at monthly intervals rather than the current 6 month schedule. This information will be useful when modifications to the drains at 37+50 are carried out.

Sta 58+00: LLL1 has continued to display an increasing rise in the piezometric level in July 2008. This trend will continue to be monitored on a monthly basis. The other piezometers are generally within their historic range.

Relief Wells: The relief wells appear to be discharging in their historic range.

Sta 65+00: Piezometric levels at C, E and MM are within their historic ranges.

Sta 70+00: All of these piezometers are reading in their historic ranges.

Weir and Pipe Flows: Weir measurements at Sta. 49+00 have indicated a higher than normal flow the past two measurements (July 31 and September 8, 2008). It is recommended that site personnel continue to measure/monitor the flow rate at this weir on a weekly basis to see if this rate is sustained or reverts back to its historic range. Please keep SCG Hydro Services advised.

Separation Dike:

These piezometers are registering in their historic ranges. They exhibit a muted relationship with the storage pond elevation but little relationship to the ash pond elevation.

Potable Water Pond Dike:

These piezometers were registering in their historic ranges.

**CONFIDENTIAL BUSINESS
INFORMATION**

Plant Wansley

2008 - 3rd Quarter Inspection Summary

Dam Safety Surveillance

| | | | |
|--------------------------------|-------------------------------|--|--------------------|
| Date of Inspection: | <u>July 22, 2008</u> | Inspection by: | <u>H. Armitage</u> |
| Weather: | <u>Sunny to Mostly Cloudy</u> | CONFIDENTIAL BUSINESS INFORMATION | |
| Temperature: | <u>~75° to 91° F</u> | | |
| Rainfall (past 24 hrs): | <u>0.74"</u> | | |

SUMMARY

1. No major dam safety issues that would impact the safety of the structures were observed during this inspection. Recommendations to address current and previous inspection observations are summarized below. Generally, these recommendations are routine, on-going maintenance type activities.

ADDITIONAL COMMENTS

- Plant personnel do a very good job of maintaining the embankment slopes at the different ponds at the site.
- A copy of the Plant Wansley instrumentation data and review comments are attached.

CURRENT RECOMMENDATIONS - 3rd Quarter Inspection

| No. | Location and Description | Photo No. |
|-----|---|--------------|
| 1 | Storage Pond - North Dike - Warning sign needs to be re-mounted on pole | 1 |
| 2 | Storage Pond & Potable Water Pond - General - Localized bare spots on grass covered slopes need repair. Re-seeding and mulching required to prevent further surface erosion. | 2, 6, 16, 21 |
| 3 | Storage Pond - East and SE Dike - Concrete Lined Ditches & Toe Drains - Localized vegetation growth and debris needs to be removed from ditches so that flow isn't restricted from approx. Sta. 1+60 to 3+50 and Sta. 5+00 to 23+50. Vegetation removal required at outlet of Drain at Sta. 19+00. Drains at Sta 73+00 & 74+00 need to be cleaned of silt and debris. | 4, 5 & 12 |
| 4 | Storage Pond Spillway - Downstream of end of spillway requires trees and bushes to be cut down and cleared so that flows are not restricted during flow. | 8 |
| 5 | Storage Pond - SE Dike (South End) and Potable Water Pond (U/S Slope) - Trees and bushes need to be cut down at toe of slopes to mitigate root growth (seepage path) into embankment. | 10 & 20 |
| 6 | Storage Pond - SE Dike- Lower Slope - Rodent holes on lower slope near Sta. 67+60 and 68+40 need to be filled in. | 14 |
| 7 | Storage Pond - SE Dike- Lower Slope - Sta 37+50 - Wet area and small scarp on slope needs to be monitored for any signs of movement on a weekly basis. | 15 |
| 8 | Storage Pond - SE Dike- Lower Slope - Sta 39+00. Increase the flow measurement frequency at the drain at Sta 39+00 to monthly rather than the current 6 month schedule. This information will be useful when modifications to the drains at 37+50 are carried out. | n/a |
| 9 | Separator Dike - Upstream & Downstream Slopes - Localized erosion rills/gullies need to be repaired to mitigate further erosion. | 17 & 18 |
| 10 | Potable Water Pond Spillway - Upstream end of spillway. Approach channel) requires trees and bushes to be cut down and cleared so that flows are not restricted. | 22 |
| 11 | Detention Pond - Downstream Slope - Small bushes and trees on slope need to be cut down. Grass on slope needs to be cut. | 24 |

PREVIOUS RECOMMENDATIONS - 1st Quarter Inspection

| No. | Description & Action | Location | Status Open/Closed |
|-----|---|--------------|-----------------------|
| 1 | General Comment & Sta 1+00 to 8+00 - Remove accumulated vegetation from within concrete lined channels - Pending Completion - See Current Reco. 3 above - See photos 4, 5 & 12). | Storage Pond | Open |
| 2 | Various Locations -Cracks in concrete lined ditches should be cleaned out and caulked - Pending completion | Storage Pond | Open |
| 3 | Sta. 75+00, 76+00 & 77+00 - Clean out end of finger drains - Completed. | Storage Pond | Closed |
| 4 | Multiple Locations on slopes -Fill in animal burrows - Rodent holes observed in 1st Qtr filled or could not be found during current inspection - See Current Reco. 6 above - See Photo 14). | Storage Pond | Closed |

Plant Wansley

2008 - 3rd Quarter Inspection Summary

PREVIOUS RECOMMENDATIONS - 1st Quarter Inspection - Continued

| No. | Description & Action | Location | Status Open/Closed |
|------------|--|---------------------------|-------------------------------|
| 5 | Sta 73+00 & 74+00 - Bare spots on slope need to be re-seeded. - Some area have become grown over with grass cover satisfactorily. See Current Reco. 2 above. (photos 2, 6, 16 and 20) | Storage Pond | Closed |
| 6 | Sta. 66+00, 70+00 & 72+50 - Repair end of damaged toe drains - The ends have been fixed. | Storage Pond | Closed |
| 7 | Sta. 62+50 - near toe of slope - Bare spots on slope need to be reseeded sand mulched. See Current Reco. 2 above (Photos 2, 6, 16, & 20) | Storage Pond | Open |
| 8 | Sta 62+00 - Clean Silt behind Weir - Cleaned out | Storage Pond | Closed |
| 9 | Sta 19+00 - Clean out vegetation of outlet of toe drain - Pending completion | Storage Pond | Open |
| 10 | Sta 37+00 - Undermining at end of concrete channel - Pending completion | Storage Pond | Open |
| 11 | Separator Dike - Runoff erosion at crest of upstream slope. - Pending completion - See Current Rec. 9 - See photos 17 & 18) | Separator Dike | Open |
| 12 | Localized bare spots on slope to be re-seeded (or covered with small rip-rap). Pending completion (See Current Reco. 2 above) | Potable Water Pond | Open |
| 13 | Upstream Toe of Slope- Vegetation needs to be cut down - Pending completion - See Current Reco. 5 above - See photos 5 & 10) | Potable Water Pond | Open |

**CONFIDENTIAL BUSINESS
INFORMATION**

Plant Wansley

2008 - 3rd Quarter Inspection Summary

OBSERVATIONS FOR 3rd QUARTER INSPECTION

| I - Storage Pond - North Dike - (Road to Recreational Area) | | Storage Pond Elev. 783.6' |
|--|---|----------------------------------|
| Observations - Comments | | Photograph No. |
| 1. Upstream Slope | | |
| a. Condition | Grass covered - Overall condition is good. No evidence of instability. | n/a |
| b. Erosion/Sloughing | Yes () No (X) - No beaching observed. | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced - looks good. No distress or potholes in road surface observed. Warning sign needs to be re-mounted onto pole. | 1 |
| 3. Downstream Slope | | |
| a. Condition | Grass covered - Overall condition is good. No evidence of instability. Localized bare spots on slope where re-seeding/mulching required to prevent further erosion. | 2 |
| b. Visible Seepage or Wet Spots | Yes () No (X) - No seepage or wet spots observed on slope. | n/a |
| c. Erosion or Sloughing | Yes () No (X) | n/a |
| II - Storage Pond - East Dike (North Dike to Spillway) | | |
| Observations - Comments | | Photograph No. |
| 1. Upstream Slope | | |
| a. Condition | Rip-rap on upstream face looks satisfactory and no dam safety issues observed. - No beaching observed. Rip Rap varies in size. | n/a |
| b. Erosion/Sloughing | Yes () No (X) | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced - looks good. No distress or potholes in road surface observed. | n/a |
| 3. Downstream Slope | | |
| a. Condition | Grass covered - Overall - looks good. Grass cutting in progress. Localized bare spots need to be re-seeded & mulched (photo 6 - Sta 11+20) | 3 & 6 |
| b. Visible Seepage or Wet Spots | Yes () No (X) - No seepage or wet spots observed on slope. | n/a |
| c. Erosion or Sloughing | Yes () No (X) | n/a |
| d. Concrete-Lined Drainage Ditch | Concrete in good condition. Localized vegetation growth and debris needs to be removed from ditches so that flow isn't restricted from approx. Sta. 1+60 to 3+50 and Sta. 5+00 to 23+50. | 4 & 5 |
| e. Emergency Aggregate Stockpiles | Yes (X) No () | 7 |
| III - Storage Pond - Spillway | | |
| Observations - Comments | | Photograph No. |
| 1. Spillway Abutment/Deck | | |
| a. Condition | Concrete condition is satisfactory. Per Ga SDP letter 4-3-08, crack in left abutment needs to be repaired, just downstream of the gate needs to be fixed. SCG Hydro Services to review during next site inspection. | n/a |
| 2. Spillway Floor | | |
| a. Condition | Concrete condition is satisfactory | n/a |
| 3. Spillway Walls | | |
| a. Condition | Concrete condition is satisfactory | n/a |
| 4. Downstream of Spillway (Channel) | | |
| a. Condition | Vegetation downstream of spillway needs to be cleared to prevent blockage/restriction of flow capacity of channel | 8 |

CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley

2008 - 3rd Quarter Inspection Summary

| IV - Storage Pond - Southeast Dike (Spillway to Separator Dike) | | |
|---|---|----------------|
| Observations - Comments | | Photograph No. |
| 1. Upstream Slope | | |
| a. Condition | Rip-rap (size varies) on upstream slope looks acceptable. No instability or beaching evident. (SCG to assess condition per GA EPD-SDP letter 4/3/08). Bushes and trees at toe of slope need to be cut down to prevent potential instability issues at toe of slope (see Photo 10) | 9, 10 |
| b. Erosion or Sloughing | Yes () No (X) | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced/Railway tracks - No distress or potholes observed in road surface . | n/a |
| 3. Downstream Slope | | |
| 3a - Upper Slope | | |
| a. Condition | Grass covered - looks satisfactory. No evidence of instability observed. | 11 |
| b. Visible Seepage or Wet Spots | Yes () No (X) - No seepage or wet spots observed on slope. | n/a |
| c. Erosion or Sloughing | Yes () No (X) - No evidence of instability. | n/a |
| 3b - Mid-Slope Road & Drainage Ditch | | |
| a. Road Condition | Gravel surfaced - looks good. No distress or potholes in road surface observed. | n/a |
| b. Concrete-Lined Drainage Ditch | Concrete in good condition. Vegetation in ditch/around drain at Sta. 73+00 needs to be removed so that flow isn't restricted. Localized areas where grass growing and silt has built up on bottom of drainage ditch. Removal of vegetation and silt required | 12 |
| 3c - Middle Slope | | |
| a. Condition | Grass covered. Satisfactory. No visual evidence of instability. Previous rodent hole filled in. | 13 |
| b. Visible Seepage or Wet Spots | Yes () No (X) | n/a |
| c. Erosion or Sloughing | Yes () No (X) | n/a |
| 3d. Lower Road & Drainage Ditch | | |
| a. Road Condition | Gravel surfaced - looks good. No distress or potholes in road surface observed. | n/a |
| b. Concrete-Lined Drainage Ditch | Concrete condition is acceptable | n/a |
| 3e - Lower Slope | | |
| a. Condition | Grass covered - Overall - looks good. Grass requires cutting but this did not affect satisfactory visual assessment. Several rodent holes at Stations 67+60 (near headwall) and 68+40 - see photo 14. | 14 |
| b. Visible Seepage or Wet Spots | Yes (X) No () - Wet spot observed at ground surface on lower slope at Sta 37+50. A localized area where a minor slough was observed. Plant personnel were advised of observation and they will routinely monitor condition. | 15 |
| c. Erosion or Sloughing | Yes () No (X) - No evidence of instability. Localized bare spots in grass cover adjacent to drainage ditch and other localized other areas. | 16 |
| d. Concrete Drainage Ditch | Concrete condition is good. Vegetation in ditch at Sta. 73+00 needs to be removed so that flow ditch is not restricted. | n/a |
| e. Emergency Aggregate Stockpiles | Yes (X) No () | n/a |
| 3f - Lower Concrete-Lined Drainage Ditch | | |
| a. Condition | Condition is acceptable | n/a |

CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley

2008 - 3rd Quarter Inspection Summary

| V - Storage Pond/Ash Pond - Separator Dike | | Pond Elev. 783.6' |
|--|---|--|
| Observations- Comments | | Photograph No. |
| 1. Upstream Slope (Storage Pond) | | |
| a. Condition | Rip-Rap - Looks satisfactory. Size of stone on surface of slope varies. No evidence of instability. | n/a |
| b. Erosion or Sloughing | Yes (X) No () - Localized, shallow erosion rills/gullies need to be repaired (filled in with stone/rip-rap). | 17 |
| 2. Crest | | |
| a. Condition | Gravel surfaced and in good condition. No distress or potholes observed on road surface. Clean up of mud on road from construction vehicles required. | n/a |
| 3. Downstream Slope (Ash Pond) | | |
| 3a. North End | | |
| a. Condition | Rip-Rap - Looks satisfactory. Size of stone on surface of slope varies. No evidence of instability. | n/a |
| b. Erosion or Sloughing | Yes (X) No () - Localized, shallow erosion rills/gullies need to be repaired (filled in with stone/rip-rap). | 18 |
| 3b. South End - (No longer applicable due to Gypsum Pond/berm construction) | | |
| a. Condition | N/A - Recently constructed gypsum storage pond dike now abuts the south end of the separator dike. | 19 |
| VI- Potable Water Pond | | Potable Water Pond Elev. 806' |
| Observations - Comments | | Photograph No. |
| 1. Upstream Dike Slope (Potable Water) | | |
| a. Condition | Rip-rap on upstream face looks good. Small trees and bushes at toe need to be cut down to maintain integrity of embankment toe. | 20 |
| b. Erosion or Sloughing | Yes (X) No () - Localized, minor surface erosion. Re-seeding and mulching to reestablish vegetative growth. | 21 |
| c. Concrete Drainage Ditch | Concrete in good condition. No obstructions in channel observed. | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced - looks good. No distress or potholes in road surface observed. | n/a |
| 3. Downstream Dike Slope (Storage Pond) | | |
| a. Condition | Grass covered - Overall - looks good. Localized, minor surface erosion. Re-seeding and mulching to reestablish vegetative growth. | n/a |
| b. Visible Seepage or Wet Spots | Yes () No (X) - No seepage or wet spots observed on slope. | n/a |
| c. Erosion or Sloughing | Yes (X) No () - Localized, minor surface erosion. Re-seeding and mulching to reestablish vegetative growth. | n/a |
| d. Concrete Drainage Ditch | Yes () No (X) - Condition of concrete satisfactory. and no further erosion noticed & are stable at this time. | n/a |
| 4. Spillway Approach Channel | | |
| a. Condition - General | Small bushes/trees to be removed to prevent restriction of flow in channel. | 22 |
| b. Condition - Rip-Rap | Good. No evidence of instability. | n/a |
| c. Condition - Concrete | Good. | n/a |
| 5. Spillway Structure - Abutments/Deck | | |
| a. Condition | Concrete in good condition. | n/a |
| 6. Spillway Structure - Floor | | |
| a. Condition | Concrete in good condition | n/a |
| 7. Spillway Structure - Walls | | |
| a. Condition | Concrete - Good | n/a |

CONFIDENTIAL BUSINESS
INFORMATION


Plant Wansley

2008 - 3rd Quarter Inspection Summary


VII - Detention Pond

| Observations- Comments | | Photograph No. |
|-------------------------------------|--|----------------|
| 1. Upstream Dike Slope | | |
| a. Condition | Rip-rap in good condition. Pond being dredged during visit. Pond level below normal level. | 23 |
| b. Erosion or Sloughing | Yes () No (X) - Slope looks satisfactory, no visible instability observed | n/a |
| 2. Crest | | |
| a. Condition | Gravel surfaced and in good condition. No distress or potholes observed. | n/a |
| 3. Downstream Dike Slope | | |
| a. Condition | Well grass-covered. Needs cutting but this did not prevent good visual examination. Small bushes/trees need to be removed. No visible evidence or instability observed | 24 |
| b. Visible Seepage or Wet Spots | Yes () No (X) | n/a |
| c. Erosion or Sloughing | Yes () No (X) | n/a |
| 4. Concrete Spillway Channel | | |
| a. Concrete Condition | Concrete is in good condition | n/a |
| 5. Spillway Outlet Channel | | |
| a. Condition | Rip-rap at outfall and outlet channel is in good condition. No issues observed. | 25 |

CONFIDENTIAL BUSINESS
INFORMATION


 Hugh H. Armitage - Sr. Engineer
 SCG - Hydro Services





**Location Plan
Storage Pond and Potable Water Pond**



Plant Wansley

2008 - 3rd Quarter Inspection Photographs - July 22, 2008

(See accompanying report attached)





| Photo No. | Description | |
|-----------|---|--|
| 1 | Storage Pond - N Dike - Near Rec. Center Entrance - Warning sign needs to be re-mounted. |  |
| 2 | Storage Pond - N. Dike - Localized bare spots in grass cover. Re-establish grass to prevent erosion. |  |
| 3 | Storage Pond - E. Dike - Downstream slope in good condition |  |
| 4 | Storage Pond - E. Dike - D/S slope - Toe Ditch - Localized vegetation and debris needs removal so that flow isn't restricted. (Sta.1+60 to 3+50). |  |

**CONFIDENTIAL BUSINESS
INFORMATION**

Plant Wansley

2008 - 3rd Quarter Inspection Photographs - July 22, 2008





(See accompanying report attached)

| Photo No. | Description | |
|-----------------------------------|--|--|
| 5 | Storage Pond - East Dike - Concrete lined toe ditches - Vegetation/Debris needs to be cleaned out of ditch (Approx Sta. 5+00 to 23+50) |  |
| 6 | 'Storage Pond - East Dike - Bare spots on slope to be re-seeded to prevent further erosion. Sta 11+20 |  |
| 7 | Storage Pond - East Dike - Emergency Stockpiles of coarse and fine aggregate |  |
| 8 | Storage Pond -Spillway - Vegetation downstream of end of spillway needs to be cleared. |  |
| CONFIDENTIAL BUSINESS INFORMATION | | |
| | | |

Plant Wansley

2008 - 3rd Quarter Inspection Photographs - July 22, 2008




(See accompanying report attached)

| Photo No. | Description | |
|-----------|---|--|
| 9 | Storage Pond - Southeast Dike - Upstream Slope - Rip-rap varies in size from gravel size to 18"-24", occasional 24" to 36" nominal size. Per GA Safe Dams letter of 4-3-08, this will be addressed by SCG Hydro Services. |  |
| 10 | Storage Pond - Southeast Dike - South end near Separator Dike. Bushes and trees need to be removed at toe of slope. |  |
| 11 | Storage Pond - Southeast Dike - Downstream (D/S) - Upper Slope looks satisfactory |  |
| 12 | Storage Pond - Southeast Dike- D/S -Silt and debris removal required at outlet of Drain at Sta. 73+00 and 74+00 |  |

Plant Wansley

2008 - 3rd Quarter Inspection Photographs - July 22, 2008





(See accompanying report attached)

| Photo No. | Description | |
|-----------------------------------|---|--|
| 13 | Storage Pond - Southeast Dike D/S - Previous rodent hole has been filled in. |  |
| 14 | Storage Pond - Southeast Dike D/S - Rodent Holes on lower slope at approx. Sta 67+60 (near headwall) and Sta 68+40 need to be filled | |
| 15 | Storage Pond - Southeast Dike D/S - Sta. 37+50 - Ground surface was damp/wet. A localized area was observed where minor scarp indicating surface movement may have occurred. This area to be monitored routinely by plant for evident of on-going movement. |  |
| 16 | Storage Pond - Southeast Dike D/S - Localized bare spots on lower slope that need to be reseeded/mulched to prevent further erosion. | |
| CONFIDENTIAL BUSINESS INFORMATION | |  |

Plant Wansley

2008 - 3rd Quarter Inspection Photographs - July 22, 2008





(See accompanying report attached)

| Photo No. | Description | |
|--|---|--|
| 17 | Storage/Ash Pond - Separator Dike - Upstream Slope. No evidence of instability or distress. Minor erosion rills/gullies need to be filled in. |  |
| 18 | Storage/Ash Pond - Separator Dike - Downstream Slope - Localized erosion rills/gullies need to be repaired to prevent further erosion. |  |
| 19 | Storage/Ash Pond - Separator Dike - South End. Gypsum Storage pond berm on right side of photo. |  |
| 20 | Potable Water Pond- Upstream Slope. Small trees/bushes at toe need to be removed. |  |
| CONFIDENTIAL BUSINESS INFORMATION | | |

Plant Wansley

2008 - 3rd Quarter Inspection Photographs - July 22, 2008


(See accompanying report attached)

| Photo No. | Description | |
|-----------------------------------|---|--|
| 21 | Potable Water Pond- Upstream Slope. Localized bare spots on slope. Re-establish vegetation to prevent further erosion |  |
| 22 | Potable Water Pond-Spillway Approach Channel- Remove small trees/bushes within channel. |  |
| 23 | Detention Pond - Upstream Slope - Rip-rap in good condition, no visible evidence of instability. |  |
| 24 | Detention Pond - Downstream Slope - Good grass cover, but needs to be cut. Small trees/bushes on slope need to be cut down. |  |
| CONFIDENTIAL BUSINESS INFORMATION | | |

Plant Wansley


2008 - 3rd Quarter Inspection Photographs - July 22, 2008

(See accompanying report attached)

| Photo No. | Description | |
|-----------|---|--|
| 25 | Detention Pond - Outfall Channel - Rip-rap and channel are in good condition. No erosion or instability observed. |  |


**CONFIDENTIAL BUSINESS
INFORMATION**

Wansley Storage Pond Pz's at Sta. 20+00




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Pz's at Sta. 37+50-1




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Pz's at Sta. 37+50-2




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Pipe Flows




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 47+50




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 58+00




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Well Flows




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 65+00




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 70+00




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Weir and Pipe Flows




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Potable Pond Piezometers



CONFIDENTIAL BUSINESS
INFORMATION

Wansley Separation Dike Pz's BB and DD



CONFIDENTIAL BUSINESS
INFORMATION

Southern Company Generation
Bin 10193
241 Ralph McGill Boulevard NE
Atlanta, Georgia 30308-3374
Tel 404.506.7033



May 28, 2008

Plant Wansley
Dam Safety Surveillance
Quarterly Report
REA No. WN-08900

Mr. J. P. Heilbron
Plant Manager
Georgia Power Co.
Plant Wansley

Dear Mr. Heilbron:

Attached is the first 2008 quarterly report on Dam Safety Surveillance for Plant Wansley, prepared by the SCG Hydro Services Group. The report includes observations of site conditions made during our inspection, plots of surveillance data, and our interpretation of this data. The inspection of the Storage Pond Main Dike was carried out on March 10, 2008 in conjunction with the Georgia Department of Natural Resources, Environmental Protection Division, Safe Dams Program (SDP) annual inspection.

No major dam safety issues that would immediately impact the safety of the structures were discovered during this inspection. However, there are a number of maintenance items that should be addressed soon to assure the continued safety and performance of the structures. These items are identified in the report.

Should you have any questions, please do not hesitate to contact me at extension 8-506-7033.

Sincerely,

A handwritten signature in black ink that reads "Joel Galt".

Joel Galt
Hydro Services Supervisor

Attachments

/hha

WAN-API 054

CONFIDENTIAL BUSINESS
INFORMATION

xc: **Georgia Power Company**
T. E. Wilson (w/ attachment)
N. I. Dean (w/ attachment)

Southern Company Services
E. B. Allison (w/ attachment)
J. H. Crisler (w/ attachment)
F. J. Pryor (w/ attachment)

Hydro Service Wansley Notebook
Master File: WN-08900

T:\Quarterly Reports\Fossil Plants\2008\Wansley\08 - Qtr 1 - Wansley Surveillance Report Transmittal.doc

**CONFIDENTIAL BUSINESS
INFORMATION**

INSTRUMENTATION

Following are observations from the review of the dam safety instrumentation at Plant Wansley.

Storage Pond:

Sta. 20+00: Piezometers are within their historic range. Both seem to track the pond level.

Sta 37+50: All of these piezometers appear to be in their historic range. All seem to track pond level.

Sta 37+50 Pipe Flows: These flows appear to be in their historic ranges. The flow at 37+50C seems to be in a recent declining phase, and is at its lowest flow rate in the past four years. These flow rates will continue to be monitored to assess if any trends develop.

Sta 47+50: The relatively high reading measured in September 2007 on SS, appears to have been an anomaly since subsequent readings up to April 2008 have been within the historic range of past measurements. The other piezometers are within their historic range of measurement.

Sta 58+00: LLL1 and LLL have increased slightly since the 3rd quarter 2007 report and are generally within their historic range as is the case with the other piezometers.

Relief Wells: The relief wells appear to be discharging in their historic range. The flow appears to vary with the pond elevation with the exception of well 1.

Sta 65+00: Measurement of the piezometric level at E has resumed since the 3rd Quarter report. C, E and M are within their historic ranges.

Sta 70+00: All of these piezometers are reading in their historic ranges.

Weir and Pipe Flows: With the recent exception of the measurements weir at 49+00 and 11+20 (March/April 2008), both weirs appeared to be flowing in their historic ranges with the exception of the past 2 months. During the inspection it was noted that the weirs at Sta. 62+00 and 57+00 were silted up. These weirs should be cleaned out and allowed to stabilize before each reading. Reading them when they are silted up produces bad data.

Separation Dike:

These piezometers are registering in their historic ranges. They exhibit a muted relationship with the storage pond elevation but little relationship to the ash pond elevation.

Potable Water Pond Dike:

These piezometers were registering in their historic ranges.

INSPECTIONS

On March 10, 2008, Joel Galt and Hugh Armitage of Southern Company Generation (SCG) Hydro Services conducted a dam safety inspection of the dikes at Plant Wansley. The inspection of the Storage Pond Main DiKE was carried out in conjunction with the Georgia Department of Natural Resources, Environmental Protection Division, Safe Dams Program (SDP) annual inspection. Mr. Terry Wilson of Georgia Power Company accompanied SCG and SDP personnel on the inspection of the Storage Pond Main DiKE. The weather was clear and warm. Approximately 2 to 3 inches of rain had fallen in the area the week preceding the inspection, but conditions were generally dry on the day of the inspection.

No major dam safety issues that would immediately impact the safety of the structures were discovered during this inspection. There are a number of maintenance items that should be addressed soon to assure the continued safety and performance of the structures. If not addressed in a timely manner, these things can become more costly to fix. The actions suggested are in **bold text**. These issues can be addressed as time and resources permit, but should be addressed within the next three months.

The site personnel that have the best opportunity to thoroughly inspect the dikes are the mowing crew. During the next mowing of the dikes, it would be a good idea to have the mowing crew flag any ant mounds and animal burrows that they come across. Then the mounds could be poisoned and the burrows filled in. However, safety considerations should be foremost.

The upstream slopes of the main dike, the east dike and separator dikes were examined from a boat. The downstream slopes and the remainder of the upstream slopes at the other ponds were inspected by traversing along the downstream slope and/or making observations from the crest of the dikes.


During this inspection at the Main Storage Dam, we made use of a GPS unit to capture the locations, using waypoints, of items described in the text. The waypoints are indicated by red flags and numbers on an aerial photo of the subject structure. The paragraph describing this location begins with the waypoint number. In some cases, these flags and numbers have tended to overlap, obscuring some of the numbers. Some waypoints were taken for reference, so that all flags on the aerial photos do not necessarily indicate the location of an item described in the text. With experience, we hope that the method can be refined and will result in a report that is more valuable to the user.

Storage Pond - Main DiKE

**CONFIDENTIAL BUSINESS
INFORMATION**

The text for this segment is arranged as if the reader is moving from southwest to northeast along the main storage dike and then to the spillway and then back along the toe of the slope towards the southwest.

LOWER MAIN DIKE



**General Comment – Remove all
accumulated vegetation within concrete
lined channels**



**CONFIDENTIAL BUSINESS
INFORMATION**

Pt. 130 – Cracks in concrete lined channel. **Cracks like this should be cleaned out of dirt and caulked (using a appropriate caulking material).** This will prevent water infiltration and progressive undermining beneath the concrete,



Pt. 131 – Sta. 77+00 – Localized build-up of grass, silt and debris. **Requires clean out of the outlet end of the finger drain.**



Sta. 76+60 – **Animal Burrow** needs to be filled in.



Pt. 132 – Sta. 76+00 - Localized build-up of grass, silt and debris. **Requires clean out of the outlet end of the finger drain.**



Sta. 75+00 – Localized build-up of grass, silt and debris. **Requires clean out of the outlet end of the toe drain.**



Sta. 73+00 to 74+00 – Bare spots on slope. **Re-seed and mulch areas to re-establish grass cover to mitigate surface erosion.**



Pt. 133 (Approx. 75+50)
Pt. 134 (Sta. 73+00)
Pt. 135, 136 (pictured at right) and 137
(~Sta 66+67)

Animal burrows need to be filled in.



Sta. 72+50 and 70+00 (pictured) and 66+00
– End of toe and finger drains damaged by mowers. **Repair ends of drains (i.e. add new section of pipe or beat back into shape). Provide markers to prevent re-occurrence**



**CONFIDENTIAL BUSINESS
INFORMATION**

An aerial photograph of a golf course. A light-colored, sandy path or fairway curves from the bottom left towards the top right. Along this path, several red flag markers are placed, each with a white number. From bottom left to top right, the markers are numbered 920, 921, 922, 923, 924, and 925. The area to the right of the path is covered in dense, dark green trees and foliage. The overall lighting is somewhat dim, suggesting an overcast day or late afternoon.



MN (37° W)

6

Pt. 140 (~Sta. 57+00) – Build-up of silt at weir. **Clean out dirt around weir.**



Pt 141 (~Sta 53+00) – **Animal burrow needs to be filled in.**



Pt. 142 (~Sta. 45+00) – **Three animal burrows at headwall need to be filled in.**



Pt. 143 (approx Sta. 40+00) – **Rip-Rap on upstream slope of main dike.**



**CONFIDENTIAL BUSINESS
INFORMATION**

Pt 144 – Rip-Rap on upstream slope of separator dike.



STORAGE POND - EAST DIKE



Data use subject to license.

© 2008 DeLorme Topo USA® 6.0



Pt. 145 – Sta. 1+00 to 8+00 – Clear debris from finger drains at Sta. 1+00 & Sta. 7+00 and clean out bottom of concrete lined channel of silt/sand and miscellaneous.

(Note: Pt. 146 – not shown on plan – same comment as Pt. 147 below)



**CONFIDENTIAL BUSINESS
INFORMATION**

Pt. 147 – Minor seepage into concrete channel (~ Sta. 12+50).



Pt. 148 (~Sta. 15+00) Finger drain dry, but localized seepage into channel. **Localized grass in channel needs to be removed.**



Pt. 149 – (Sta 19+00) – **Finger drain blocked at this location and needs to be cleaned out.**



Pt. 150 – Build-up of grass and debris in channel, (restriction of flow through channel). **Debris/grass needs to be cleaned out of channel**



**CONFIDENTIAL BUSINESS
INFORMATION**

Storage Pond Main Dike/Spillway

Pt. 151 – Localized minor vegetation observed at floor of spillway. **Remove vegetation from weephole and other various locations in the spillway floor.**



Sta. 37+50 – Progressive undermining of concrete paving. **Requires repair to mitigate further ground loss and future damage to pavement. (See attached Sketch No. 1 below for proposed repair option)**



Pt 152 (Sta. 68+00) –Bare spots in slope
Localized re-seeding to re-establish grass cover.




Pt 153 – Animal burrow just upslope from concrete drainage channel (approx Sta. 68+00). **Requires repair/filled in.**



CONFIDENTIAL BUSINESS
INFORMATION

Pt 154 – Stockpiles of emergency coarse and fine aggregate drainage materials looks good



Separator Dike

Upstream slope generally looks satisfactory although surface runoff is causing localized erosion near top of slope.

Localized re-grading required to flatten over steepened upper portion of slope and to provide positive drainage to minimize over-slope flows (which will result in progressive erosion along slope)

CONFIDENTIAL BUSINESS
INFORMATION



Crest of Upstream Slope - Localized erosion rill needs to be repaired with #57 stone.



Potable Water Pond Dike

Localized bare spots on slope. Repair either by re-seeding to re-establish grass cover or place small rip-rap/stone).

(See Updated Status from Third Quarter Report –Location 092, for items to be completed)



Vegetation growth at toe of upstream slope. Cut down and remove vegetation (grass/bushes)

(See Updated Status from Third Quarter Report – Location 089, for items to be completed).



**CONFIDENTIAL BUSINESS
INFORMATION**

Ash Pond Emergency Overflow

Repair of downstream outfall completed

(See Updated Status from Third Quarter Report – 094).



Rip-rap on upstream and downstream slopes overall looks good. No evidence of recent erosion or instability. Brush has been cleared since 3rd Quarter 2007.

(See Updated Status from Third Quarter Report – Location 095, for items to be completed).



Detention Pond

Vegetation on downstream slope.
**Remove/cut down
vegetation/brush/small trees for a
distance of 30 ft. out from toe of slope.**

(See Updated Status from Third Quarter Report – Location 099, for items to be completed).



CONFIDENTIAL BUSINESS
INFORMATION

Tree and brush adjacent to spillway should be cleared.

(See Updated Status from Third Quarter Report – Location 100, for items to be completed).



UPDATED STATUS (Reference - 3rd Quarter Report dated October 27, 2007)

073 The cleanout pipes for the subsurface drain at Sta 69+00 do not have covers on them. **These pipes should be covered.**

3-10-08 – Pipes capped



075 The stockpile of granular material west of the makeup water pump station appears to have gotten smaller than it should be. **It would be a good idea to add one load of sand, one load of #89 stone and two loads of #57 stone.**

3-10-08 – No Change



062 At the paved ditch at the toe of the maximum section of the storage pond dike, the slopes of the ditch have become overgrown with tall weeds and woody brush. **This vegetation should be cleared or poisoned.**

3-10-08 - Brush cleared



062 The brush growing up between the steps has also made walking on the stairs to the relief well flow measurement platform hazardous. **This brush should be removed. The weir in the paved ditch at this location is clogged with silt and should be cleaned out.**

3-10-08 - Brush cleared



CONFIDENTIAL BUSINESS
INFORMATION

066 An animal burrow was noted next to the paved ditch at Sta 45+00. There is some woody brush in this area that should also be cut. Brush and tall grass provide cover for burrowing animals and therefore encourage their burrowing. **The animal should be trapped or gassed and the burrow should be packed with gravel and/or foamed. The brush should be cleared.**

3-10-08 – Brush cleared but burrow still observed



068 The toe of the dike at Sta 37+50 was very boggy as usual. In May, Hydro Services had Dr. Rene Rodriguez conduct geophysical testing of this area to try to determine the flow path of the water. Dr. Rodriguez' results and a drawing of the finger drain system correlate to indicate that the source of the water may be a buried finger drain with no outlet to the surface. **Hydro Services will work with plant management to plan an exploration of this area with the aim of locating the buried drain and installing a pipe to provide relief to this groundwater.**

069 The weir at Sta 37+50 is silted up and should be cleared so that it can be read properly.

3-10-08 – Weir cleared of silt

070 The emergency granular material stockpiles at Sta 37+50 are overgrown with weeds and brush. This vegetation might hinder access to the materials in an emergency. **The stockpiles should be sprayed to kill the weeds.**

3-10-08 – weeds and grass cleared. Sand and stone replenished, but need another load of #89 stone



077 The stoplogs for the spillway are stored on the dike adjacent to the spillway sitting on some timbers. The skin side of the stoplogs is down, allowing rainwater to stand in the stoplog. This causes corrosion and shortens the life of the stoplogs. It would be a good idea to examine the stoplogs for loss of section due to corrosion, repair and paint them if necessary, **and store them skin side up to reduce the potential for corrosion.** **3-10-08 – Unchanged**



**CONFIDENTIAL BUSINESS
INFORMATION**

Storage Pond – East Dike

081 There are some small trees and woody brush growing at the heel (upstream) of the east dike at this point. **This vegetation should be cut or poisoned.** (about Sta 7+00?)

3-10-08 – Vegetation cleared



082 Tall grass and woody brush are growing on both sides of the paved ditch at the toe of the east dike from Sta 5+00 to Sta 20+00. **This vegetation should be cut down.**

3-10-08 – Vegetation cleared



083 The granular material stockpiles downstream of the east dike have become overgrown with weeds. The sand will not be useable due to roots. **The stockpile should be sprayed with poison and a load of sand added.** (about Sta 10+00)


3-10-08 – Vegetation removed and stone added to stockpile



**CONFIDENTIAL BUSINESS
INFORMATION**

Potable Water Pond Dike

3-10-08 - Brush cleared downstream of the dike but brush needs to be cleared on upstream toe of slope



089 An eroded area was noted on the downstream slope just east of the spillway. This appears to be the result of runoff from the roadway passing through the riprap and running down this area instead of into the adjacent paved ditch. It would be a good idea to add some rock to the eroded area to protect it from further erosion and to add some rock to the riprap at the top of the slope to try to direct the runoff into the existing paved ditch. There are also some small trees growing in this area. These should be cut or poisoned.

3-10-08 – Trees and bushes removed and gravel placed in rip rap. Some additional rock required to cover bare spots



CONFIDENTIAL BUSINESS
INFORMATION

091 On the downstream side of the dike there is a growth of tall grass and woody brush along the east and west contacts of the dike with the natural ground. **This vegetation should be cut or poisoned. 3-10-08 – Brush cleared at both locations**




092 The upstream slope of the dike is rip rapped. There is a fair amount of grass growing in the riprap. **This grass should be poisoned.** There is a stand of brush along the upstream edge of the dike. **This brush should be removed.**

3-10-08 – No work yet.



Ash Pond Emergency Overflow



094 The downstream outfall for the paved ditch has been undermined. Storm flows from the ditch undermine the ditch liner and will eventually remove the soil supporting the end of the ditch liner causing the liner to fail. **This area should be reinforced by placing Type I riprap in the pond at the outfall and choking that with Type III riprap. See sketch below.**

3-10-08 – Work completed



CONFIDENTIAL BUSINESS
INFORMATION

095 The upstream spillway of the paved ditch has been repaired with Type III riprap, but **the riprap needs to be dressed to match the contours of the paved ditch**. The current layout could result in uneven flows over the riprap and subsequent erosion

3-10-08 – No change



096 There is woody brush growing on the east end of the dike on the downstream side. **This brush should be cut or poisoned.**

3-10-08 – Brush has been cut



There is a bare spot adjacent to paved ditch near the location noted above. **This area should be armored with Type III riprap on a 4" bed of #57 stone.** **3-10-08 – Still required**



098 There is woody brush growing in various locations around the perimeter of the pond on the downstream side of the skimmer wall. This brush could make recovery efforts difficult in the event of an oil spill to the ash pond. **This brush should be cut or poisoned.** **3-10-08 – Brush cleared**



**CONFIDENTIAL BUSINESS
INFORMATION**

Detention Pond


099 The tall grass and small trees growing on the downstream side of the dike should be cut for a distance of 30 feet out from the toe. **3-10-08 – No work yet.**

100 The tree and brush growing adjacent to the edge of the spillway should be cleared. **3-10-08 – No work yet.**




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 20+00




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Pz's at Sta. 37+50-1




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Pz's at Sta. 37+50-2




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Pipe Flows




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 47+50




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 58+00




CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Well Flows




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 65+00




CONFIDENTIAL BUSINESS
INFORMATION

Wansley Storage Pond Pz's at Sta. 70+00



CONFIDENTIAL BUSINESS
INFORMATION


Plant Wansley Weir and Pipe Flows



MAINELEV 11+20 49+00


CONFIDENTIAL BUSINESS INFORMATION

Wansley Separation Dike Pz's BB and DD



CONFIDENTIAL BUSINESS
INFORMATION

Plant Wansley Potable Pond Piezometers



CONFIDENTIAL BUSINESS
INFORMATION

P L A N T W A N S L E Y

EARTH EMBANKMENTS

FINAL REPORT

AND

APPENDICES

GEORGIA POWER COMPANY
CIVIL ENGINEERING DEPARTMENT

MAY, 1975

WAN-API 035

CONFIDENTIAL BUSINESS
INFORMATION

TABLE OF CONTENTS

Introduction

Construction History

Construction Materials

Embankments

East Dike

Storage Pond Dike

Separation Dike

Potable Water Supply Dam

Summary

CONFIDENTIAL BUSINESS
INFORMATION

A P P E N D I C E S

VOLUME 1

| | |
|--------------|--|
| Appendix I | Compilation of Preliminary Reports and Investigations |
| Appendix II | Procedures for Quality Control |
| Appendix III | Designation of Quality Control Responsibility |
| Appendix IV | East Dike Daily Inspection Progress Reports |
| Appendix V | Storage Pond Dike, Separation Dam, Potable Water Supply Dam, Soils Reports |

VOLUME 2

| | |
|------------|---------------------------------------|
| Appendix A | East Dike, Compaction Reports |
| Appendix B | Storage Pond Dike, Compaction Reports |

VOLUME 3

| | |
|------------|--|
| Appendix C | Separation Dike, Compaction Reports |
| Appendix D | Potable Water Supply Dam, Compaction Reports |

CONFIDENTIAL BUSINESS
INFORMATION

INTRODUCTION

The following narrative and attached appendices are in response to letter, Southern Services, dated February 27, 1975, requesting a compilation of design and construction data for the earth dams at Plant Wansley. Specifically, the letter requested information on the following:

- a. Dam construction history.
- b. Identification of borrow pits used for various portions of the dam.
- c. Field compaction control and results summary.
- d. Sources of riprap, filter material.
- e. Identification of all Georgia Power Company, Law Engineering and Contractor personnel who inspected or supervised the work with the dates of their involvement.

Detailed studies on all of the earth dam portions of the project are on file with Southern Services, and are listed by date and title in Appendix I. The plans and specifications for the project, including the as-built drawings, are also available. The narrative report will therefore be relatively brief, but will be supported by the specific reports and detailed studies made throughout the design and construction period either by reference or in appendices. The appendices also contain daily and weekly reports, and field control data, if reference to these details should ever be required.

The information in the report was assembled by T.B. Chaudhary in the form of a preliminary document. It was reviewed and revised in the Civil Engineering Department of Georgia Power Company. In accord with the items "a" through "e" above, the report initially discusses the general construction history, including the personnel involved in the construction, inspection and supervision of the dam and dikes. Subsequent sections describe in more detail the construction of the various dike or dam segments. The data on compaction control and test results for each segment is appended, as well as selected photographs taken during

earthwork construction. Special paragraphs on stone protection, which comprised an important part of the dike construction, are included.

CONSTRUCTION HISTORY

Field supervision of the project for Georgia Power Company throughout the construction period was under the direction of Mr. C.B. Head, Project Superintendent, and Mr. R.S. Ponsell, Civil Supervisor.

In early spring of 1972, Georgia Power Company selected Southland Constructors, Inc., as contractor for all grading work, including the dike and dam construction. Mr. Simpson Faulkner, President of Southland, was in charge of the Southland work until the end of January 1975, when he was replaced by Mr. Bobby Slaughter.

The survey work was initially done by Riley-Park-Hayden, who were later replaced by a Georgia Power Company survey group.

Law Engineering Testing Company was selected to provide a quality control program to assure that the grading work was performed in accordance with the plans and specifications, and to report any situation requiring special engineering attention. They assigned Mr. Michael R. Turner as Project Site Engineer to oversee all grading work. A team of soil technicians, including Law Engineering Testing Company and Georgia Power Company employees, was organized to observe and test the compaction of all fill work under the direction of Mr. Turner.

On May 1, 1972, the first compaction test strips were placed to evaluate the performance of the compaction equipment proposed to be used for the grading work. Law and Georgia Power Company's project construction group formulated procedures for Quality Control during fill placement for the dike construction (refer to Appendix #2). The procedure required that all phases of dike construction be witnessed by the civil group or their consultants.

On September 19, 1972, the contractor started stripping operations for the East Dike between Stations 0+00 and 22+00. Mr. Edward O. Prescott, Soils

CONFIDENTIAL BUSINESS
INFORMATION

Engineer, Law Engineering Testing Company, was assigned to the project on September 25, 1972, to assist Mr. Turner, and to be responsible for the East Dike construction inspection. Mr. Prescott remained at the site until December 5, 1972 when construction of the East Dike was suspended because of inclement weather. When the work resumed on February 20, 1973, Mr. Jay Budde, Soils Engineer, LETCo, assumed Mr. Prescott's responsibilities. Mr. Budde remained on the site until March 5, 1973.

On February 23, 1973, Mr. Beadles of LETCo met with Messrs. Ponsell and Edwards of Georgia Power. As a result of this meeting, Mr. Charles Edwards of Georgia Power was assigned to assume the responsibilities of earth construction inspection and testing. Mr. Turner assisted Mr. Edwards until he became familiar with the inspection and testing operations. Mr. T.B. Chaudhary of LETCo was designated to provide consultation to Mr. Edwards on an as-requested basis. These changes of engineering and inspection responsibilities are summarized in letters of confirmation dated March 1 and March 15, 1973 (Appendix #3). Under Mr. Edwards' supervision, the Separation and Storage Pond Dikes were partially completed, and the major portion of preparation and cleaning of the Potable Water Dam abutments was done.

Mr. Edwards requested assistance during a part of the foundation preparation for the Separation Dike. Mr. Thomas L. Cross (from June 5 to June 29, 1973) and Mr. David Bourne (from July 2 to August 17, 1973), both of LETCo, assisted Mr. Edwards during this phase of inspection. Mr. Edwards resigned from the Georgia Power Company on February 21, 1974. Mr. T.B. Chaudhary assumed the engineering inspection responsibilities for the remaining earth work related construction.

CONFIDENTIAL BUSINESS
INFORMATION

During this assignment, the Separation Dike was completed. Yellowdirt Creek was diverted for Potable Water Supply Dam construction, and the Potable Water Supply Dam was completed. Mr. Chaudhary was re-assigned on April 18, 1975, and the last section of the Storage Pond Dike, between Stations 50 and 70, was completed under the supervision of Georgia Power personnel.

CONSTRUCTION MATERIALS

Prior to and concurrent with construction, extensive explorations were conducted to identify and classify the soil and rock materials to be used for embankment construction. Reports for each of these detailed investigations are on file and are listed in Appendix I.

In brief, the site geology and soil profile are typical of much of the Southeastern Piedmont. The plant area and embankments are entirely within the Brevard Zone, which is a pronounced geologic lineament of deformed rocks extending from Alabama northeastward into North Carolina. The rocks at the site are biotite gneisses and schists, typically striking northeast with a southeast dip. Where sound and unweathered, they are highly competent, but because of pronounced foliation, they break into flat particles when excavated and crushed. However, this characteristic is not sufficiently detrimental to prevent the rock from being entirely adequate for riprap, bedding material, sub-ballast, and road base. It was not used for concrete aggregate.

Upland soils throughout the site are residual from in-place weathering of the underlying parent rock. These soils were used in the construction of the dikes and dams, and are generally sandy, micaceous, silts and silty, micaceous, fine sand. The upper layer, however, was more clayey because of advanced weathering of the minerals, and is generally described as red-brown, sandy, silty, clay or sandy, clayey silts.

CONFIDENTIAL BUSINESS
INFORMATION

In the valleys of the streams and smaller drainage features, alluvial soils cover the valley floors. These are primarily silts and fine sands, with pockets of soft, organic muck soils which required removal before placing embankments. They were not used for embankment fills.

Sources for embankment materials were explored prior to construction and are described in detail in appropriate reports (Appendix I). The location and approximate available yards in each area are shown on Drawing H-10061 and on the respective contract drawings. As more than one borrow area might be used at one time for several portions of the dam work, it is not reasonable to attempt to identify each portion of the embankments with a definite elevation of a specific borrow area. However, the daily and weekly reports for each of the structures identify the borrow areas and embankment stations being placed at the time of the report, and the source of the material at any station or elevation could be determined from these reports if necessary (Appendices IV and V). Air photos taken during construction are also helpful in identifying the borrow areas.

The residual soils from the borrow areas produced exceptionally fine embankments. Little difficulty was encountered in securing the required 100% compaction, with densities averaging 100 to 110 lbs. per cu.ft. (See test reports, Appendices A through D). The strength of the material was demonstrated in several instances where trenches for drains were excavated with a backhoe, producing dense, vertical, soil walls. Laboratory tests made on soil samples taken from the embankment indicated strengths and permeabilities equal to or exceeding the design parameters (Appendix I, Reports 62 and 63).

Stone slope protection in the form of riprap and bedding material represented a substantial part of the cost of the embankment construction, and every attempt was made to secure the necessary rock from the site with a minimum of haul distance. Grading for the plant site required considerable excavation below top of sound rock, and the blasted gneiss was stockpiled for later use

as riprap. Although the foliation of the gneiss produced blasted rock with a tendency toward flat particles, this feature was not sufficiently serious to effect its suitability for stone embankment protection. The blasted rock was stockpiled at the plant site after excavation until it was needed as riprap. Generally, the rock was reasonably well graded, and when placed on the embankment it was entirely satisfactory for embankment protection. The occasional stones which were too large for the specified riprap sizes were broken at the stockpile by a drop ball.

All riprap for the separation dike, and a portion of that required for the storage pond dam, was secured from the excavation stockpile. This supply was eventually depleted, and a quarry was opened in the storage pond area to provide the remainder of the rock needed for the storage pond dikes. All rock for the potable water supply dam was secured from a quarry opened for that purpose between the embankment and the spillway.

Bedding material between the embankment soil and the riprap layer was manufactured by crushing rock secured from site grading. The 3/8 inch crusher run material was mixed with 25% off-site white sand to produce a blend which was satisfactory with respect to gradation requirements. Riprap and bedding were placed on the dikes as follows:

Separation Dike, Pool Side:

- a. Three feet of riprap on 1 foot of bedding up to elevation 745.
- b. Two feet of riprap, without bedding, from elevation 745 to elevation 780.
- c. Two feet of riprap on 1 foot of bedding from elevation 780 to top of embankment.

Separation Dike, Ash pond Side:

Two feet of riprap from 775 berm to top of embankment. Bedding material (12") from El. 790 to top. No rock protection below El. 775.

CONFIDENTIAL BUSINESS
INFORMATION

X

Potable Water Supply Dam:

Potable Water Side - 24" riprap with no bedding to El. 795. From El. 795 to top 24" riprap on 12" of bedding.

Storage Pond Side - 24" riprap with no bedding to El. 780. From El. 780 to top 24" riprap on 12" of bedding.

Storage Pond Dam:

All embankment protected by 2 feet of riprap with 1 foot of bedding above El. 780. Areas of natural ground between embankment sections not protected.

On most embankment projects it is difficult to secure compaction at the edge of each compacted lift. When riprap and bedding is placed against such uncompacted material, and saturation occurs after the pool is impounded, slumping occurs which is often mistakenly attributed to riprap failure. On the Wansley embankments this was avoided by overbuilding the fill and then removing the loose exterior soil with a Gradall. Bedding material and riprap were then placed by building the embankment about 12 feet above the previously placed riprap; dumping the stone on top of the embankment; and placing the required bedding and riprap with the Gradall. This procedure resulted in a dense, well graded rock mass without underlying loose embankment fill.

By planned use of available site materials, adequate rock protection for the Wansley embankments has been secured at minimum cost.

EMBANKMENTS

East Dike - The Storage Pond Dike from Stations 0 through 22 is referred to as the East Dike. Construction started on September 19, 1972, with stripping of the entire dike section and additional undercutting of soft material between Station 9+00 and 20+00 prior to proof rolling the foundation subgrade. Mr. Turner witnessed the proof rolling operation prior to fill placement. In conformance with the construction procedures, a LETCo engineer, Mr. Prescott, was assigned the responsibility of construction inspection of the East Dike, starting September 25, 1972.

CONFIDENTIAL BUSINESS
INFORMATION

On September 22, 1972, it was discovered that the upstream face of the dike was constructed on a 2(H):1(V) slope rather than 3:1, as specified. The contractor was directed to correct the slopes by benching in the addition width of the dike. (Appendix IV).

Excavation for the longitudinal drain between Station 7+50 and 9+50 was started on September 22. Initially, vertical sand drains (18" in diameter) were installed from Stations 7+65 through 11+65. Each drain was advanced to the natural ground and backfilled with concrete sand densified using concrete vibrators. After installation of the vertical drains, the specified longitudinal drains were constructed using a #57 stone core encased in one foot of concrete sand. All vertical, longitudinal, and transverse drains were constructed in this manner according to the specifications. To determine the effectiveness of the internal drains, a flow test was conducted on October 11, 1972. Water poured into the longitudinal drain at Station 17+10 started flowing through the transverse drain at Station 16+15, indicating that the drain was operational and effective (Appendix IV).

Because of inclement weather, construction of the East Dike was suspended on December 6, 1972. When work resumed on February 20, 1973, Mr. Prescott was replaced by Mr. Budde. With the exception of bedding and riprap placement on the upstream face, the dike was essentially completed by March 5, 1973. The bedding (1 foot thick) and riprap (2 feet thick) was placed in December 1974 and January 1975. This work was done according to the plans and specifications.

Detailed daily inspection reports for the East Dike are included in the "Dike Construction Progress Report," Appendix IV. The compaction test reports are attached as Appendix A.

Storage Pond Dike - The dike between Stations 22 and 110 was referred to during construction as Storage Pond Dike. The main fill embankment extends from Station 33 to Station 85. The section from Station 85 to 110 is primarily cut, and low embankment extends from Stations 95 and 98, and from Stations 105

to 108. Rock was blasted to obtain the specified elevation between Station 85 and 98 and from 109 to 110.

A cofferdam was constructed from Stations 60 to 70 and Yellowdirt Creek was diverted through the minor diversion ditch shown on Plan H-12350. Subsequently, the major diversion ditch was excavated. Presplit rock blasting techniques were required through the ridge for this excavation. The foundation was then cleaned and leveling concrete fill placed to the specified pipe invert elevation. Daniel Construction Company installed the twin steel pipe culverts and encased them in structural concrete. The north end of the twin steel pipes was extended with corrugated metal pipes. After diversion culverts were completed, Yellowdirt Creek was diverted through the pipes.

To facilitate dewatering of the remaining dike foundation at this location, several ditches were excavated and water pumped from a sump located at the south end of the dike. For dewatering the west side of the culvert, another sump was maintained to the left of the major diversion ditch. All alluvial soil (consisting of clay, sand, and gravel) was removed to rock beneath the entire dike foundation. After satisfactory clean-up of the foundation, select silty clay was used to start the embankment. The first layer of the fill was rolled with a pneumatic tire roller to obtain better compaction on the uneven rock surface.

Fill placement proceeded satisfactorily and all internal vertical, longitudinal and transverse drains were installed according to plan (except as noted below) using sand purchased from T&L Company and rock manufactured at the site. The elevations of the longitudinal and transverse drain between Stations 54 and 70 were changed by Georgia Power Company's survey group. The actual elevation changes were noted on the plan and forwarded to Southern Services.

Daily compaction reports for the Storage Pond Dike are attached as Appendix B.

CONFIDENTIAL BUSINESS
INFORMATION

Separation Dike - Detailed exploration and design studies for the Separation Dike are contained in Communication No. 39, Appendix I. The diversion scheme and construction drawings are shown on Dwgs. H-12364 through H-12366, and Dwgs. H-12396 through H-12398.

The plans required the removal of all alluvial soils and all sand and gravel from the core area, and the removal of the alluvial material only from under the balance of the embankment. Initial work on stripping began on May 17, 1973, and details of the construction of the embankment are contained in the reports shown in Appendix V. In brief, a 48-inch corrugated metal pipe was installed for diversion of the creek. The upstream portion of the embankment, Stage 1, was constructed, after stripping, to El. 745. The core area in the flood plain was then undercut to weathered rock, and fill was compacted onto the inspected rock surface. Drainage was accomplished with open ditches and pumping from sumps. The location of the ditches and sumps are shown on report dated September 14, 1973, Appendix V.

Soils used for embankment fill were lean clays and silts obtained from borrow areas as described in the weekly reports (Appendix V) and compaction reports (Appendix C). Unit weights average 100 to 110 lbs per cu.ft., and 100% density was obtained. During September and October, 1973, sandy material was encountered in the borrow areas. Samples of the material was placed in the dike were obtained, and laboratory tests were conducted. The results showed the materials to be satisfactory with respect to design parameters (Communications 62 and 63, Appendix I).

On May 2, 1974, a dam was constructed to stop the water flow through the diversion pipe and both ends of the pipe were plugged with approximately 8 feet of concrete. The foundations for the balance of the dike were prepared, and fill

CONFIDENTIAL BUSINESS
INFORMATION

placement continued. The procedures for tying in the second stage construction with the first stage dike are described in letter dated September 28, 1973, Appendix V. The horizontal drainage blankets shown on Dwg. H-12365 were constructed, using at first sand from Yellowdirt Creek, later supplemented by sand purchased from T&L Company of Whitesburg, Georgia.

Stone protection was placed on the embankment as described in the preceeding section of this report under "Construction Materials."

Potable Water Supply Dam - Details of the exploration and design for the Potable Water Supply Dam are described in Communications Nos. 43,44,46,47, and 53. Initial stripping began during the first week of November 1973 under the field supervision of Charles Edwards. Excavation of the valley section and the abutments was generally according to Dwg. H-12352, except that over-excavation of the east abutment produced a near vertical face from top of rock at about elevation 740 to overburden at 780. This face was later dressed back as the embankment was placed to produce a sloping contact between the fill and the weathered rock abutment (see attached photos).

Both abutments contained rock outcrops which would have prevented proper compaction of the embankment fill. These were blasted with light charges during foundation preparation to permit proper compaction of the fill against the abutment.

The 72" concrete pipe which will provide permanent control of the Potable Water Supply Pond was used for diversion of the creek (Dwg. H-12356). To control the stream flow during construction of the concrete pipe, the contractor constructed a wooden wall parallel to the stream channel. Holes 8" in diameter were drilled on about 10' centers for anchoring vertical wooden posts.

CONFIDENTIAL BUSINESS
INFORMATION

Tongue and groove joint laggings were then installed between the posts and anchored with sand bags. The creek was diverted to the east side of the wall, providing a fairly dry area for the construction of the concrete pipe. (See attached photographs for diversion details.)

All sand and gravel, alluvium, and broken rock debris were removed from the pipe foundation and fill concrete placed to the specified elevation. After completion of the foundation work, the concrete pipe was installed and the lower half encased in concrete. Daniel Construction Company then built the north and south head walls and apron. The water was diverted through the pipe and a cofferdam constructed at the north end of the proposed dam to obtain a dry working area on both sides of the pipe.

The west side of the pipe area was cleaned first. Concrete was placed in any narrow slots in the foundation rock to facilitate the initial fill compaction. The first layer of embankment was selected clayey material compacted with pneumatic tired equipment. The fill was placed to the level of the top of the pipe. The east side of the pipe was then cleaned, leveled and similarly filled. When the embankment level reached the vertical cut described previously, the bank was sloped to allow better fill compaction and bond to the abutment.

The sand plug and sand-gravel drains were installed on both sides of the concrete pipe according to Dwg. H-12356. All upstream and downstream horizontal sand blankets were installed as specified with sand purchased from T&L Company. Stone protection for both upstream and downstream embankment slopes was 12" of bedding material and 24" of riprap. The bedding material was manufactured from the stockpile stone, and riprap stone was secured from a quarry opened for that purpose west of the embankment.

Southland Power Constructors excavated the spillway channel, the lower end of which required blasting of rock to obtain the specified elevation. The spillway structure itself was built by Daniel Construction Company.

CONFIDENTIAL BUSINESS
INFORMATION

SUMMARY

The material contained in this report is intended to briefly furnish information on the personnel who supervised the inspection of the embankments, together with sufficient data to permit identification of the reports which are available for all portions of the project. If it should ever become necessary to review the construction details of any part of the embankment, the proper field inspection report contained in these appendices, together with the project plans and the appropriate portions of the specifications, should be sufficient to identify the records and the procedures used for that part of the project.

Dam embankments constructed of compacted Piedmont soils on properly prepared Piedmont foundations have an excellent performance record. The Wansley foundations are strong and relatively impervious, and the residual Piedmont soils, properly compacted, make excellent embankment fill. The Wansley embankments were conservatively designed, with adequate provisions for foundation and embankment drainage, and with heavy riprap protection against wave action. There is no feature of the construction which should ever be a cause for concern. However, if it should become necessary at some future date to investigate a feature or area of the work, the design studies and the plans and specifications, together with the construction records contained herein, should be adequate for determination of the problem and to indicate any necessary remedial work.

CONFIDENTIAL BUSINESS
INFORMATION

**CONFIDENTIAL BUSINESS
INFORMATION**



11 App. II
sh

LAW ENGINEERING TESTING COMPANY

Geotechnical and Materials Engineers

412 PLASTERS AVENUE, N.E. / ATLANTA, GEORGIA 30324 / (404) 873-4761

PROCEDURES FOR QUALITY CONTROL DURING FILL PLACEMENT FOR DIKE CONSTRUCTION

GENERAL

(1) All phases of dike construction will be witnessed by the civil group or their consultants to verify that the specifications and design drawings are adhered to and to verify that conditions in the field are similar to those upon which the designs were based. No changes in the specifications or designs will be made without prior approval of the design group of Georgia Power Co.

(2) A soil technician will be assigned to specific areas of dike construction on a full-time basis to carry out the work as prescribed in this procedure.

Note: The contractor must notify the soils technician in advance of his initiating any work in areas of dike construction.

(3) The soil technician and site soil engineer will have authority to stop all dike construction in a given area if the design specifications and drawings are not being followed.

FILL CONTROL

(4) All areas to receive fill will be thoroughly inspected by the site soils engineer to verify that adequate stripping of topsoil and organic debris is performed.

(5) During filling, the earth moving operations will be continuously monitored visually and with testing to verify that proper soils are being utilized and that adequate compaction is being achieved.

(6) At least one (1) density test will be made for each approximate 1500 yards of fill placed.

(7) The nuclear density gage shall be utilized in monitoring the in-place density of the fill material. However, approximately twenty percent of tests made with the nuclear device will be verified by conventional sand cone or Shelby tube methods, as described in the Quality Assurance Manual.

- (8) If the dry density obtained by the nuclear gage method varies by more than 4 lbs. from that of the conventional method, an additional conventional test will be made. The average density of the two (2) conventional method tests will then be compared with the average of the previous five (5) tests with the nuclear gage on that particular fill lift. If the average densities obtained by this procedure vary by less than 4 lbs., the tests will be considered valid. If they vary by more than 4 lbs. the site soils engineer will be consulted as to need for further testing of the suitability of the fill.
- (9) Generally, the density as determined by the nuclear density gage will be that which will be compared with the compaction curves for determination of suitability of compaction.
- (10) The density of the fill will be considered failing if a degree of compaction of less than 100 percent of the Standard Proctor Maximum dry density is obtained. Additional densification of the fill will be required if less than 100 percent is obtained.

INTERNAL DRAINS

- (11) The construction of the internal drains shall be continuously observed by a soils engineer from the civil group to verify that the drain locations are as required and that proper thicknesses of the required materials are installed.
- (12) The materials in the drains shall be compacted to the suitability of the soils engineer.
- (13) Fine aggregate and coarse aggregates being utilized in drain construction will be tested each day to verify that their gradation is in compliance with the design requirements.
- (14) On an occasional basis, the soils engineer will inject water into the drains prior to their being covered with fill to verify that they will perform satisfactorily.

RIP-RAP PLACEMENT

- (15) The installation of rip-rap will be continuously observed by an engineer or technician from the soil group.
- (16) He will verify that the required thicknesses of both the cushion blanket of fine stone and outer layer of armor stone are placed.
- (17) The cushion blanket material will be tested daily to verify that its gradation is in compliance with the specifications.
- (18) The armor stone will be visually inspected and volume measurements of pieces made to verify that its general gradation and maximum stone size are in compliance with the specifications.

QUALITY CONTROL

YELLOW RIVER STEAM PROJECT

CIVIL *ASP*

EXEC

MEAS.



From App. V.
gh

September 28, 1973

Mr. G. B. Dougherty
Southern Services Inc.
P. O. Box 2625
Birmingham, Alabama 35202

Subject: Borrow Material And Construction Procedures
For The Plant Wansley Separation Dam

Dear Mr. Dougherty:

After encountering low density borrow material (90 to 95 pounds per cubic foot dry density) and very sandy material, we decided that additional testing was needed. A two-foot lift of the sandy material was placed on the upstream edge of the separation dam. Six undisturbed samples were obtained on September 27. These samples were sent to Law Engineering Testing Company for triaxial testing.

As soon as the weather permits, a two-foot lift of the low density material will be placed. This test lift will only cover an area sufficiently large enough to obtain the same compactive effort as is applied to large fill areas. We will obtain six more undisturbed samples for triaxial testing. Until we obtain the test results and your written approval, this low density material will only be placed in one six-inch lift per ten feet of fill. No additional sandy material will be used until we get your written approval.

All triaxial test results and all in-place density test results on the separation dam will be forwarded to you. After the results of these triaxial tests are obtained, we will decide on a definite schedule of triaxial testing. We plan to obtain five additional undisturbed samples of the normal specified fill material for triaxial testing as soon as filling resumes on the separation dam.

As to your question on tying the Stage I Construction to the remaining fill, we plan to continuously bench into the sloping fill. We will have a dozer cut into the existing fill until we obtain material that has the specified density as verified by in-place density tests. Close observation is provided by me and the field technicians to assure that this operation is performed correctly. It is simple to visualize that a proper benching operation requires that, at all times, the compacted material into which the horizontal bench is cut must be showing on the vertical portion of the bench cut.

CONFIDENTIAL BUSINESS
INFORMATION

Mr. G. B. Dougherty -- 9-28-73

When tying the fill to the existing abutments, several procedures are used. Steep abutments are cut back as much as possible. The existing natural ground is scarified completely before fill placement starts. The abutment is benched, if necessary. The rollers continuously run from the fill material onto the abutment. Since the sheeps foot or grid roller leaves the upper six inches of the compacted fill in a loose state, successive layers are fused together in a continual process, insuring an excellent seal between the existing abutment and the placed fill.

Yours very truly,

GEORGIA POWER COMPANY

Charles A. Edwards
Senior Engineering Associate

CAE:esv

cc: Mr. R. S. Ponsell
Mr. Don Foster
Quality Assurance File ✓

GEORGIA POWER COMPANY -- SOILS
NUCLEAR DENSITY METER WORK SHEET

FROM APPC 2-5-76

PROJECT: LUMASLEY
JOB NO.: SEPRDTH
AREA: WIGHT SHED

DATE: 10/13
DENSITY STANDARD COUNT: 221
MOISTURE STANDARD COUNT: 1111

| | | | | | | | | |
|-----------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 432 | 444 | 436 | 437 | 432 | 478 | 436 | 426 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 127.0 | 125.5 | 126.5 | 126.5 | 127.0 | 127.5 | 126.5 | 128.0 |
| (F) Moist Count | 1260 | 1208 | 1224 | 1224 | 1264 | 1248 | 1222 | 1222 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 25.4 | 24.2 | 24.6 | 24.8 | 25.4 | 25.2 | 24.6 | 25.2 |
| (I) Dry Wt. | 101.6 | 101.3 | 101.9 | 101.7 | 101.6 | 101.3 | 101.9 | 103.0 |
| (J) Proctor Wt. | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 18+00 | 18+70 | 20+00 | 20+00 | 20+00 | 20+00 | 20+00 | 20+00 |
| (O) Elev. | 744 | 745 | 749 | 750 | 753 | 754 | 754 | 755 |

CONFIDENTIAL BUSINESS
INFORMATION

Compaction Required 116.4

Technician UD 7

PROJECT: WANSLEY

JOB NO.: 231

AREA: SEPARATION DAM

DATE: OCT 4, 1973

DENSITY STANDARD COUNT: 231

MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|------------------|------------------|------------------|------------------|------------------|--|--|--|
| (A) Test Number | 1A | 2A | 3A | 4A | 5A | | | |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 408 | 406 | 392 | 416 | 396 | | | |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 130.0 | 130.2 | 132.0 | 129.0 | 131.5 | | | |
| (F) Moist Count | 1130 | 990 | 980 | 1060 | 1060 | | | |
| (G) F ÷ Std Count | 22.4 | 19.1 | 18.9 | 20.8 | 20.8 | | | |
| (H) Wt. Moist (lbs) | | | | | | | | |
| (I) Dry Wt. | 107.6 | 111.1 | 113.1 | 108.2 | 110.7 | | | |
| (J) Proctor Wt. | | | | | | | | |
| (K) % Comp. I ÷ J | | | | | | | | |
| (L) % Moist | | | | | | | | |
| (N) Location | 5+00 150' L & | 4+25 135' L & | 3+25 135' L & | 3+00 160' L & | 3+75 160' L & | | | |
| (O) Elev. | 759 | 762 | 767 | 768 | 767 | | | |

FOR TRIAXIAL TESTING

Compaction Required _____

CONFIDENTIAL BUSINESS
INFORMATION

Technician

M. K

DATE: 10-7-55
DENSITY STANDARD COUNT:
MOISTURE STANDARD COUNT:

| | | | | | | | | |
|-----------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 422 | 216 | 225 | 238 | 412 | 414 | 424 | 402 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 128.5 | 129.0 | 127.5 | 130.0 | 129.5 | 127.5 | 128.0 | 130.0 |
| (F) Moist Count | 1134 | 1096 | 988 | 1117 | 1084 | 1088 | 1108 | 1090 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 22.2 | 21.5 | 19.1 | 22.0 | 21.0 | 21.0 | 21.0 | 21.0 |
| (I) Dry Wt. | 101.1 | 107.5 | 108.4 | 108.0 | 108.2 | 108.0 | 108.0 | 108.2 |
| (J) Proctor Wt. | 101.1 | 107.5 | 108.4 | 108.0 | 108.2 | 108.0 | 108.0 | 108.2 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 2440 | 2450 | 2445 | 2448 | 2442 | 2442 | 2441 | 2441 |
| (O) Elev. | 746 | 747 | 746 | 745 | 746 | 747 | 746 | 747 |

10090

**CONFIDENTIAL BUSINESS
INFORMATION**

VD-70

GEORGIA POWER COMPANY - SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WINSLEY
JOB NO.: 12
AREA: SCORPION

NIGHT SHIFT

DATE: 10-8-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1211

| | | | | | | | | |
|-----------------------------------|---------|-------|---------|-------|-------|-------|---------|-------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 426 | 434 | 442 | 428 | 446 | 444 | 434 | 444 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 128.0 | 126.5 | 125.5 | 127.5 | 125.0 | 125.5 | 126.5 | 125.5 |
| (F) Moist Count | 1236 | 1268 | 1214 | 1236 | 1210 | 1228 | 1225 | 1236 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 2540 | 2472 | 2472 | 2478 | 2422 | 2478 | 2510 | 2510 |
| (I) Dry Wt. | 10310 | 10213 | 10113 | 10277 | 10618 | 10677 | 10618 | 10618 |
| (J) Proctor Wt. | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 23+00 | 23+20 | 24+50 | 24+50 | 26+50 | 26+10 | 27+10 | 27+85 |
| | 90' R d | → | 25' R d | → | → | → | 60' R d | → |
| (O) Elev. | 755 | 754 | 754 | 755 | 754 | 755 | 755 | 756 |

Compaction Required 100%

CONFIDENTIAL BUSINESS
INFORMATION

Technician WD/70

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WANSLEY
JOB NO.: SEP
AREA: DAM

DATE: 10/8/73
DENSITY STANDARD COUNT: 2300
MOISTURE STANDARD COUNT: 200

DAY SHIFT

| | | | | | |
|-----------------------------------|------------------|-------------------|-------------------|----|--|
| (A) Test Number | 17 | 18 | 19 | 20 | |
| (B) Probe Depth | 6" | | | 6" | |
| (C) Dens. Count | 466 | 502 | 506 | | |
| (D) C ÷ Std Count | | | | | |
| (E) Wet Wt. (lb/ft ³) | <u>(222.5)</u> | <u>(118.5)</u> | <u>(118.0)</u> | | |
| (F) Moist Count | 1040 | 928 | 984 | | |
| (G) F ÷ Std Count | | | | | |
| (H) Wt. Moist (lbs) | 20.3 | 17.8 | 18.9 | | |
| (I) Dry Wt. | 102.2 | 100.7 | 99.1 | | |
| (J) Proctor Wt. | 101.0 | 101.0 | 101.0 | | |
| (K) % Comp. I ÷ J | 100 + | 99.8 | 98.3 | | |
| (L) % Moist | | | REFROLLEN | | |
| (N) Location | 17+90 31' R E | 19+50 160' R E | 19+30 170' R E | | |
| (O) Elev. | 710 | 718 | 717 | | |

Compaction Required 100%

CONFIDENTIAL BUSINESS
INFORMATION

Technician N. L. F. C. F.

GEORGIA POWER COMPANY — SUHLS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Wamsley
JOB NO.: sewdom
AREA: night shift

DATE: 10-7-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-----------------|------------|------------|------------|-----------------|------------|-----------------|------------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 464 | 448 | 452 | 444 | 446 | 438 | 442 | 452 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 123.0 | 125.0 | 124.5 | 125.5 | 125.0 | 126.0 | 125.5 | 124.5 |
| (F) Moist Count | 1158 | 1174 | 1160 | 1202 | 1158 | 1140 | 1200 | 1125 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 23.2 | 23.4 | 23.2 | 24.0 | 23.2 | 23.0 | 24.0 | 22.4 |
| (I) Dry Wt. | 98.8 | 101.6 | 101.3 | 101.5 | 101.5 | 101.0 | 101.1 | 100.7 |
| (J) Proctor Wt. | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | REF | REF | REF | REF | REF | REF | REF | REF |
| (N) Location | 17+50 30' Rk | 17+65 → | 18+75 ← | 18+85 → | 18+90 50' Rk | 19+00 → | 19+10 20' Rk | 19+20 → |
| (O) Elev. | 740 | 741 | 747 | 748 | 751 | 752 | 752 | 752 |

Compaction Required 100%

CONFIDENTIAL BUSINESS
INFORMATION

Technician UD

GEORGIA POWER COMPANY -- SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Ellansley
JOB NO.: SEP 12/71
AREA: SEP 12/71

DATE: 10-7-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
|-----------------------------------|------------------------|-------|-------|-------|-------|-------|-------|-------|
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 498 | 462 | 478 | 490 | 458 | 470 | 476 | 488 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 119.0 | 123.2 | 121.5 | 120.0 | 123.7 | 123.2 | 119.2 | 120.0 |
| (F) Moist Count | 1260 | 1100 | 990 | 1170 | 1080 | 1120 | 1000 | 1010 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 25.4 | 21.7 | 19.1 | 23.4 | 21.3 | 22.2 | 19.2 | 19.6 |
| (I) Dry Wt. | 93.6 | 101.5 | 102.4 | 96.6 | 102.4 | 100.0 | 100.0 | 100.4 |
| (J) Proctor Wt. | 92 | 100 | 100 | 99 | 102 | 100 | 100 | 100 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 20+00 - +15 100 LTR | +15 | 22+00 | +15 | 24+00 | +15 | 26+00 | +15 |
| (O) Elev. | 755 | 754 | 753 | 752 | 753 | 752 | 751 | 750 |

Compaction Required _____

Technician M. K.

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY - SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WAS/ky
JOB NO.: 50100000
AREA: 54. FT

DATE: 10-8-77
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-------|-------|--------|-------|-------|-------|--------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 1" | | | | | | | |
| (C) Dens. Count | 402 | 426 | 418 | 428 | 410 | 416 | 406 | 422 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 131.0 | 127.5 | 129.0 | 130.5 | 130.0 | 129.0 | 130.0 | 128.5 |
| (F) Moist Count | 1202 | 1180 | 1214 | 1152 | 940 | 1111 | 1116 | 1174 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 24.0 | 23.6 | 24.2 | 23.8 | 18.0 | 21.1 | 22.2 | 21.7 |
| (I) Dry Wt. | 107.0 | 103.9 | 104.8 | 104.5 | 112.0 | 107.9 | 107.8 | 108.2 |
| (J) Proctor Wt. | 106.2 | 103 | 103 | 103 | 110 | 106.3 | 106.7 | 106.3 |
| (K) % Comp. I ÷ J | 100 | 106 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 17+50 | 17+60 | 18+75 | 18+85 | 19+80 | | | |
| | 30' L | | 166' L | | 10' L | | 125' L | |
| (O) Elev. | 740 | 741 | 742 | 743 | 744 | 745 | 745 | 746 |

Compaction Required 100

Technician MD/70

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY -- SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Wansley
JOB NO.: SP121111
AREA: SP121111

DATE: 10-7-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1211

Night Shift

| | | | | | | | | |
|-----------------------------------|-----------------|-------------|-----------------|-------------|-------------|-------------|-----------------|-------------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 432 | 428 | 443 | 436 | 434 | 426 | 416 | 436 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 127.0 | 127.5 | 125.5 | 126.5 | 126.5 | 127.5 | 126.0 | 126.5 |
| (F) Moist Count | 1228 | 1226 | 1202 | 1216 | 1222 | 1246 | 1222 | 1238 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 24.8 | 24.8 | 24.0 | 24.6 | 24.6 | 25.0 | 24.8 | 25.0 |
| (I) Dry Wt. | 102.2 | 102.7 | 101.5 | 101.9 | 101.9 | 102.5 | 100.2 | 101.5 |
| (J) Proctor Wt. | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 19-175 46' L | 19-185 → | 21-150 20' R | 21-165 → | 24-175 φ | 24-185 → | 26-190 25' R | 26-190 → |
| (O) Elev. | 750 | 751 | 754 | 755 | 756 | 757 | 757 | 756 |

Compaction Required 16676

Technician W. A. B.

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY -- SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Wansley
JOB NO.: 1
AREA: See Dam

Tube
Dia

DATE: 10-8-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

DAY 5 HWT

| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
|-----------------------------------|------------------------|------------------------|------------------|------------------|------------------|------------------|------------------|------------------|
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 430 | 450 | 436 | 442 | 456 | 462 | 442 | 436 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | ^{127.2} 127.2 | ^{124.7} 124.7 | 126.2 | 125.7 | 124.0 | 123.2 | 125.2 | 126.2 |
| (F) Moist Count | 1040 | 1100 | 1030 | 1010 | 1120 | 1020 | 1000 | 990 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 20.3 | 21.7 | 20.1 | 19.6 | 22.2 | 20.0 | 19.3 | 19.1 |
| (I) Dry Wt. | 106.9 | 103.0 | 106.1 | 106.1 | 101.8 | 103.7 | 105.7 | 106.1 |
| (J) Proctor Wt. | 103 | 103 | 103 | 103 | 101 | 103 | 103 | 103 |
| (K) % Comp. I ÷ J | 100 ⁺ | 100 ⁺ | 100 ⁺ | 100 ⁺ | 100 ⁺ | 100 ⁺ | 100 ⁺ | 100 ⁺ |
| (L) % Moist | ^{19.5} | ^{22.0} | | | | | | |
| (N) Location | 27+00 50.7 E | 27+15 D | 25+00 60.7 E | 25+15 D | 23+00 30.7 E | 23+15 D | 21+00 E | 21+20 D |
| (O) Elev. | 755 | 754 | 755 | 754 | 754 | 753 | 752 | 751 |

Compaction Required 155

Technician _____

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WANSLEY

JOB NO.:

AREA:

SEPARATION DAM

DATE: 10/8/73

DENSITY STANDARD COUNT: 231

MOISTURE STANDARD COUNT: 1331

DAY 511111

| | | | | | | | | |
|-----------------------------------|-------------------|-------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|------------------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | 6" | | | | | | | 6" |
| (C) Dens. Count | 432 | 450 | 440 | 466 | 450 | 460 | 430 | 472 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 127.0 | 129.5 | 126.0 | 122.5 | 124.5 | 123.5 | 127.5 | 122.0 |
| (F) Moist Count | 1440 | 1396 | 1346 | 1336 | 1464 | 1114 | 1014 | 1196 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 29.6 | 28.7 | 27.5 | 27.3 | 30.1 | 22.0 | 19.6 | 19.3 |
| (I) Dry Wt. | 97.4 | 95.8 | 98.5 | 95.2 | 94.9 | 101.5 | 107.9 | 102.7 |
| (J) Proctor Wt. | 95.0 | 95.0 | 95.0 | 95.0 | 92.0 | 101.0 | 107.0 | 101.0 |
| (K) % Comp. I ÷ J | 100+ | 100+ | 100+ | 100+ | 100+ | 100+ | 100+ | 100+ |
| (L) % Moist | | — LIGHT WEIGHT MATERIAL | | | | | | |
| (N) Location | 26+50 160' L & | 25+50 160' L & | 24+50 160' L & | 23+50 160' L & | 22+50 160' L & | 18+60 110' R & | 18+20 120' R & | 17+70 70' R & |
| (O) Elev. | 757 | 758 | 759 | 760 | 755 | 715 | 716 | 711 |

Compaction Required 100%

Technician

M.K. C.E. 9-13

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

2-5-76

PROJECT: _____
JOB NO.: _____
AREA: Sep Dam

DATE: 9-27-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

Page 3

| | | | | | | | | |
|-----------------------------------|-----------|-------|-----------|-------|-----------|-------|----|----|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 406 | 412 | 436 | 424 | 412 | 430 | | |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 130.0 | 129.5 | 126.5 | 128.0 | 129.5 | 127.0 | | |
| (F) Moist Count | 1290 | 1280 | 1400 | 1320 | 1470 | 1280 | | |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 26.2 | 259 | 28.7 | 26.8 | 30.3 | 28.3 | | |
| (I) Dry Wt. | 103.8 | 103.6 | 97.8 | 101.2 | 99.2 | 98.7 | | |
| (J) Proctor Wt. | 100 | 106 | 98 | 100 | 98 | 98 | | |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | | |
| (L) % Moist | | | | | | | | |
| (N) Location | 100 L79 — | 12400 | 100 L79 — | 13400 | 125 L79 — | 17450 | | |
| (O) Elev. | 710 | 711 | 706 | 705 | 707 | 700 | | |

Compaction Required 100

Technician M. R.

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY

WORK SHEET

FIELD DENSITY TEST (Shelby Tube Method)

Client _____ Date _____

Project _____ Job / lab no. _____

| TEST NO. | W. W. SAMPLE & MOLD | WT. MOLD | W. W. SAMPLE | W. W. CU. FT. | W. W. MOIST SAMPLE | D. W. MOIST SAMPLE | W. MOIST | % MOIST | DRY DENSITY | * | % COMP. | LOCATION | C |
|----------|---------------------|----------|--------------|---------------|--------------------|--------------------|----------|---------|-------------|---|---------|------------|---|
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| 1 | | | | 117.2 | | | | 19.9 | 106.6 | | 100 | See Fig. 3 | |
| | | | | | | | | | | | | | |
| 2 | 25' | | 100 | 169 | 10 | 163 | 100 | 19.3 | 106.6 | | 100 | | |
| | | | | | | | | | | | | | |
| 3 | 10' | | 115 | 1007 | 10 | 837 | 75 | 19.3 | 106.6 | | 100 | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| 10 | | | | 127.8 | | 83.6 | | 19.3 | 106.6 | | | See Fig. 3 | |
| | | | | | | | | | | | | | |
| 12 | | | | 126.3 | | | | 22.9 | 103.0 | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |

* Tests Compared To:

Compaction Curve No. _____ Maximum _____ pcf. Optimum Moisture _____ %

Compaction Required _____ %

Mold Volume Factor _____

Not to be typed

Work performed by _____

CONFIDENTIAL BUSINESS INFORMATION

NUCLEAR DENSITY METER WORK SHEET

PROJECT: 14th Street
 JOB NO.: 100
 AREA: 100

DATE: 9-27-73
 DENSITY STANDARD COUNT: 231
 MOISTURE STANDARD COUNT: 1271

| | | | | | | | |
|-----------------------------------|---------|---------|---------|---------|---------|--------|--|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | |
| (B) Probe Depth | | | | | | | |
| (C) Dens. Count | 122 | 454 | 122 | 122 | 122 | 410 | |
| (D) C ÷ Std Count | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 128.2 | 128.2 | 128.2 | 128.2 | 128.2 | 128.2 | |
| (F) Moist Count | 1070 | 1070 | 1070 | 1070 | 1070 | 900 | |
| (G) F ÷ Std Count | | | | | | | |
| (H) Wt. Moist (lbs) | 21.3 | 14.3 | 14.3 | 14.3 | 14.3 | 11.5 | |
| (I) Dry Wt. | 107.7 | 108.7 | 108.7 | 108.7 | 108.7 | 112.3 | |
| (J) Proctor Wt. | 1 | 106 | 106 | 106 | 106 | 106 | |
| (K) % Comp. I ÷ J | 102 | 103 | 102 | 102 | 102 | 102 | |
| (L) % Moist | 20.0 | 12.9 | 12.9 | 12.9 | 12.9 | 7 | |
| (N) Location | 2+75 | 2+50 | 2+25 | 2+00 | 2+00 | 2+00 | |
| | 135-179 | 135-179 | 135-179 | 135-179 | 135-179 | 65-179 | |
| (O) Elev. | 74.0 | 74.0 | 74.0 | 74.0 | 74.0 | 74.0 | |

Compaction Required 100%

Technician 701

CONFIDENTIAL BUSINESS INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Wansley

JOB NO.:

AREA:

Seperation Dam

DATE: Sept 22-1965

DENSITY STANDARD COUNT: 202

MOISTURE STANDARD COUNT: 1522

| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
|-----------------------------------|----------------------|-----------------|----------------------|-----------------|---------------|---------------|---------------|---------------|
| (B) Probe Depth | 6" | ← | | | | | → | 6" |
| (C) Dens. Count | 460 | 438 | 450 | 440 | 464 | 458 | 486 | 470 |
| (D) C ÷ Std Count | 126.4 | 129.5 | 128.0 | 128.9 | 126.5 | 127.0 | 123.9 | 125.5 |
| (E) Wet Wt. (lb/ft ³) | 23 | | | | | | | |
| (F) Moist Count | 1432 | 1422 | 1630 | 1472 | 1504 | 1548 | 1466 | 1386 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 23.2 | 23.0 | 27.0 | 24.0 | 24.7 | 25.4 | 23.8 | 22.3 |
| (I) Dry Wt. | 203.2 | 206.5 | 202.0 | 204.9 | 201.8 | 201.6 | 200.1 | 203.2 |
| (J) Proctor Wt. | 103 | 106 | 100 | 103 | 100 | 100 | 100 | 103 |
| (K) % Comp. I ÷ J | 100% | 100% | 100% | 100% | 100% | 100% | 100% | 100% |
| (L) % Moist | | | | | | | | |
| (N) Location | Left 60 FT Sta 12+00 | 60 FT Sta 12+15 | Left 60 FT Sta 13+05 | 60 FT Sta 13+20 | 50' Sta 14+20 | 50' Sta 14+45 | 50' Sta 15+05 | 50' Sta 15+20 |
| (O) Elev. | 710 | 711 | 709 | 708 | 702 | 702 | 697 | 698 |

Compaction Required 100%

Technician A.M.L.

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: W. Rossley
JOB NO.: SEP 2001
AREA: SEP 2001

Night

DATE: 9-26-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|--------|-------|--------|-------|---------|-------|--------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 408 | 422 | 416 | 412 | 406 | 408 | 418 | 420 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 130.0 | 128.5 | 129.0 | 129.5 | 130.5 | 130.0 | 129.0 | 128.5 |
| (F) Moist Count | 1172 | 1194 | 1204 | 1192 | 1204 | 1188 | 1156 | 1182 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 23.4 | 23.8 | 24.0 | 23.8 | 24.0 | 23.8 | 23.2 | 23.6 |
| (I) Dry Wt. | 106.6 | 104.7 | 105.0 | 105.7 | 106.5 | 106.2 | 105.8 | 104.9 |
| (J) Proctor Wt. | 105 | 105 | 105 | 105 | 105 | 105 | 105 | 105 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 11700 | 11715 | 12750 | 12766 | 13775 | 13785 | 14725 | 14750 |
| | 50' Rd | → | 80' Rd | → | 100' Rd | → | 30' Rd | → |
| (O) Elev. | 701 | 702 | 697 | 698 | 692 | 693 | 691 | 692 |

Compaction Required 100%

Technician V.D. / 70

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY - BUILDS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Wk 25/ey
JOB NO.: SEP 2000
AREA: SEP 2000

DATE: 9-27-73
DENSITY STANDARD COUNT: 271
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 402 | 412 | 408 | 406 | 398 | 416 | 404 | 414 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 131.0 | 129.5 | 130.0 | 130.0 | 131.5 | 129.0 | 130.5 | 129.5 |
| (F) Moist Count | 1174 | 1192 | 1216 | 1204 | 1090 | 1144 | 1216 | 1186 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 23.4 | 23.8 | 24.6 | 24.0 | 21.5 | 22.7 | 24.6 | 22.8 |
| (I) Dry Wt. | 107.6 | 105.7 | 105.4 | 106.0 | 110.0 | 106.3 | 105.9 | 105.7 |
| (J) Proctor Wt. | 108.5 | 106.7 | 105.5 | 105.3 | 108 | 106.3 | 105.3 | 105.7 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 11+75 | 11+85 | 12+50 | 12+65 | 13+25 | 13+35 | 14+00 | 14+10 |
| (O) Elev. | 704 | 705 | 798 | 799 | 694 | 693 | 691 | 692 |

Compaction Required 100%

Technician VD/70

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: W. 1000000
AREA: Area

DATE: 9-26-66
DENSITY STANDARD COUNT: 1000
MOISTURE STANDARD COUNT: 1000

| | | | | | | | | |
|-----------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 130 | 142 | 150 | 152 | 155 | 158 | 160 | 164 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 125.2 | 135.7 | 145.5 | 150.0 | 155.0 | 160.0 | 165.0 | 170.0 |
| (F) Moist Count | 1300 | 1410 | 1510 | 1550 | 1600 | 1650 | 1700 | 1750 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 2.2 | 2.4 | 2.6 | 2.7 | 2.8 | 2.9 | 3.0 | 3.1 |
| (I) Dry Wt. | 2.0 | 2.2 | 2.4 | 2.5 | 2.6 | 2.7 | 2.8 | 2.9 |
| (J) Proctor Wt. | 1.0 | 1.1 | 1.2 | 1.3 | 1.4 | 1.5 | 1.6 | 1.7 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 12-75 | 12-70 | 11-45 | 11-40 | 11-35 | 11-30 | 11-25 | 11-20 |
| (O) Elev. | 75.87 | 75.80 | 75.75 | 75.70 | 75.65 | 75.60 | 75.55 | 75.50 |

Compaction Required 100

Technician 100

CONFIDENTIAL BUSINESS
INFORMATION

PROJECT: _____
JOB NO.: _____
AREA: _____

DATE: _____
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | | | | |
|-----------------------------------|--------------------|------------|-------------------|-------|--|--|--|--|--|
| (A) Test Number | | | | | | | | | |
| (B) Probe Depth | | | | | | | | | |
| (C) Dens. Count | 121 | | | | | | | | |
| (D) C ÷ Std Count | | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 121 | | | | | | | | |
| (F) Moist Count | 126 | 9.6 | 1.96 | 12.10 | | | | | |
| (G) F ÷ Std Count | | | | | | | | | |
| (H) Wt. Moist (lbs) | 15.7 | 1.1 | 2.15 | 25.0 | | | | | |
| (I) Dry Wt. | 102.1 | 10.0 | 1.0 | 99.5 | | | | | |
| (J) Proctor Wt. | | | 1.0 | | | | | | |
| (K) % Comp. I ÷ J | 102 | 1.3 | 1.02 | | | | | | |
| (L) % Moist | | | | | | | | | |
| (N) Location | 12+50 100 ± 7.3 | 12+70 4 | 13+50 90 ± 7.3 | | | | | | |
| (O) Elev. | 100 | 19.0 | | | | | | | |

Compaction Required

Technician

**CONFIDENTIAL BUSINESS
INFORMATION**

NUCLEAR DENSITY METER WORK SHEET

PROJECT: Wansley
 JOB NO.: SEP / DAM
 AREA: SEP / DAM

DATE: 9-25-73
 DENSITY STANDARD COUNT: 231
 MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-------|-------|---------|-------|---------|-------|---------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 452 | 446 | 478 | 434 | 418 | 436 | 432 | 444 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 124.5 | 125.0 | 127.5 | 126.5 | 128.5 | 126.5 | 127.0 | 125.5 |
| (F) Moist Count | 1202 | 1214 | 1234 | 1224 | 1148 | 1196 | 1192 | 1206 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 24.0 | 24.2 | 24.8 | 24.6 | 20.6 | 24.0 | 23.8 | 24.2 |
| (I) Dry Wt. | 100.5 | 100.8 | 102.7 | 101.9 | 107.9 | 102.5 | 103.2 | 101.3 |
| (J) Proctor Wt. | 180 | 180 | 180 | 180 | 186.3 | 180 | 180 | 180 |
| (K) % Comp. I ÷ J | 180 | 180 | 180 | 180 | 180 | 180 | 180 | 180 |
| (L) % Moist | | | | | | | | |
| (N) Location | 10+50 | 10+80 | 11+50 | 11+75 | 12+75 | 12+85 | 14+80 | 14+20 |
| | φ | → | 80' R φ | → | 90' L φ | → | 25' R φ | → |
| (O) Elev. | 712 | 713 | 712 | 713 | 712 | 713 | 713 | 714 |

Compaction Required 108%

Technician VD / 70

CONFIDENTIAL BUSINESS INFORMATION

GEORGIN (OTHER COMPANY) - QUILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WANSLEY
JOB NO.: 1
AREA: SEP Dam

DATE: 9/26-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|--------------------|-------|---------------------|-------|---------------------|-------|-------|-------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 460 | 454 | 436 | 442 | 416 | 452 | 456 | 458 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 123.5 | 124.0 | 126.5 | 125.5 | 129.0 | 124.5 | 124.0 | 123.5 |
| (F) Moist Count | 1178 | 1196 | 1232 | 1192 | 1012 | 1222 | 1180 | 1168 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 23.6 | 23.8 | 24.8 | 23.8 | 19.6 | 24.6 | 23.6 | 23.4 |
| (I) Dry Wt. | 99.9 | 100.2 | 101.7 | 101.7 | 109.4 | 99.9 | 100.7 | 100.1 |
| (J) Proctor Wt. | 100 | 100 | 100 | 100 | 108 | 100 | 100 | 100 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 10+50 | 10+60 | 12+00 | 12+10 | 13+00 | 13+20 | 14+75 | 14+80 |
| | 40' L ₄ | → | 100' R ₄ | → | 100' L ₄ | → | → | → |
| (O) Elev. | 713 | 714 | 714 | 715 | 714 | 715 | 714 | 715 |

Compaction Required 100%

Technician UD/gd

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Winstley
JOB NO.:
AREA: Department Dam

DATE: 9/22/83
DENSITY STANDARD COUNT:
MOISTURE STANDARD COUNT:

[illegible]

| | |
|---------------------|-----|
| Compaction Required | 160 |
|---------------------|-----|

Technician

**CONFIDENTIAL BUSINESS
INFORMATION**

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Labrador
JOB NO.:
AREA:

DATE: 9/10/54
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 171

| | | | | | | | | | |
|-----------------------------------|--------|-------|--|--|--|--|--|--|--|
| (A) Test Number | 17 | 18 | | | | | | | |
| (B) Probe Depth | | | | | | | | | |
| (C) Dens. Count | 150 | 112 | | | | | | | |
| (D) C ÷ Std Count | | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 124.7 | 125.7 | | | | | | | |
| (F) Moist Count | 1120 | 1100 | | | | | | | |
| (G) F ÷ Std Count | 22.2 | 21.7 | | | | | | | |
| (H) Wt. Moist (lbs) | 102.5 | 104.0 | | | | | | | |
| (I) Dry Wt. | 100 | 100 | | | | | | | |
| (J) Proctor Wt. | 103 | 104 | | | | | | | |
| (K) % Comp. I ÷ J | | | | | | | | | |
| (L) % Moist | | | | | | | | | |
| (N) Location | 21400 | 21420 | | | | | | | |
| | 9027 ± | — | | | | | | | |
| (O) Elev. | 746 | 745 | | | | | | | |

Compaction Required 100

Technician

**CONFIDENTIAL BUSINESS
INFORMATION**

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: 11A-10
JOB NO.: 1000
AREA: 1000

DATE: 9/23/72
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 12-11

| | | | | | | | |
|-----------------------------------|-------|-------|-------|-------|-------|-------|-----|
| (A) Test Number | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | | | | | | | |
| (C) Dens. Count | 100 | 448 | 160 | | 438 | | 428 |
| (D) C ÷ Std Count | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 122.5 | 125.0 | 123.5 | 127.2 | 125.0 | 125.5 | |
| (F) Moist Count | 100 | 1220 | 100 | 1040 | 1040 | 1060 | |
| (G) F ÷ Std Count | | | | | | | |
| (H) Wt. Moist (lbs) | 23.2 | 24.6 | 25 | 27.3 | 27.3 | 27.6 | |
| (I) Dry Wt. | 99.3 | 100.4 | 97.1 | 106.7 | 104.7 | | |
| (J) Proctor Wt. | 100 | 104 | 98 | 104 | 104 | 103 | |
| (K) % Comp. I ÷ J | | | | | | | |
| (L) % Moist | | | | | | | |
| (N) Location | 22+50 | 22+70 | 23+15 | 23+50 | 23+50 | 23+55 | |
| | 30+14 | 30+14 | 30+14 | 30+14 | 30+14 | 30+14 | |
| (O) Elev. | 746 | 745 | 745 | 748 | 748 | 748 | |

Compaction Required 100%

Technician W K

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WANSLEY
JOB NO.: SEP DAM
AREA: SEP DAM

DATE: 9-24-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1276

| | | | | | | | | |
|-----------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 482 | 494 | 486 | 466 | 492 | 488 | 478 | 484 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 121.0 | 119.5 | 120.5 | 122.0 | 119.5 | 120.5 | 121.5 | 120.5 |
| (F) Moist Count | 1050 | 1080 | 1062 | 1106 | 1028 | 1056 | 1092 | 1068 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 20.6 | 21.7 | 20.8 | 22.0 | 20.1 | 20.8 | 21.5 | 21.1 |
| (I) Dry Wt. | 100.4 | 98.2 | 99.7 | 100.0 | 99.4 | 99.7 | 100.0 | 99.4 |
| (J) Proctor Wt. | 190.0 | 98 | 100.0 | 100.0 | 98 | 100.0 | 100.0 | 98 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 19+75 | 19+80 | 24+00 | 21+15 | 22+75 | 23+00 | 24+00 | 25+15 |
| (O) Elev. | 753 | 754 | 755 | 756 | 755 | 756 | 721 | 722 |

NEW PROCTOR

Compaction Required 100%

Technician SD/70

CONFIDENTIAL BUSINESS
INFORMATION

NUCLEAR DENSITY METER WORK SHEET

PROJECT: W Ansley
 JOB NO.: 1
 AREA: SEP Dam

DATE: 9-25-73
 DENSITY STANDARD COUNT: 231
 MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|--------|-------|---------|-------|---------|-------|---------|-------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 466 | 482 | 464 | 468 | 472 | 446 | 438 | 454 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 122.5 | 121.0 | 123.0 | 122.5 | 122.0 | 125.0 | 126.0 | 124.0 |
| (F) Moist Count | 1084 | 1048 | 1102 | 1014 | 1020 | 998 | 976 | 982 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 21.3 | 20.4 | 21.7 | 19.6 | 19.9 | 19.3 | 18.9 | 18.9 |
| (I) Dry Wt. | 101.2 | 100.4 | 101.3 | 102.9 | 102.1 | 103.7 | 107.1 | 105.1 |
| (J) Proctor Wt. | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (K) % Comp. I ÷ J | | | | | | | | |
| (L) % Moist | | | | | | | | |
| (N) Location | 20+50 | 20+65 | 22+50 | 22+60 | 24+00 | 24+15 | 25+75 | 25+85 |
| | 80' Ld | → | 150' Ld | → | 100' Ld | → | 105' Ld | → |
| (O) Elev. | 754 | 755 | 758 | 759 | 758 | 759 | 760 | 759 |

Compaction Required 100%

Technician VD/70

CONFIDENTIAL BUSINESS
 INFORMATION

PROJECT: WANSLEY

JOB NO.: 3

AREA: SEPARATION DAM

DATE: SEPT 24, 1973

DENSITY STANDARD COUNT: 262

MOISTURE STANDARD COUNT: 1572

| | | | | | | | | |
|-----------------------------------|---------------------|--------------------|---------------------|--------------------|--------------------|--------------------|--------------------|--------------------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 456 | 469 | 496 | 494 | 428 | 468 | 460 | 444 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 127.5 | 126.5 | 123.0 | 123.0 | 130.5 | 126.0 | 126.7 | 126.7 |
| (F) Moist Count | 1564 | 1530 | 1418 | 1454 | 1192 | 1288 | 1420 | 1370 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 25.8 | 25.0 | 23.0 | 23.8 | 18.8 | 20.5 | 24.2 | 24.1 |
| (I) Dry Wt. | 101.7 | 101.5 | 100.0 | 99.2 | 111.7 | 105.5 | 102.5 | 106.7 |
| (J) Proctor Wt. | 100.0 | 100.0 | 100.0 | 98.0 | 110.0 | 105.0 | 100 | 105 |
| (K) % Comp. I ÷ J | 100.0% | 100.0% | 100.0% | 100.0% | 100.0% | 100.0% | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 22+00 100' LT. & | 22+30 90' LT. & | 24+50 100' LT. & | 24+70 90' LT. & | 27+00 80' LT. & | 31+20 70' LT. & | 34+00 80' LT. & | 34+20 80' LT. & |
| (O) Elev. | 755 | 754 | 753 | 753 | 755 | 754 | 738 | 737 |

Compaction Required 100%

Technician

R. DUKE # CE

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY - SUILO
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Manley
JOB NO.:
AREA: Separation Dam

DATE: 9/24/73
DENSITY STANDARD COUNT: 262
MOISTURE STANDARD COUNT: 1522

| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
|-----------------------------------|---------|---------|---------|---------|---------|---------|---------|---------|
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 434 | 110 | 126 | 152 | 430 | 438 | 152 | 434 |
| (D) C ÷ Std Count | | | 1.62 | 1.73 | 1.64 | 1.67 | 1.73 | 1.66 |
| (E) Wet Wt. (lb/ft ³) | 130.0 | 130.5 | 131.0 | 131.7 | 130.5 | 131.0 | 131.7 | 130.0 |
| (F) Moist Count | 1300 | 1310 | 1340 | 1350 | 1300 | 1300 | 1310 | 1320 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 23.0 | 23.0 | 21.5 | 21.7 | 21.7 | 21.2 | 22.0 | 21.7 |
| (I) Dry Wt. | 108.0 | 109.8 | 108.5 | 108.0 | 109.8 | 109.3 | 108.7 | 108.3 |
| (J) Proctor Wt. | 107 | 107 | 107 | 107 | 107 | 107 | 107 | 107 |
| (K) % Comp. I ÷ J | 101 | 103 | 102 | 101 | 103 | 102 | 103 | 101 |
| (L) % Moist | | | | | | | | |
| (N) Location | 300 L+0 | 300 L+0 | 300 L+0 | 300 L+0 | 300 L+0 | 300 L+0 | 300 L+0 | 300 L+0 |
| (O) Elev. | 22.1 | 22.1 | 22.1 | 22.1 | 22.1 | 22.1 | 22.1 | 22.1 |

Compaction Required 100

Technician MM-2

CONFIDENTIAL BUSINESS
INFORMATION

GLUING POWER COMPACT - SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Wassley

JOB NO.:

AREA: Intake - access Road

DATE: Sept 23-1973

DENSITY STANDARD COUNT: 231

MOISTURE STANDARD COUNT: 1221

| | | | | | | | | |
|-----------------------------------|--|--|---|---|---|---|--|--|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | 6" | 6" | 6" | 6" | 6" | 6" | 6" |
| (C) Dens. Count | 424 | 432 | 464 | 500 | 432 | 456 | 474 | 480 |
| (D) C ÷ Std Count | | | 125.0 | | | | | |
| (E) Wet Wt. (lb/ft ³) | 128.0 | 127.0 | 95.4 119.0 | | 127.0 | 124.0 | 122.0 | 121.0 |
| (F) Moist Count | | | 95.4 | | | | | |
| (G) F ÷ Std Count | 1160 | 1140 | 18.3 | | 1126 | 1036 | 980 | 1026 |
| (H) Wt. Moist (lbs) | 23.2 | 22.7 | 18.3 | 13.4 | 22.3 | 20.2 | 18.9 | 19.9 |
| (I) Dry Wt. | 104.8 | 104.3 | 104.7 | 105.6 | 104.7 | 103.8 | 103.1 | 101.7 |
| (J) Proctor Wt. | 103 | 103 | 103 | 103 | 103 | 103 | 103 | 100 |
| (K) % Comp. I ÷ J | 100% | 100% | 106% | 100% | 100% | 100% | 100% | 100% |
| (L) % Moist | | | | | | | | |
| (N) Location | 20' Lt G Facing North 125' North of downstream cell | 20' Lt G Facing North 100' North of downstream cell | 20' Lt G Facing North 40' North of downstream cell | 20' Lt G Facing North 55' North of downstream cell | 12' Lt G Facing North 30' North of downstream cell | 12' Lt G Facing North 45' North of downstream cell | 12' Lt G Facing North 120' North of downstream cell | 12' Lt G Facing North 135' North of downstream cell |
| (O) Elev. | 682 | 680 | 683 | 684 | 683 | 682 | 683 | 684 |

678 687 672 682

Compaction Required 100%

Technician A.M.L.

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

2-5-76

PROJECT: 60 New/100
JOB NO.: 100000
AREA: 100000

DATE: 9-22-73
DENSITY STANDARD COUNT: 2531
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|--------|-------|--------|-------|--------|-------|-------|-------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 454 | 442 | 434 | 448 | 454 | 452 | 446 | 426 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 124.0 | 126.0 | 126.5 | 125.0 | 124.0 | 123.5 | 123.0 | 126.5 |
| (F) Moist Count | 1022 | 1094 | 1070 | 1054 | 982 | 966 | 1025 | 1056 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 19.9 | 21.5 | 21.1 | 20.6 | 18.9 | 18.7 | 17.8 | 20.3 |
| (I) Dry Wt. | 104.1 | 104.5 | 105.4 | 104.4 | 105.1 | 104.8 | 107.2 | 106.2 |
| (J) Proctor Wt. | 113 | 103 | 102 | 103 | 103 | 103 | 106.3 | 106.3 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 21+50 | 21+60 | 22+75 | 22+00 | 24+80 | 24+00 | 26+50 | 26+65 |
| | 200' L | → | 100' L | → | 120' L | → | 25' L | → |
| (O) Elev. | 759 | 760 | 762 | 763 | 764 | 765 | 764 | 765 |

Compaction Required 100%

CONFIDENTIAL BUSINESS
INFORMATION

Technician UD

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: W. West
JOB NO.: 50010241
AREA: 50010241

DATE: 7-21-78
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1171

| | | | | | | | | |
|-----------------------------------|--------|-------|--------|-------|--------|-------|--------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 502 | 466 | 456 | 462 | 448 | 454 | 438 | 436 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 118.5 | 123.0 | 124.0 | 123.5 | 125.0 | 124.0 | 125.0 | 126.8 |
| (F) Moist Count | 1150 | 1132 | 1168 | 1126 | 1098 | 1062 | 1038 | 1104 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 23.0 | 22.4 | 23.4 | 22.4 | 26.7 | 20.8 | 20.3 | 21.7 |
| (I) Dry Wt. | 95.5 | 100.6 | 100.6 | 101.1 | 103.3 | 103.2 | 104.7 | 104.8 |
| (J) Proctor Wt. | 100 | 100 | 100 | 100 | 103 | 103 | 103 | 103 |
| (K) % Comp. I ÷ J | 96 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | Rekd | | | | | | | |
| (N) Location | 23+50 | 23+60 | 25+00 | 25+20 | 23+40 | 22+25 | 19+00 | 19+20 |
| | 230'24 | → | 275'24 | → | 250'24 | → | 180'24 | → |
| (O) Elev. | 741 | 742 | 742 | 743 | 740 | 739 | 738 | 739 |

Compaction Required 100 %

Technician VP

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: See Data

DATE: 7-22-75
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | | | |
|-----------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 454 | 430 | 430 | 438 | 480 | 440 | 573 | 428 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 124.2 | 127.2 | 127.2 | 128.2 | 121.2 | 125.7 | 121.5 | 127.5 |
| (F) Moist Count | 1060 | | | | | | | |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 20.8 | 22.2 | 21.1 | 20.6 | 21.8 | 19.7 | 19.3 | 21.3 |
| (I) Dry Wt. | 103.4 | 105.0 | 106.1 | 105.6 | 100.4 | 105.0 | 102.2 | 107.2 |
| (J) Proctor Wt. | 100 | 103 | 102 | 103 | 100 | 103 | 100 | 105 |
| (K) % Comp. I ÷ J | 103 | 102 | 103 | 103 | 100 | 103 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 26+00 | 26+15 | 25+00 | 25+15 | 23+50 | 24+35 | 21+00 | 21+21 |
| | 1149 | 1149 | 1527 | 1527 | 2 | 2 | 1079 | 2 |
| (O) Elev. | 750 | 749 | 749 | 748 | 744 | 743 | 739 | 738 |

Compaction Required 1/16

Technician 7912

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY - SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: 504 Dism

DATE: 12/20/70
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | | | |
|-----------------------------------|--------|--------|--------|--------|-------|-------|-------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 300 | 118 | 516 | 480 | 540 | 520 | 418 | 430 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 1310 | 128.7 | 111.5 | 121.2 | 114.7 | 116.7 | 123.7 | 123.0 |
| (F) Moist Count | 1240 | 1030 | 890 | 1080 | 1060 | 1070 | 1010 | 1000 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 25.0 | 19.7 | 16.9 | 21.2 | 20.8 | 20.3 | 19.6 | 19.7 |
| (I) Dry Wt. | 106.0 | 108.8 | 99.1 | 100.0 | 94.0 | 96.4 | 109.1 | 107.7 |
| (J) Proctor Wt. | 104 | 107 | 98 | 98 | 94 | 94.0 | 107 | 107 |
| (K) % Comp. I ÷ J | 102 | 102 | 101 | 102 | 100 | 102 | 102 | 101 |
| (L) % Moist | | | | | | | | |
| (N) Location | 25400 | 25415 | 23450 | 23470 | 21450 | 21170 | 20450 | 20270 |
| | 100272 | 100272 | 110272 | 100272 | 25272 | 25272 | 50272 | 50272 |
| (O) Elev. | 718 | 747 | 746 | 745 | 746 | 745 | 745 | 724 |

Compaction Required _____

CONFIDENTIAL BUSINESS
INFORMATION

Technician JM-A

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Waukesha
JOB NO.: SEP DAM
AREA: SEP DAM

DATE: 9-21-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
|-----------------------------------|--------------------|-------------|--------------------|-------------|--------------------|-------------|--------------------|-------------|
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 438 | 426 | 434 | 428 | 430 | 470 | 466 | 460 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 126.0 | 127.5 | 126.5 | 125.0 | 127.0 | 122.5 | 122.5 | 123.5 |
| (F) Moist Count | 1156 | 1166 | 1098 | 1156 | 1120 | 932 | 916 | 926 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 23.2 | 23.4 | 21.7 | 23.2 | 22.2 | 17.8 | 17.5 | 17.8 |
| (I) Dry Wt. | 102.8 | 104.1 | 105.8 | 101.8 | 104.8 | 104.7 | 105.0 | 105.7 |
| (J) Proctor Wt. | 100 | 100 | 105.0 | 100 | 105.0 | 100 | 100 | 100 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 19-100 30' 2 ft | 19-120 → | 21-450 80' 2 ft | 21-475 → | 23-775 75' 2 ft | 23-180 → | 23-150 20' 2 ft | 25-160 → |
| (O) Elev. | 730 | 731 | 733 | 734 | 740 | 741 | 752 | 753 |

Compaction Required 180/90

Technician UD/TO

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: W PWSLEY
JOB NO.: SEP 2100
AREA: SEP 2100

DATE: 9-22-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1231

| | | | | | | | | |
|-----------------------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|
| (A) Test Number | 91 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 424 | 430 | 460 | 466 | 428 | 416 | 414 | 432 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 128.0 | 127.0 | 123.5 | 125.5 | 127.5 | 129.6 | 122.0 | 123.5 |
| (F) Moist Count | 1162 | 1164 | 972 | 1128 | 1168 | 1202 | 926 | 444 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 23.2 | 23.2 | 18.7 | 22.4 | 23.4 | 24.0 | 17.8 | 18.0 |
| (I) Dry Wt. | 104.8 | 103.8 | 104.8 | 103.1 | 104.1 | 105.0 | 104.2 | 105.5 |
| (J) Proctor Wt. | 107 | 107 | 107 | 107 | 107 | 107 | 107 | 107 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 18+60 100' 2' | 18+75 100' 2' | 20+50 100' 2' | 20+60 100' 2' | 22+50 100' 2' | 22+60 100' 2' | 24+15 125' 2' | 24+80 125' 2' |
| (O) Elev. | 732 | 733 | 734 | 735 | 742 | 743 | 751 | 750 |

Compaction Required 180%

Technician U.D. 70

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY -- SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: Gap Cave

DATE: 9-21-73
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | | | |
|-----------------------------------|---------|---------|---------|---------|---------|---------|---------|---------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 430 | 420 | 440 | 478 | 450 | 452 | 400 | 418 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 1272 | 128.5 | 126.0 | 121.5 | 124.5 | 123.2 | 121.0 | 122.7 |
| (F) Moist Count | 1100 | 1080 | | 1260 | 1180 | 1200 | 1000 | 1080 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 21.7 | 21.3 | 28.7 | 25.4 | 23.5 | 26.4 | 21.5 | 21.3 |
| (I) Dry Wt. | 105.5 | 107.2 | 97.3 | 96.1 | 101.0 | 96.8 | 107.5 | 106.4 |
| (J) Proctor Wt. | 103 | 105 | 94 | 94 | 98 | 94 | 101 | 106 |
| (K) % Comp. I ÷ J | 103 | 102 | 100 | 100 | 100 | 100 | | |
| (L) % Moist | | | | | | | | |
| (N) Location | 20+00 | 20+15 | 21+00 | 21+20 | 23+00 | 24+00 | 24+50 | 24+50 |
| | 25 LT E | 25 LT E | 25 LT E | 25 LT E | 25 LT E | 25 LT E | 25 LT E | 25 LT E |
| (O) Elev. | 730 | 729 | 734 | 733 | 742 | 741 | 732 | 731 |

Compaction Required 100

Technician M. H.

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY - SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Wmnsley
JOB NO.: SEPDM
AREA:

DATE: 9-21-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|------------------|------------|-------------------|------------|-------------------|------------|-------------------|------------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 448 | 454 | 456 | 442 | 438 | 448 | 452 | 464 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 125.0 | 124.0 | 124.0 | 125.5 | 126.0 | 125.0 | 123.5 | 123.0 |
| (F) Moist Count | 1212 | 1194 | 1216 | 1182 | 1232 | 1068 | 1020 | 1016 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 24.2 | 23.8 | 24.6 | 23.6 | 24.8 | 21.1 | 19.9 | 19.9 |
| (I) Dry Wt. | 100.8 | 100.2 | 99.4 | 101.9 | 101.2 | 103.9 | 103.6 | 103.1 |
| (J) Proctor Wt. | 100 | 100 | 98 | 100 | 100 | 103 | 103 | 103 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 18+50 80' 24" | 18+60 → | 19+75 175' 24" | 20+00 → | 21+75 110' 24" | 22+00 → | 23+50 100' 24" | 23+65 → |
| (O) Elev. | 757 | 756 | 759 | 758 | 762 | 761 | 762 | 761 |

Compaction Required 16090

CONFIDENTIAL BUSINESS
INFORMATION

Technician UD/TB

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: Scp Dam

DATE: 9/21/73
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | | | |
|-----------------------------------|-------------------|-------------|-------------------|-------------|-------------------|-------------|-------------------|-------------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | | | | | | | 492 | 510 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 1260 | 1272 | 1282 | 1295 | 1287 | 1265 | 1277 | 1277 |
| (F) Moist Count | 1100 | 1060 | 1110 | 1030 | 1060 | 980 | 1120 | 1050 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 21.7 | 20.8 | 22.0 | 20.1 | 20.8 | 13.9 | 13.6 | 20.6 |
| (I) Dry Wt. | 104.3 | 106.4 | 106.2 | 109.4 | 107.9 | 107.6 | 76.1 | 97.1 |
| (J) Proctor Wt. | 103 | 103 | 103 | 106 | 106 | 106 | 104 | 99.0 |
| (K) % Comp. I ÷ J | 101 | 103 | 103 | 103 | 102 | 102 | 102 | 103 |
| (L) % Moist | | | | | | | | |
| (N) Location | 26+75 200 RT 9 | 26+60 —A | 25+75 200 RT 9 | 25+45 —A | 22+50 190 RT 9 | 21+70 —A | 20+40 180 RT 9 | 20+65 —A |
| (O) Elev. | 725 | 726 | 723 | 722 | 720 | 721 | 720 | 721 |

Compaction Required 100

CONFIDENTIAL BUSINESS
INFORMATION

Technician M. Z.

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: Sep Dam

DATE: 9-20-73
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | | | |
|-----------------------------------|--------|--------|-------|--------|--------|--------|--------|--------|
| (A) Test Number | 1 | 2 | 3 | A | 5 | 6 | 7 | 8 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 436 | 420 | 410 | 412 | 442 | 448 | 1 | 458 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 126.5 | 128.5 | 131.0 | 129.0 | 125.7 | 125.0 | | 123.7 |
| (F) Moist Count | 1160 | 1080 | 1000 | 1100 | 1241 | 1210 | 110 | 1180 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 43.7 | 21.3 | 19.3 | 21.1 | 25.0 | 28.4 | | 22.1 |
| (I) Dry Wt. | 103.3 | 107.2 | 111.7 | 107.3 | 100.7 | 96.6 | 89.7 | 101.1 |
| (J) Proctor Wt. | 101 | 103 | 102 | 104 | 98 | 98 | 118 | 92 |
| (K) % Comp. I ÷ J | 102 | 104 | 104 | 103 | 102 | 112 | 112 | 102 |
| (L) % Moist | | | | | | | | |
| (N) Location | 25450 | 25458 | 23450 | 23455 | 21450 | 21450 | 19450 | 19455 |
| | 100172 | 100172 | 90172 | 100172 | 100172 | 100172 | 105172 | 105172 |
| (O) Elev. | 745 | 746 | 738 | 737 | 733 | 732 | 728 | 727 |

Compaction Required 100

Technician M K

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY - SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WATWOLEY
JOB NO.: 1
AREA: SPRINTZ

DATE: 7-20-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|----------|----------|----------------|----------|---------------|----------|----------------|----------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 396 | 408 | 466 | 444 | 412 | 406 | 458 | 498 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 131.5 | 130.0 | 123.0 | 125.5 | 129.5 | 130.0 | 123.5 | 125.0 |
| (F) Moist Count | 1138 | 1092 | 1168 | 1100 | 1084 | 1120 | 1106 | 1088 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 22.7 | 21.5 | 22.0 | 21.7 | 21.3 | 22.2 | 22.0 | 21.5 |
| (I) Dry Wt. | 108.8 | 108.5 | 101.0 | 103.8 | 108.2 | 107.8 | 100.5 | 103.5 |
| (J) Proctor Wt. | 108 | 108 | 100 | 100 | 108 | 108 | 100 | 100 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 2+30 | 2+50 | 3+50 | 3+65 | 4+75 | 4+80 | 6+50 | 6+60 |
| | <u>6</u> | <u>→</u> | <u>150' Rd</u> | <u>→</u> | <u>75' Rd</u> | <u>→</u> | <u>130' Rd</u> | <u>→</u> |
| (O) Elev. | 766 | 765 | 764 | 763 | 763 | 762 | 762 | 761 |

Compaction Required 100 %

Technician VD/TO

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY - SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: See Draw

DATE: 7-20-73
DENSITY STANDARD COUNT: 221
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-----------------------|--------------|-----------------------|--------------|--------|------------------------|--------------|--------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 440 | 436 | 430 | 478 | 404 | 412 | 426 | 408 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 1260 | 1267 | 1270 | 1215 | 1305 | 1295 | 1277 | 1300 |
| (F) Moist Count | 1100 | 930 | 1000 | 920 | 1030 | 1050 | 1010 | 1030 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 21.7 | 17.8 | 19.3 | 17.5 | 20.1 | 20.6 | 19.6 | 21.3 |
| (I) Dry Wt. | 104.3 | 108.9 | 107.7 | 104.0 | 110.4 | 108.9 | 108.1 | 108.7 |
| (J) Proctor Wt. | 103 | 107 | 107 | 123 | 107 | 107 | 107 | 107 |
| (K) % Comp. I ÷ J | 101 | 102 | 101 | 101 | 103 | 102 | 101 | 102 |
| (L) % Moist | | | | | | | | |
| (N) Location | 3+00 | 3+20 | 6+00 | 6+10 | 6+30 | 3+00 | 3+15 | 6+00 |
| | 80 L E - A | A | 90 L E - A | A | 95 L E | 75' R E - A | A | 80 R E |
| (O) Elev. | 765 | 764 | 757 | 756 | 755 | 768 | 767 | 754 |

Compaction Required 100

Technician M. K.

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WPAWSLEY
JOB NO.: SEP DIRM
AREA: SEP DIRM

DATE: 9-19-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|---------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 420 | 426 | 422 | 448 | 416 | 444 | 426 | 458 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 128.5 | 128.5 | 128.5 | 125.0 | 129.0 | 125.5 | 128.0 | 124.0 |
| (F) Moist Count | 880 | 1022 | 1074 | 1176 | 1006 | 1142 | 1014 | 1096 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 16.6 | 19.9 | 21.1 | 23.6 | 19.6 | 22.7 | 19.6 | 21.7 |
| (I) Dry Wt. | 111.9 | 108.6 | 107.4 | 101.4 | 109.4 | 102.8 | 108.4 | 102.3 |
| (J) Proctor Wt. | 108 | 108 | 108 | 100 | 108 | 100 | 108 | 100 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 19+25 | 19+35 | 20+50 | 20+60 | 21+40 | 21+50 | 22+75 | 22+85 |
| | 135' Rd | → 160' Rd | → 160' Rd | → 140' Rd | → 140' Rd | → 125' Rd | → 125' Rd | → 125' Rd |
| (Q) Elev. | 756 | 755 | 756 | 755 | 756 | 757 | 756 | 757 |

Compaction Required 100%

CONFIDENTIAL BUSINESS
INFORMATION

Technician UD/70

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: W. 205 Hwy
OB NO.:
REA: SEP 10 1966

DATE: 9-20-70
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT:

| | | | | | | | |
|----------------------------------|--------------------|--------------------|--------------------|-------|--------------------|-------|---|
| A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 1 |
| B) Probe Depth | | | | | | | |
| C) Dens. Count | 432 | 424 | 428 | 454 | 448 | 452 | |
| D) C ÷ Std Count | | | | | | | |
| E) Wet Wt. (lb/ft ³) | 127.0 | 128.0 | 127.5 | 124.0 | 125.0 | 124.5 | |
| F) Moist Count | 948 | 1074 | 984 | 1072 | 1016 | 1066 | |
| G) F ÷ Std Count | | | | | | | |
| H) Wt. Moist (lbs) | 18.5 | 19.6 | 18.9 | 21.1 | 19.9 | 19.6 | |
| I) Dry Wt. | 108.5 | 108.4 | 108.6 | 102.9 | 105.1 | 104.9 | |
| J) Proctor Wt. | 108 | 109 | 108 | 100 | 105 | 105 | |
| K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | |
| L) % Moist | | | | | | | |
| N) Location | 23+50 | 23+60 | 24+10 | 24+15 | 22+75 | 22+60 | |
| | 125' EE | 130' EE | 140' EE | → | 165' EE | → | |
| O) Elev. | 757 | 758 | 758 | 759 | 756 | 757 | |

Compaction Required 100%

Technician UD/70

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: Storage Pond RR #1

DATE: 9/19/73
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 |
|-----------------------------------|-------------------|------------|-------------------|------------|--------------------|-------------------|
| (B) Probe Depth | | | | | | |
| (C) Dens. Count | 450 | 434 | 496 | 490 | 456 | 462 |
| (D) C ÷ Std Count | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 123.5 | 126.7 | 1190 | 1250 | 1240 | 1232 |
| (F) Moist Count | 1170 | 1080 | 1060 | 1090 | 1100 | 1020 |
| (G) F ÷ Std Count | | | | | | |
| (H) Wt. Moist (lbs) | 23.4 | 20.8 | 20 | 21.5 | 21.7 | 19.9 |
| (I) Dry Wt. | 100.1 | 105.9 | 100 | 103.5 | 103.3 | 102.6 |
| (J) Proctor Wt. | 90 | 105 | 70 | 90 | 103 | 103 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | |
| (N) Location | 95+75 25' RT E | 95+91 A | 97+25 30' RT E | 97+70 A | 100+50 35' RT E | 99+50 40' RT E |
| (O) Elev. | 800 | 801 | 803 | 802 | 800 | 802 |

Compaction Required 100%

CONFIDENTIAL BUSINESS
INFORMATION

Technician MR

GEORGIA POWER COMPANY - SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: MANVILLE
JOB NO.: 00000000000000000000
AREA: 00000000000000000000

DATE: 9/19/73
DENSITY STANDARD COUNT:
MOISTURE STANDARD COUNT:

| | | | | | |
|-----------------------------------|------------|----------------|----------------|----------------|--------------------|
| (A) Test Number | 9 | 10 | 11 | 12 | One More for 13 |
| (B) Probe Depth | | | | | |
| (C) Dens. Count | 396 | 424 | 452 | 410 | 420 |
| (D) C ÷ Std Count | | | | | |
| (E) Wet Wt. (lb/ft ³) | 131.5 | 128.6 | 124.0 | 129.7 | 128.5 |
| (F) Moist Count | 1180 | 1210 | 1030 | 1040 | 1100 |
| (G) F ÷ Std Count | | | | | |
| (H) Wt. Moist (lbs) | 23.6 | 24.2 | 20.1 | 20.3 | 21.7 |
| (I) Dry Wt. | 109.9 | 103.8 | 103.9 | 109.4 | 106.8 |
| (J) Proctor Wt. | 106 | 103 | 103 | 106 | 103 |
| (K) % Comp. I ÷ J | 104 | 101 | 101 | 103 | 104 |
| (L) % Moist | | | | | |
| (N) Location | 96+60 E | 96+70 517 E | 96+80 587 E | 95+50 207 E | 95+67 218 E |
| (O) Elev. | 803 | 802 | 801 | 802 | 801 |

Compaction Required 100 +

Technician MPK

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY -- SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WANSLEY
JOB NO.: 1004
AREA: 1004

DATE: 12/13/73
DENSITY STANDARD COUNT: 118.5
MOISTURE STANDARD COUNT: 1150

| | | | | | | | |
|-----------------------------------|------------------|------------------|------------------|------------------|------------------|------------------|--|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | |
| (B) Probe Depth | | | | | | | |
| (C) Dens. Count | 462 | 152 | 196 | 460 | 486 | 501 | |
| (D) C ÷ Std Count | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 123.2 | 124.7 | 125.2 | 121.0 | 120.7 | 118.5 | |
| (F) Moist Count | 1200 | 1240 | 980 | 1150 | 1130 | 1120 | |
| (G) F ÷ Std Count | | | | | | | |
| (H) Wt. Moist (lbs) | 2.40 | 25.0 | 18.9 | 23.0 | 22.4 | 24.2 | |
| (I) Dry Wt. | 99.7 | 99.7 | 106.3 | 98.0 | 98.3 | 94.3 | |
| (J) Proctor Wt. | 98 | 98 | 106 | 98.0 | 98. | 92 | |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | |
| (L) % Moist | | | | | | | |
| (N) Location | 11+25 30 RT E | 11+40 40 RT E | 12+50 40 RT E | 12+70 40 RT E | 11+70 88 LT E | 11+90 88 LT E | |
| (O) Elev. | 698 | 699 | 700 | 699 | 696 | 695 | |

Compaction Required 1004

Technician MPK

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY - SOILS
NUCLEAR DENSITY METER WORK SHEET

2-5-76

PROJECT: W. N. S. / P. 1
JOB NO.: 117731
AREA: 117731

DATE: 9-22-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 7211

| | | | | | | | | |
|-----------------------------------|-----------------|------------|-----------------|-------------|-----------------|-----------|-----------------|------------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 454 | 442 | 434 | 448 | 454 | 462 | 446 | 426 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 129.0 | 126.0 | 126.5 | 125.0 | 129.0 | 123.8 | 125.0 | 126.5 |
| (F) Moist Count | 1022 | 1094 | 1070 | 1054 | 982 | 966 | 1028 | 1030 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 19.9 | 21.5 | 21.1 | 20.8 | 18.9 | 18.7 | 17.8 | 20.3 |
| (I) Dry Wt. | 104.1 | 107.5 | 105.4 | 104.4 | 105.1 | 107.2 | 106.3 | 106.2 |
| (J) Proctor Wt. | 113 | 153 | 102 | 103 | 107 | 103 | 106.3 | 106.3 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 21+50 260' L | 21+60 → | 22+75 160' L | 22+100 → | 24+50 120' L | 2500 → | 26+50 750' L | 26+65 → |
| (O) Elev. | 739 | 760 | 762 | 16' | 714 | 713 | 764 | 763 |

Compaction Required 100%

Technician LD

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: Sup. Dam

DATE: 3-22-73
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | | | |
|-----------------------------------|-------|-------|-------|-------|-------|-------|-------|-----|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 454 | 430 | 438 | 480 | | 440 | | 178 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 124.2 | 127.2 | 127.2 | 121.2 | 125.1 | 121.5 | 127.5 | |
| (F) Moist Count | 1060 | | | | | | | |
| (G) F ÷ Std Count | | | | 1050 | 1060 | 1020 | 1040 | |
| (H) Wt. Moist (lbs) | 20.8 | 22.2 | 21.1 | 23.0 | 24 | 20.3 | 21.8 | |
| (I) Dry Wt. | 103.4 | 105.0 | 106.1 | 105.6 | 104.1 | 102.2 | 105.7 | |
| (J) Proctor Wt. | 120 | 133 | 103 | 103 | | 100 | 100 | |
| (K) % Comp. I ÷ J | 103 | 102 | 103 | 103 | 103 | 100 | 100 | |
| (L) % Moist | | | | | | | | |
| (N) Location | 26402 | 26415 | 25400 | 26415 | 25400 | 25400 | 25400 | |
| | 102+4 | 102+4 | 15272 | 102+4 | 9 | 102+4 | 102+4 | |
| (O) Elev. | 77.0 | 77.0 | 77.0 | 77 | 77.4 | 77.3 | 77.3 | 38 |

Compaction Required 115

Technician W.R.

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: Sec. 10

DATE: 9/20/77
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | | | |
|-----------------------------------|------------------|------------------|------------------|------------------|----------------|----------------|-----------------|-----------------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 400 | 418 | 576 | 480 | 540 | 520 | 418 | 430 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 131.0 | 128.7 | | 151.2 | 114.7 | 116.7 | 128.7 | 123.0 |
| (F) Moist Count | 1240 | 1020 | 820 | 1080 | 1060 | 1140 | 1010 | 1000 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 25.0 | 17.9 | 16.9 | 21.2 | 20.9 | 20.5 | 10.1 | 13.2 |
| (I) Dry Wt. | 105.0 | 110.8 | 99.1 | 100.0 | 94.0 | 76.4 | 109.1 | 107.7 |
| (J) Proctor Wt. | 104 | 107 | 98 | 78 | 94 | 84.0 | 107 | 107 |
| (K) % Comp. I ÷ J | 102 | 102 | 101 | 102 | 100 | 102 | 102 | 101 |
| (L) % Moist | | | | | | | | |
| (N) Location | 25400 100 L72 | 25415 100 L72 | 25450 100 L72 | 25470 100 L72 | 25450 25478 | 21470 25478 | 20450 50 R72 | 20470 50 R72 |
| (O) Elev. | 748 | 747 | 746 | 745 | 746 | 745 | 745 | 745 |

Compaction Required _____

Technician 7/1/77

CONFIDENTIAL BUSINESS
INFORMATION

PROJECT: WPNsley
JOB NO.: SEP 12/10
AREA: SEP 12/10

DATE: 9-22-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-----------------|-----------------|-----------------|-----------------|-----------------|-----------------|-----------------|-----------------|
| (A) Test Number | 91 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 424 | 430 | 460 | 466 | 428 | 416 | 474 | 432 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 128.0 | 127.0 | 123.5 | 122.5 | 127.5 | 129.0 | 122.0 | 122.5 |
| (F) Moist Count | 1162 | 1164 | 972 | 1128 | 1138 | 1202 | 1252 | 1202 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 23.2 | 23.2 | 18.7 | 22.4 | 22.4 | 24.0 | 17.8 | 18.6 |
| (I) Dry Wt. | 104.8 | 103.8 | 104.8 | 103.1 | 105.1 | 105.0 | 104.2 | 113.8 |
| (J) Proctor Wt. | 103 | 103 | 103 | 103 | 103 | 103 | 103 | 103 |
| (K) % Comp. I ÷ J | 140 | 140 | 140 | 140 | 140 | 140 | 140 | 140 |
| (L) % Moist | | | | | | | | |
| (N) Location | 18460 100624 | 18475 100624 | 20150 100624 | 20150 100624 | 20150 100624 | 20160 100624 | 20175 100624 | 20180 100624 |
| (O) Elev. | 732 | 733 | 734 | 735 | 736 | 737 | 738 | 739 |

Compaction Required 16096

Technician UD/70

CONFIDENTIAL BUSINESS
INFORMATION

PROJECT: W. A. S. C. 11
JOB NO.: 11111111
AREA: 11111111

DATE: 11-21-73
DENSITY STANDARD COUNT: 251
MOISTURE STANDARD COUNT: 1111

| | | | | | | | | |
|-----------------------------------|---------|---------|---------|---------|---------|---------|---------|---------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 502 | 466 | 456 | 462 | 448 | 454 | 448 | 436 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 118.5 | 123.0 | 124.0 | 123.5 | 125.0 | 124.0 | 125.0 | 126.5 |
| (F) Moist Count | 1150 | 1132 | 1168 | 1126 | 1095 | 1062 | 1078 | 1104 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 23.0 | 22.4 | 23.4 | 22.4 | 21.7 | 20.8 | 20.3 | 21.7 |
| (I) Dry Wt. | 95.5 | 100.6 | 100.6 | 101.1 | 103.3 | 103.2 | 104.7 | 104.8 |
| (J) Proctor Wt. | 100 | 100 | 100 | 100 | 103 | 103 | 103 | 103 |
| (K) % Comp. I ÷ J | 96 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | 20.0 | 20.0 | 20.0 | 20.0 | 20.0 | 20.0 | 20.0 | 20.0 |
| (N) Location | 23+50 | 23+60 | 25+00 | 25+20 | 23+00 | 22+25 | 19+00 | 19+20 |
| | 230'24" | 230'24" | 275'24" | 250'24" | 250'24" | 250'24" | 160'24" | 160'24" |
| (O) Elev. | 741 | 742 | 742 | 743 | 740 | 739 | 738 | 739 |

Technician VD

Compaction Required 100 %

CONFIDENTIAL BUSINESS
INFORMATION

UNIVERSITY OF CALIFORNIA
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Wausley
JOB NO.: SEP 2000
AREA: SEP 2000

DATE: 9-21-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-------------------|------------|--------------------|-------------|-------------------|------------|-------------------|------------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 438 | 426 | 434 | 448 | 430 | 470 | 466 | 460 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 136.0 | 127.5 | 126.5 | 125.0 | 127.0 | 122.5 | 122.5 | 123.5 |
| (F) Moist Count | 1156 | 1166 | 1098 | 1156 | 1120 | 932 | 916 | 926 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 23.2 | 23.4 | 21.7 | 23.2 | 22.2 | 17.8 | 17.5 | 17.8 |
| (I) Dry Wt. | 102.8 | 104.1 | 105.8 | 161.8 | 104.8 | 104.7 | 105.0 | 105.7 |
| (J) Proctor Wt. | 100 | 100 | 105.7 | 100 | 103.5 | | | |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 19100 30' 2" → | 19120 → | 214.50 80' 2" → | 214.50 → | 23.50 75' 2" → | 23.50 → | 23.50 20' 2" → | 23.50 → |
| (O) Elev. | 7330 | 731 | 733 | 734 | 730 | 741 | 752 | 750 |

Compaction Required 180070

CONFIDENTIAL BUSINESS
INFORMATION

Technician UD/TO

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____

JOB NO.: _____

AREA: Sup Dam

DATE: 9-21-73

DENSITY STANDARD COUNT: _____

MOISTURE STANDARD COUNT: _____

| | | | | | | | | |
|-----------------------------------|---------|---------|---------|---------|---------|---------|---------|---------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 430 | 420 | 440 | 478 | 450 | 462 | 400 | 418 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 127.2 | 128.5 | 126.0 | 121.5 | 124.5 | 123.2 | 121.0 | 128.7 |
| (F) Moist Count | 1100 | 1080 | | 1260 | 1180 | 1300 | 1090 | 1380 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 21.7 | 21.3 | 28.7 | 25.1 | 23.5 | 26.4 | 21.5 | 21.3 |
| (I) Dry Wt. | 105.5 | 107.2 | 97.3 | 96.1 | 101.0 | 96.8 | 109.5 | 106.4 |
| (J) Proctor Wt. | 103 | 105 | 94 | 94 | 98 | 94 | 107 | 105 |
| (K) % Comp. I ÷ J | 103 | 102 | 100 | 106 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 20+00 | 20+15 | 21+00 | 21+13 | 23+00 | 23+15 | 24+50 | 25+00 |
| | 25 LT E | 25 LT E | 25 LT E | 25 LT E | 25 LT E | 25 LT E | 25 LT E | 25 LT E |
| (O) Elev. | 730 | 729 | 734 | 733 | 742 | 741 | 752 | 757 |

Compaction Required 100

Technician M. J.

CONFIDENTIAL BUSINESS
INFORMATION

PROJECT: Wansley
JOB NO.:
AREA: SEP 20 1977

DATE: 9-21-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-----------------|------------|------------------|------------|-----------------|------------|------------------|------------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 448 | 454 | 456 | 442 | 438 | 448 | 462 | 464 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 125.0 | 124.0 | 124.6 | 125.5 | 126.6 | 125.0 | 123.5 | 123.0 |
| (F) Moist Count | 1212 | 1194 | 1216 | 1182 | 1232 | 1068 | 1020 | 1016 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 24.2 | 23.8 | 24.6 | 23.6 | 24.8 | 21.1 | 19.9 | 19.9 |
| (I) Dry Wt. | 100.8 | 100.2 | 99.4 | 101.9 | 101.2 | 103.9 | 103.6 | 103.1 |
| (J) Proctor Wt. | 100 | 100 | 98 | 100 | 100 | 103 | 103 | 103 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 18+50 80' 2d | 18+60 → | 19+75 175' 2d | 20+00 → | 2+75 110' 2d | 22+00 → | 23+50 100' 2d | 27+65 → |
| (O) Elev. | 757 | 756 | 759 | 755 | 762 | 761 | 762 | 761 |

Compaction Required 100%

Technician UD/TG

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY - SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: sep Dam

DATE: 9/21/73
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | | | |
|-----------------------------------|---------------------|------------|--------------------|------------|--------------------|------------|--------------------|------------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | | | | | | | | |
| (D) C ÷ Std Count | | | | | | | 492 | 510 |
| (E) Wet Wt. (lb/ft ³) | 126.0 | 127.2 | 128.2 | 129.5 | 128.7 | 126.5 | 127.7 | 117.7 |
| (F) Moist Count | 1100 | 1060 | 1110 | 1030 | 1060 | 980 | 1180 | 1050 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 21.7 | 20.8 | 22.0 | 20.1 | 20.6 | 18.9 | 23.2 | 23.5 |
| (I) Dry Wt. | 104.3 | 106.4 | 106.2 | 109.4 | 107.9 | 107.6 | 96.1 | 97.1 |
| (J) Proctor Wt. | 103 | 103 | 103 | 106 | 106 | 106 | 94 | 92.0 |
| (K) % Comp. I ÷ J | 101 | 103 | 103 | 103 | 102 | 102 | 102 | 107 |
| (L) % Moist | | | | | | | | |
| (N) Location | 26+7.5 200 R1 E- | 26+60 A | 25+25 200 R1 E- | 25+10 A | 22+50 190 R1 E- | 22+70 A | 20+00 180 RT E- | 10+55 A |
| (O) Elev. | 719.5 | 726 | 723 | 722 | 720 | 721 | 720 | 721 |

Compaction Required

100

CONFIDENTIAL BUSINESS
INFORMATION

Technician

7/1 Z

PROJECT: _____
 JOB NO.: _____
 AREA: Sep Dam

DATE: 9-20-73
 DENSITY STANDARD COUNT: _____
 MOISTURE STANDARD COUNT: _____

| | | | | | | | | |
|-----------------------------------|-----------|-----------|----------|-----------|-----------|-----------|-----------|-----------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 436 | 420 | 400 | 415 | 442 | 448 | 1 | 458 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 126.5 | 123.5 | 131.0 | 129.0 | 125.0 | 125.0 | 123.7 | |
| (F) Moist Count | 1160 | 1120 | 1000 | 1100 | 1211 | 1260 | 1100 | |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 23.2 | 21.3 | 19.3 | 21.7 | 25.0 | 25.4 | 23.1 | |
| (I) Dry Wt. | 103.3 | 107.2 | 111.7 | 107.3 | 100.7 | 99.6 | 99.7 | 100.1 |
| (J) Proctor Wt. | 100 | 103 | 108 | 104 | 98 | 98 | 98 | 98 |
| (K) % Comp. I ÷ J | 103 | 104 | 104 | 103 | 102 | 102 | 102 | 102 |
| (L) % Moist | | | | | | | | |
| (N) Location | 25+50 | 25+55 | 23+50 | 23+35 | 21+50 | 21+30 | 19+50 | 19+65 |
| | 100 L T 8 | 100 L T 8 | 90 L T 8 | 100 L T 8 | 100 L T 8 | 100 L T 8 | 105 L T 8 | 105 L T 8 |
| (O) Elev. | | 726 | 728 | 737 | 733 | 732 | 728 | 727 |

Compaction Required 100

Technician MMK

CONFIDENTIAL BUSINESS INFORMATION

NUCLEAR DENSITY METER WORK SHEET

PROJECT: W. Hawley
 JOB NO.: SPR 11/11
 AREA: SPR 11/11

DATE: 9/20/73
 DENSITY STANDARD COUNT: 231
 MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 396 | 408 | 466 | 444 | 412 | 406 | 458 | 448 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 131.5 | 130.0 | 123.0 | 125.5 | 129.5 | 130.0 | 123.5 | 125.0 |
| (F) Moist Count | 1138 | 1092 | 1168 | 1100 | 1084 | 1120 | 1106 | 1088 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 22.7 | 21.5 | 22.0 | 21.7 | 21.3 | 22.2 | 22.0 | 21.5 |
| (I) Dry Wt. | 108.8 | 108.5 | 101.0 | 103.8 | 108.2 | 109.8 | 100.5 | 103.5 |
| (J) Proctor Wt. | 108 | 108 | 100 | 100 | 108 | 108 | 100 | 100 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 2+30 | 2+50 | 3+50 | 3+65 | 4+75 | 4+80 | 6+50 | 6+60 |
| (O) Elev. | 766 | 765 | 764 | 763 | 763 | 762 | 762 | 761 |

Compaction Required 100%

Technician VD/70

CONFIDENTIAL BUSINESS INFORMATION

PROJECT: _____
 JOB NO.: _____
 AREA: Sep Dam

DATE: 9-20-73
 DENSITY STANDARD COUNT: 231
 MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|--------|-------|--------|-------|--------|--------|-------|--------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 440 | 436 | 430 | 478 | 404 | 412 | 426 | 408 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 1260 | 1267 | 1270 | 1215 | 130.5 | 129.5 | 127.7 | 130.0 |
| (F) Moist Count | 1100 | 930 | 1000 | 920 | 1030 | 1050 | 1010 | 1080 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 217 | 178 | 193 | 175 | 20.1 | 20.6 | 19.6 | 21.3 |
| (I) Dry Wt. | 104.3 | 108.9 | 107.7 | 104.0 | 110.4 | 108.9 | 108.1 | 108.7 |
| (J) Proctor Wt. | 103 | 107 | 107 | 103 | 107 | 107 | 107 | 107 |
| (K) % Comp. I ÷ J | 101 | 102 | 101 | 101 | 103 | 102 | 101 | 102 |
| (L) % Moist | | | | | | | | |
| (N) Location | 3400 | 3420 | 6400 | 6410 | 6430 | 3400 | 3415 | 6400 |
| | 8017 E | 7 | 9017 E | 7 | 9517 E | 7517 E | 7 | 8017 E |
| (O) Elev. | 765 | 764 | 757 | 756 | 755 | 768 | 767 | 754 |

Compaction Required 100

Technician M. K.

CONFIDENTIAL BUSINESS
 INFORMATION

NUCLEAR DENSITY METER WORK SHEET

PROJECT: W. 20.70
 JOB NO.: 500000
 AREA: 500000

DATE: 9-20-70
 DENSITY STANDARD COUNT: 271
 MOISTURE STANDARD COUNT: 1071

| | | | | | | | |
|-----------------------------------|--------------------|--------------------|--------------------|-------|--------------------|-------|---|
| (A) Test Number | 7 | 10 | 11 | 12 | 13 | 14 | 1 |
| (B) Probe Depth | | | | | | | |
| (C) Dens. Count | 432 | 424 | 428 | 454 | 448 | 452 | |
| (D) C ÷ Std Count | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 127.0 | 128.0 | 127.5 | 124.0 | 125.0 | 128.5 | |
| (F) Moist Count | 948 | 1014 | 984 | 1072 | 1016 | 1066 | |
| (G) F ÷ Std Count | | | | | | | |
| (H) Wt. Moist (lbs) | 18.5 | 19.6 | 18.5 | 21.1 | 19.9 | 19.6 | |
| (I) Dry Wt. | 108.5 | 108.4 | 108.6 | 102.9 | 105.1 | 104.9 | |
| (J) Proctor Wt. | 108 | 108 | 108 | 100 | 105 | 105 | |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | |
| (L) % Moist | | | | | | | |
| (N) Location | 23450 | 23460 | 24400 | 24415 | 22475 | 22460 | |
| | 125' EE | 130' EE | 140' EE | → | 165' EE | → | |
| (O) Elev. | 757 | 758 | 758 | 758 | 756 | 757 | |

Compaction Required 100%

Technician UD/

CONFIDENTIAL BUSINESS
 INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: W. P. O. S. E. 1
JOB NO.: 301-1000
AREA: 301-1000

DATE: 9-19-73
DENSITY STANDARD COUNT: 221
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 420 | 426 | 422 | 448 | 416 | 444 | 426 | 458 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 128.5 | 128.5 | 128.5 | 125.0 | 129.0 | 125.5 | 128.0 | 124.0 |
| (F) Moist Count | 880 | 1022 | 1074 | 1176 | 1006 | 1142 | 1014 | 1096 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 16.6 | 19.9 | 21.1 | 23.6 | 19.6 | 22.7 | 19.6 | 21.7 |
| (I) Dry Wt. | 111.9 | 108.6 | 107.4 | 101.4 | 109.4 | 102.8 | 108.4 | 102.3 |
| (J) Proctor Wt. | 108 | 108 | 108 | 100 | 108 | 100 | 108 | 100 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 19+25 | 19+35 | 20+50 | 20+60 | 21+40 | 21+50 | 22+75 | 22+85 |
| (O) Elev. | 756 | 755 | 756 | 755 | 756 | 757 | 756 | 757 |

Compaction Required 100%

Technician UD/TO

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WANSLEY
JOB NO.: 245
AREA: 1004

DATE: 9/13/73
DENSITY STANDARD COUNT:
MOISTURE STANDARD COUNT:

| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 |
|-----------------------------------|------------------|------------------|-------------------|-------------------|-------------------|-------------------|
| (B) Probe Depth | | | | | | |
| (C) Dens. Count | 462 | 452 | 446 | 480 | 186 | 501 |
| (D) C ÷ Std Count | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 123.2 | 124.7 | 125.2 | 121.0 | 120.7 | 118.5 |
| (F) Moist Count | 1200 | 1240 | 980 | 1150 | 1130 | 121 |
| (G) F ÷ Std Count | | | | | | |
| (H) Wt. Moist (lbs) | 200 | 25.0 | 18.9 | 23.0 | 22.4 | 24.2 |
| (I) Dry Wt. | 99.2 | 99.7 | 106.3 | 75.0 | 98.3 | 94.3 |
| (J) Proctor Wt. | 98 | 98 | 106 | 986 | 98 | 92 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | |
| (N) Location | 11+25 30 RT E | 11+40 30 RT E | 12+50 40' RT E | 12+70 40' RT E | 11+70 88' RT E | 11+90 88' RT E |
| (O) Elev. | 698 | 699 | 700 | 699 | 696 | 695 |

Compaction Required 1004

Technician MMK

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY - SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: VERBURN

DATE: 9-12-73
DENSITY STANDARD COUNT: 251
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|------------------|------------------|------------|------------|------------------|------------|------------|------------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 456 | 466 | 472 | 468 | 482 | 474 | 480 | 478 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 124.0 | 123.0 | 122.0 | 123.0 | 121.6 | 122.0 | 121.0 | 121.5 |
| (F) Moist Count | 1134 | 1242 | 1202 | 1216 | 1154 | 1062 | 1084 | 1106 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 22.4 | 25.0 | 24.0 | 24.6 | 23.0 | 20.8 | 21.3 | 22.0 |
| (I) Dry Wt. | 101.6 | 98.0 | 98.0 | 99.4 | 98.0 | 101.2 | 99.7 | 98.5 |
| (J) Proctor Wt. | 98 | 98 | 98 | 98 | 98 | 78 | 98 | 98 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 700 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 10450 45' R L | 10410 55' R L | 10475 L | 10485 → | 11450 60' R L | 11450 → | 11475 → | 11485 → |
| (O) Elev. | 687 | 688 | 688 | 687 | 685 | 686 | 687 | 687 |

Compaction Required 100%

Technician OD/17

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: 58-121111
AREA: _____

DATE: 9-17-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|------------------|------------------|-----------------|-----------------|------------------|------------|-------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 462 | 456 | 486 | 474 | 478 | 454 | 472 | 472 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 123.0 | 124.0 | 120.5 | 122.0 | 121.5 | 124.6 | 122.0 | 122.0 |
| (F) Moist Count | 1018 | 1032 | 926 | 952 | 1090 | 1122 | 1028 | 1002 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 22.2 | 22.4 | 17.8 | 18.5 | 21.5 | 22.2 | 24.1 | 19.3 |
| (I) Dry Wt. | 100.8 | 101.6 | 102.7 | 103.5 | 100 | 101.8 | 101.9 | 102.7 |
| (J) Proctor Wt. | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (K) % Comp. $I \div J$ | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 22+00 120' Rk | 22+15 100' Rk | 22+00 30' Rk | 22+10 45' Rk | 20+75 100' Rk | 20+85 → | 19+36 | 17+40 |
| (O) Elev. | 744 | 745 | 742 | 743 | 742 | 743 | 740 | 741 |

Compaction Required 100%

CONFIDENTIAL BUSINESS
INFORMATION

Technician

U.D. 40

GEORGIA POWER COMPANY - SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: S.F.P. DAM

DATE: 9-11-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|---------|-------|---------|-------|--------|-------|--------|-------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 450 | 432 | 438 | 446 | 430 | 422 | 390 | 408 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 124.5 | 127.0 | 126.0 | 125.0 | 127.5 | 128.0 | 132.5 | 130.0 |
| (F) Moist Count | 1112 | 1076 | 998 | 1040 | 1148 | 1022 | 1182 | 1102 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 22.0 | 21.3 | 19.3 | 20.3 | 23.0 | 19.5 | 23.6 | 21.7 |
| (I) Dry Wt. | 102.5 | 105.7 | 106.7 | 104.7 | 104.5 | 109.1 | 108.9 | 108.3 |
| (J) Proctor Wt. | 100 | 105 | 105 | 105 | 105 | 106.0 | 105 | 108 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 103 | 106 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 19700 | 19715 | 20195 | 21100 | 22785 | 23400 | 25700 | 25415 |
| | 125' RL | → | 150' RL | → | 90' RL | → | 40' RL | → |
| (O) Elev. | 734 | 735 | 736 | 737 | 737 | 738 | 737 | 735 |

Compaction Required 100%

Technician VD/JO

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY - BUILDS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: SEP 2010

DATE: 9-11-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-----------|-------|--------|-------|---------|-------|---------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 390 | 412 | 402 | 418 | 430 | 426 | 434 | 458 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 132.5 | 129.5 | 131.0 | 128.5 | 127.0 | 128.0 | 126.5 | 123.5 |
| (F) Moist Count | 974 | 988 | 904 | 942 | 1050 | 1160 | 1098 | 1074 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 18.7 | 19.1 | 17.1 | 18.0 | 20.6 | 23.2 | 21.7 | 21.1 |
| (I) Dry Wt. | 113.8 | 110.4 | 113.9 | 110.5 | 106.4 | 104.8 | 104.8 | 102.4 |
| (J) Proctor Wt. | 110 | 110 | 110 | 110 | 105 | 105 | 105 | 105 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 98 |
| (L) % Moist | | | | | | | | |
| (N) Location | 12+25 | 12+35 | 13+30 | 13+60 | 14+25 | 14+50 | 14+50 | 14+20 |
| | 120' Rd → | → | 90' Rd | → | 200' Rd | → | 150' Rd | → |
| (O) Elev. | 694 | 693 | 692 | 691 | 690 | 689 | 678 | 677 |

Compaction Required

100 %

Technician

UD / 70

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: PLANT WATKINSLEY
JOB NO.:
AREA: SEPTEMBER

DATE: 9/10/73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|----------|-------|-------|-------|-------|-------|-------|-------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | 6 inches | → | → | → | → | → | → | → |
| (C) Dens. Count | 422 | 432 | 486 | 466 | 418 | 426 | 458 | 434 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 128.2 | 127.0 | 120.5 | 122.7 | 128.7 | 127.7 | 123.7 | 126.7 |
| (F) Moist Count | 1050 | 920 | 930 | 890 | 1020 | 980 | 1000 | 910 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 20.6 | 17.5 | 17.8 | 16.9 | 19.9 | 18.9 | 19.3 | 17.3 |
| (I) Dry Wt. | 107.6 | 109.5 | 102.7 | 105.8 | 108.8 | 108.8 | 105.4 | 109.4 |
| (J) Proctor Wt. | 108 | 108 | 103 | 103 | 108 | 108 | 103 | 108 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 3+00 | 3+15 | 5+00 | 5+15 | 3+50 | 3+65 | 5+50 | 5+75 |
| (O) Elev. | 100.174 | 76.3 | 75.5 | 75.4 | 76.0 | 75.8 | 75.0 | 74.8 |

Compaction Required 100

Technician M.K.

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: Sap Ram

DATE: 9/10/73
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
|-----------------------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 434 | 424 | 496 | 454 | 454 | 462 | 440 | 430 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 126.7 | 128.0 | 119.0 | 124.2 | 124.2 | 123.2 | 126.0 | 127.2 |
| (F) Moist Count | 900 | 1010 | 960 | 840 | 920 | 980 | 1000 | 990 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 17.1 | 17.6 | 18.5 | 15.7 | 17.5 | 18.2 | 19.3 | 19.1 |
| (I) Dry Wt. | 109.6 | 108.4 | 100.5 | 108.5 | 106.7 | 109.3 | 106.7 | 108.1 |
| (J) Proctor Wt. | 108 | 128 | 100 | 108 | 106 | 103 | 106 | 106 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 24+25 250'179 | 24+37 220'179 | 22+25 220'179 | 22+40 230'179 | 20+40 230'179 | 20+65 215'179 | 19+00 215'179 | 19+25 215'179 |
| (O) Elev. | 739 | 738 | 736 | 735 | 733 | 732 | 727 | 728 |

Compaction Required 105

Technician M. K

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: DAWK
JOB NO.:
AREA:

DATE: 7-10-77
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-------|-------|--------|--------|--------|-------|-------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 476 | 468 | 466 | 452 | 478 | 470 | 484 | 466 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 121.5 | 122.5 | 123.0 | 124.5 | 121.5 | 122.0 | 120.5 | 123.0 |
| (F) Moist Count | 936 | 848 | 986 | 985 | 984 | 788 | 1090 | 794 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 18.0 | 15.8 | 19.1 | 13.1 | 16.1 | 18.1 | 21.5 | 19.1 |
| (I) Dry Wt. | 103.5 | 106.7 | 103.9 | 105.4 | 105.4 | 102.7 | 99.0 | 105.7 |
| (J) Proctor Wt. | 107 | 106.3 | 103 | 102 | 105 | 103 | 98 | 103 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 11-50 | 12-10 | 12-22 | 12-35 | 13-40 | 13-50 | 14-50 | 15-50 |
| | 40-24 | 55-24 | 108-74 | 115-74 | 100-24 | 90-24 | 50-24 | 60-24 |
| (O) Elev. | 690 | 689 | 791 | 692 | 692 | 691 | 690 | 691 |

Compaction Required 690

Technician UD

CONFIDENTIAL BUSINESS
INFORMATION

PROJECT: _____
JOB NO.: _____
AREA: Sq. Data

DATE: 5/18/73
DENSITY / STANDARD COUNT:
MOISTURE STANDARD COUNT

| | | | | | | | | | |
|-----------------------------------|----------------|----------------|--|--|--|--|--|--|--|
| (A) Test Number | 9 | 10 | | | | | | | |
| (B) Probe Depth | | | | | | | | | |
| (C) Dens. Count | 44 | 460 | | | | | | | |
| (D) C ÷ Std Count | | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 125.5 | 123.5 | | | | | | | |
| (F) Moist Count | 940 | 1250 | | | | | | | |
| (G) F ÷ Std Count | | | | | | | | | |
| (H) Wt. Moist (lbs) | 18.0 | 25.2 | | | | | | | |
| (I) Dry Wt. | 107.5 | 98.3 | | | | | | | |
| (J) Proctor Wt. | 106 | 98 | | | | | | | |
| (K) % Comp. I ÷ J | 100 | 100 | | | | | | | |
| (L) % Moist | | | | | | | | | |
| (N) Location | 24+00 77290 | 24+20 77290 | | | | | | | |
| (O) Elev. | 740 | 739 | | | | | | | |

Compaction Required

Technician

**CONFIDENTIAL BUSINESS
INFORMATION**

GLORIAN POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: 1
JOB NO.: 1
AREA: Seppan

DATE: 2/10/73
DENSITY STANDARD COUNT: 1
MOISTURE STANDARD COUNT: 1

| | | | | | | | | |
|-----------------------------------|---------|-------|-------|-------|-------|-------|-------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 416 | 410 | 434 | 418 | 440 | 444 | 428 | 411 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 129.0 | 129.5 | 126.5 | 128.7 | 126.2 | 125.5 | 127.5 | 121.7 |
| (F) Moist Count | 1010 | 1090 | 950 | 980 | 1151 | 950 | 990 | 1250 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 19.6 | 21.5 | 18.2 | 18.9 | 23.2 | 18.2 | 21 | 25.2 |
| (I) Dry Wt. | 109.4 | 108.0 | 108.3 | 109.8 | 103.0 | 107.3 | 108.2 | 97.0 |
| (J) Proctor Wt. | 107 | 107 | 107 | 107 | 100 | 106 | 110 | 91 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 578/104 | 13420 | 14100 | 1415 | 19475 | 19490 | 22410 | 22415 |
| (O) Elev. | 694 | 693 | 692 | 691 | 690 | 689 | 688 | 687 |

Compaction Required 100

Technician MMK

CONFIDENTIAL BUSINESS
INFORMATION

NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____

JOB NO.: _____

AREA: See Dam

DATE: 9/10/73

DENSITY STANDARD COUNT: _____

MOISTURE STANDARD COUNT: _____

| (A) Test Number | Nine | Ten | Eleven | Twelve | Thirteen | Fourteen | Fifteen | Sixteen |
|-----------------------------------|--------------------|------------|--------------------|------------|--------------------|------------|---------|---------|
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 416 | 404 | 438 | 432 | 436 | 446 | | |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 129.0 | 130.5 | 126.0 | 127.0 | 126.5 | 125.2 | | |
| (F) Moist Count | 1150 | 1210 | 1190 | 1300 | 1310 | 1290 | | |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 23.0 | 24.2 | 23.8 | 26.4 | 26.5 | 26.2 | | |
| (I) Dry Wt. | 106.0 | 106.3 | 102.2 | 100.6 | 100.0 | 99.0 | | |
| (J) Proctor Wt. | 103 | 103 | 100 | 100 | 98 | 98 | | |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | | |
| (L) % Moist | | | | | | | | |
| (N) Location | 10+00 75 RT E → | 10+15 → | 11+00 80 RT E → | 11+15 → | 12+00 90 RT E → | 12+21 → | | |
| (O) Elev. | 690 | 688 | 689 | 687 | 687 | 685 | | |

Compaction Required 100

Technician MM K

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: Sep Dam

DATE: 9-10-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|---------|-------|----------|-------|----------|-------|----------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 454 | 432 | 512 | 512 | 436 | 480 | 458 | 442 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 124.2 | 127.0 | 117.5 | 117.5 | 126.5 | 121.2 | 123.7 | 125.7 |
| (F) Moist Count | 1300 | 1360 | 960 | 960 | 910 | 1120 | 808 | 910 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 26.4 | 27.8 | 18.5 | 18.5 | 17.3 | 19.9 | 15.0 | 17.3 |
| (I) Dry Wt. | 97.8 | 99.2 | 99.0 | 99.0 | 109.2 | 101.3 | 108.7 | 108.4 |
| (J) Proctor Wt. | 98.0 | 98.0 | 98 | 98.0 | 107 | 98.0 | 107.0 | 107.0 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 10+50 | 10+70 | 10+00 | 10+15 | 11+50 | 11+60 | 11+70 | 11+50 |
| | 50 RT 9 | → | 250 RT 9 | → | 240 RT 9 | → | 230 RT 9 | → |
| (O) Elev. | 685 | 686 | 705 | 704 | 701 | 700 | 699 | 705 |

Core →

Compaction Required 100

CONFIDENTIAL BUSINESS INFORMATION

Technician W. K.

NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
 JOB NO.: _____
 AREA: Generation 3

DATE: 9-8-73
 DENSITY STANDARD COUNT: 231
 MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|---------|---------|---------|---------|--------|--------|--------|--------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 400 | 410 | 448 | 430 | 418 | 418 | 426 | 412 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 131.0 | 129.7 | 125.0 | 127.2 | 128.7 | 128.7 | 127.7 | 129.5 |
| (F) Moist Count | 1020 | 1010 | 990 | 1000 | 920 | 1028 | 940 | 1030 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 19.9 | 19.6 | 19.1 | 19.3 | 17.5 | 19.9 | 18.0 | 20.1 |
| (I) Dry Wt. | 111.1 | 110.1 | 105.9 | 107.9 | 111.2 | 108.8 | 109.7 | 109.4 |
| (J) Proctor Wt. | 109 | 109 | 106 | 106.0 | 109 | 109 | 109 | 109 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 3+00 | 3+20 | 5+00 | 5+19 | 4+50 | 4+65 | 3+00 | 3+21 |
| | 150 L7E | 150 L7E | 160 L7E | 160 L7E | 17E 20 | 17E 20 | 15 R7E | 15 R7E |
| (O) Elev. | 750 | 759 | 749 | 748 | 748 | 749 | 762 | 761 |

Compaction Required 100

CONFIDENTIAL BUSINESS
INFORMATION

Technician

271

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WANSLEY
JOB NO.: 512 DREA
AREA: 512 DREA

DATE: 9-8-73
DENSITY STANDARD COUNT: 731
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|---------------|----------------|---------------|---------------|----------------|----------------|----------------|----------------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 402 | 412 | 408 | 414 | 502 | 486 | 492 | 472 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 131.0 | 129.5 | 130.0 | 129.5 | 118.5 | 120.5 | 120.0 | 122.0 |
| (F) Moist Count | 988 | 926 | 962 | 934 | 1038 | 1072 | 1046 | 1108 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 19.1 | 17.8 | 18.5 | 17.8 | 20.3 | 21.1 | 20.6 | 22.0 |
| (I) Dry Wt. | 111.9 | 111.7 | 111.5 | 111.7 | 98.2 | 99.1 | 99.4 | 100.0 |
| (J) Proctor Wt. | 110 | 110 | 110 | 110 | 98 | 98 | 98 | 98 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 7+90 95' L | 7+80 100' L | 6+15 75' R | 6+10 85' R | 24+00 40' R | 24+10 30' R | 25+15 60' L | 25+25 50' L |
| (O) Elev. | 732 | 733 | 737 | 738 | 740 | 741 | 743 | 744 |

Compaction Required 100

Technician UD/7c

CONFIDENTIAL BUSINESS
INFORMATION

NUCLEAR DENSITY METER WORK SHEET

PROJECT:
 JOB NO.:
 AREA: Sap Dava

DATE: 9/8/73
 DENSITY STANDARD COUNT:
 MOISTURE STANDARD COUNT:

| | | | | | | | |
|-----------------------------------|--------|--------|-------|-------|-------|-------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| (B) Probe Depth | | | | | | | |
| (C) Dens. Count | 418 | 435 | 410 | 434 | 462 | 458 | 504 |
| (D) C ÷ Std Count | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 128.5 | 127.0 | 129.7 | 126.7 | 123.2 | 123.7 | 115.2 |
| (F) Moist Count | 980 | 960 | 1000 | 960 | 1120 | 1190 | 1060 |
| (G) F ÷ Std Count | | | | | | | |
| (H) Wt. Moist (lbs) | 12.9 | 18.5 | 19.3 | 18.5 | 22.2 | 23.8 | 20.3 |
| (I) Dry Wt. | 117.6 | 108.5 | 110.4 | 108.2 | 111.0 | 117.9 | 98.2 |
| (J) Proctor Wt. | 102 | 108 | 110 | 110 | 100 | 100 | 98 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | |
| (N) Location | 8+40 | 8+60 | 7+50 | 7+65 | 23+50 | 23+60 | 20+50 |
| | 100.78 | 100.78 | 75.78 | 75.78 | 75.78 | 75.78 | 75.78 |
| (O) Elev. | 730 | 739 | 735 | 734 | 738 | 737 | 730 |

Compaction Required 100

Technician W K V.L.

CONFIDENTIAL BUSINESS
 INFORMATION

NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
 JOB NO.: _____
 AREA: Sep Dam

DATE: 9/8/73
 DENSITY STANDARD COUNT: _____
 MOISTURE STANDARD COUNT: _____

| | | | | | | | | |
|-----------------------------------|------------------|------------------|------------------|------------------|------------------|------------------|-----------------|------------------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 416 | 404 | 492 | 520 | 420 | 436 | 414 | 422 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 129.0 | 130.5 | 119.7 | 116.7 | 128.5 | 126.2 | 129.0 | 128.0 |
| (F) Moist Count | 1010 | 1030 | 860 | 990 | 980 | 890 | 1020 | 1040 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 19.6 | 20.1 | 16.1 | 19.1 | 18.9 | 16.9 | 19.9 | 20.3 |
| (I) Dry Wt. | 108.4 | 110.4 | 103.6 | 97.6 | 109.6 | 109.3 | 108.1 | 107.7 |
| (J) Proctor Wt. | 106 | 109 | 103 | 98 | 109 | 109 | 106 | 106 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 20+00 200 L19 | 20+15 200 L19 | 23+00 175 L19 | 23+37 200 L19 | 24+50 150 L19 | 24+65 200 L19 | 23+00 80 L19 | 23+19 200 L19 |
| (O) Elev. | 731 | 729 | 734 | 732 | 740 | 739 | 734 | 735 |

Compaction Required 100

Technician M R

CONFIDENTIAL BUSINESS
 INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WAB2/04
JOB NO.:
AREA:

DATE: 9-7-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-----------|------------|------------|------------|-----------|-----------|------------|------------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 388 | 394 | 396 | 406 | 418 | 426 | 460 | 416 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 132.5 | 132.0 | 131.5 | 130.0 | 129.0 | 127.0 | 131.0 | 127.6 |
| (F) Moist Count | 896 | 1140 | 1038 | 176 | 980 | 998 | 1000 | 966 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 17.1 | 23.7 | 20.3 | 18.9 | 18.9 | 19.3 | 19.3 | 18.7 |
| (I) Dry Wt. | 115.4 | 109.3 | 111.2 | 111.1 | 110.1 | 109.7 | 112.7 | 110.3 |
| (J) Proctor Wt. | 115 | 110 | 110 | 110 | 110 | 110 | 110 | 110 |
| (K) % Comp. I ÷ J | 116 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 3+30 | 3+60 | 4+75 | 4+96 | 6+00 | 6+10 | 7+10 | 7+20 |
| | 75' L. E. | 100' L. E. | 100' R. E. | 115' R. E. | 80' L. E. | 70' L. E. | 150' L. E. | 175' L. E. |
| (O) Elev. | 760 | 759 | 756 | 755 | 749 | 748 | 745 | 744 |

Compaction Required 100%

Technician VY-11

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIN POWER COMPANY - SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: Separation Camp

DATE: 2/7/73
DENSITY/STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|----------------|-----------|-----------------|-----------|-----------------|-----------------|-----------------|-------------------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6 | → | → | → | → | → | → | → |
| (C) Dens. Count | 428 | 430 | 404 | 418 | 426 | 488 | 420 | 430 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 127.5 | 127.2 | 130.5 | 128.7 | 127.7 | 120.2 | 128.5 | 127.2 |
| (F) Moist Count | 970 | 1030 | 1000 | 990 | 808 | 860 | 990 | 1040 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 18.7 | 20.1 | 19.3 | 19.1 | 15.0 | 16.1 | 19.1 | 20.3 |
| (I) Dry Wt. | 108.8 | 107.1 | 111.2 | 109.6 | 112.7 | 104.1 | 107.9 | 106.9 |
| (J) Proctor Wt. | 108 | 105 | 108 | 108 | 108 | 103 | 108 | 105 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 3+00 50 LTR | 3+16 → | 5+00 75' LTR | 5+15 → | 3+20 100 RTR | 3+00 100 RTR | 6+00 125 RTR | 6+20- 125' RTR |
| (O) Elev. | 756 | 755 | 750 | 749 | 758 | 757 | 747 | 746 |

14.80

Compaction Required

Technician

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY - BUILD
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: Sap Dam

DATE: 9/6/73
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | | | |
|-----------------------------------|-----------------|-----------------|-----------------|-----------------|------------------|------------------|-----------------|-----------------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 432 | 450 | 408 | 426 | 472 | 418 | 420 | 442 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 127.0 | 124.7 | 130.0 | 127.7 | 122.2 | 128.7 | 128.5 | 125.8 |
| (F) Moist Count | 1020 | 920 | 1110 | 980 | 1000 | 1060 | 950 | 1110 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 19.9 | 17.5 | 22.0 | 18.9 | 19.3 | 20.8 | 18.2 | 22.0 |
| (I) Dry Wt. | 107.1 | 106.2 | 108.0 | 108.8 | 102.9 | 107.9 | 110.3 | 103.8 |
| (J) Proctor Wt. | 103 | 103 | 108 | 108 | 103 | 108 | 108 | 103 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 4+00 75 L7 E | 4+20 75 L7 E | 6+00 75 L7 E | 6+15 75 L7 E | 4+50 100 R7 E | 4+65 100 R7 E | 6+50 75 L7 E | 6+65 75 L7 E |
| (O) Elev. | 75.3 | 75.2 | 74.6 | 74.5 | 75.9 | 75.8 | 74.5 | 74.4 |

Compaction Required 100

Technician M. K.

CONFIDENTIAL BUSINESS
INFORMATION

NUCLEAR DENSITY METER WORK SHEET

PROJECT: WAWSL04
 JOB NO.: 500
 AREA: 500

DATE: 9-7-72
 DENSITY STANDARD COUNT: 231
 MOISTURE STANDARD COUNT: 1251

| | | | | | | | | |
|-----------------------------------|--------|--------|--------|----------|--|--|--|--|
| (A) Test Number | 17 | 18 | 19 | 20 | | | | |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 462 | 474 | 478 | 466 | | | | |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 123.0 | 122.0 | 121.5 | 123.0 | | | | |
| (F) Moist Count | 1130 | 1104 | 1026 | 1146 | | | | |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 22.4 | 21.7 | 20.8 | 23.0 | | | | |
| (I) Dry Wt. | 100.6 | 100.3 | 101.4 | 100.0 | | | | |
| (J) Proctor Wt. | 100 | 100 | 100 | 100 | | | | |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | | | | |
| (L) % Moist | | | | | | | | |
| (N) Location | 237-75 | 237-85 | 25-100 | 25-15 | | | | |
| | 85' Rd | 60' Rd | φ | 10' L.E. | | | | |
| (O) Elev. | 739 | 740 | 741 | 742 | | | | |

Compaction Required 100%

Technician UD/78

CONFIDENTIAL BUSINESS INFORMATION

NUCLEAR DENSITY METER WORK SHEET

PROJECT: WMS/201
 JOB NO.: SEP 10/10
 AREA: SEP 10/10

DATE: 9.6.73
 DENSITY STANDARD COUNT: 231
 MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-----------|-----------|-----------|-----------|-------|-----------|----------|----------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 506 | 478 | 488 | 492 | 466 | 474 | 450 | 436 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 118.0 | 121.5 | 120.0 | 124.0 | 123.0 | 122.0 | 124.5 | 126.5 |
| (F) Moist Count | 1016 | 1166 | 1008 | 1026 | 1074 | 1052 | 1060 | 1098 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 19.6 | 23.4 | 19.6 | 20.1 | 21.1 | 20.6 | 20.8 | 21.7 |
| (I) Dry Wt. | 97.4 | 98.1 | 100.4 | 99.9 | 101.9 | 101.4 | 103.7 | 105.8 |
| (J) Proctor Wt. | 98 | 98 | 98 | 98 | 100 | 100 | 100 | 105.3 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 28+00 | 28+20 | 27+50 | 27+60 | 20+00 | 20+15 | 21+75 | 21+95 |
| (O) Elev. | 40' 2 1/2 | 50' 2 1/2 | 80' 2 1/2 | 90' 2 1/2 | φ | 20' 2 1/2 | 150' R 6 | 140' R 1 |
| | 742 | 741 | 740 | 739 | 738 | 737 | 737 | 732 |

Compaction Required 100%

Technician UD/70

CONFIDENTIAL BUSINESS
 INFORMATION

NUCLEAR DENSITY METER WORK SHEET

PROJECT: W. Wash 14
 JOB NO.: 1
 AREA: D114

DATE: 9-6-73
 DENSITY STANDARD COUNT: 231
 MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|----------------|----------------|-----------------|-----------------|----------------|----------------|-----------------|-----------------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6 | | | | | | | |
| (C) Dens. Count | 444 | 428 | 410 | 426 | 422 | 408 | 410 | 416 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 125.5 | 127.5 | 129.5 | 127.5 | 128.0 | 130.0 | 129.5 | 129.0 |
| (F) Moist Count | 950 | 984 | 920 | 902 | 956 | 1028 | 990 | 980 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 18.2 | 18.9 | 17.5 | 17.1 | 18.5 | 20.1 | 19.1 | 18.9 |
| (I) Dry Wt. | 107.3 | 108.6 | 117.0 | 110.4 | 109.5 | 109.9 | 110.4 | 110.1 |
| (J) Proctor Wt. | 106.3 | 106.3 | 110 | 110 | 110 | 110 | 110 | 110 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 4115 60' Rd | 4425 50' Rd | 5450 185' Rd | 5440 200' Rd | 7400 40' Rd | 7410 30' Rd | 7490 140' Rd | 8400 150' Rd |
| (O) Elev. | 754 | 753 | 746 | 747 | 737 | 736 | 728 | 727 |

Compaction Required 100%

Technician D. J. / TD

CONFIDENTIAL BUSINESS INFORMATION

GEORGIA POWER COMPANY - SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Plant Wansley
JOB NO.:
AREA: Sep Dam

DATE: 9/6/73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT:

| | | | | | | | | |
|-----------------------------------|-----------------|-----------|-----------|-----------|------------------|-----------------|----------------|----------------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6 inches | | | | | | | |
| (C) Dens. Count | 420 | 430 | 434 | 420 | 428 | 418 | 400 | 436 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 128.5 | 127.2 | 126.7 | 128.5 | 127.5 | 128.7 | 131.0 | 126.2 |
| (F) Moist Count | 990 | 960 | 1120 | 1000 | 1000 | 1010 | 1100 | 1110 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 19.1 | 18.5 | 22.2 | 19.3 | 19.3 | 19.6 | 21.7 | 22.0 |
| (I) Dry Wt. | 109.4 | 108.7 | 104.5 | 109.2 | 108.2 | 109.1 | 109.3 | 104.2 |
| (J) Proctor Wt. | 108 | 108 | 103 | 108 | 108 | 108 | 108 | 103 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 5+40 250 L7E | 5+30 A | 5+50 E | 5+40 E | 4+00 R1E 100' | 4+20 R1E 90' | 4+70 50 L7E | 4+90 50 L7E |
| (O) Elev. | 795 | 794 | 747 | 746 | 752 | 757 | 750 | 749 |

Compaction Required 100

Technician 777 41

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY - SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: Sap Dam

DATE: 9/6/73
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | | |
|-----------------------------------|-----------------|-----------------|----------------|----------------|-----------------|-----------------|--|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | |
| (B) Probe Depth | | | | | | | |
| (C) Dens. Count | 424 | 454 | 410 | 418 | 452 | 430 | |
| (D) C ÷ Std Count | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 128.0 | 124.2 | 129.7 | 128.7 | 124.2 | 127.2 | |
| (F) Moist Count | 950 | 960 | 1060 | 990 | 950 | 1020 | |
| (G) F ÷ Std Count | | | | | | | |
| (H) Wt. Moist (lbs) | 18.2 | 18.5 | 20.8 | 19.1 | 18.2 | 19.9 | |
| (I) Dry Wt. | 109.8 | 105.7 | 108.9 | 109.6 | 106.0 | 107.3 | |
| (J) Proctor Wt. | 108 | 106 | 108 | 108 | 106 | 106 | |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | |
| (L) % Moist | | | | | | | |
| (N) Location | 7400 150 LTR | 7415 155 LTR | 7450 50 LTR | 7465 55 LTR | 8400 150 RTR | 8410 150 RTR | |
| (O) Elev. | 735 | 736 | 730 | 729 | 727 | 726 | |

Compaction Required 100

Technician MM

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: W/1203
JOB NO.: 2211000
AREA: 2211000

DATE: 9-6-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-------------------|--------------------|------------------|------------------|-------------------|------------------|------------|------------------|
| (A) Test Number | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 484 | 466 | 476 | 518 | 506 | 458 | 478 | 514 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 121.0 | 123.0 | 121.5 | 117.0 | 118.5 | 119.0 | 121.5 | 117.5 |
| (F) Moist Count | 1074 | 1022 | 1060 | 988 | 1004 | 1022 | 1052 | 976 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 17.6 | 20.1 | 20.8 | 19.1 | 19.3 | 19.9 | 20.6 | 18.9 |
| (I) Dry Wt. | 101.4 | 102.9 | 100.7 | 97.9 | 99.2 | 97.9 | 100.9 | 98.6 |
| (J) Proctor Wt. | 100 | 100 | 100 | 98 | 98.2 | 98 | 100 | 98 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 25±00 120' R L | 25±15' 125' R L | 26±00 80' R L | 26±20 70' R L | 26±150 60' L L | 26±10 50' L L | 26±10 L | 26±10 20' L L |
| (O) Elev. | 73.8 | 73.9 | 74.2 | 74.4 | 74.4 | 74.6 | 74 | 74.1 |

Compaction Required 100 %

Technician V.D./T.D.

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: 602205/En
JOB NO.: SPN 1.00
AREA: 1.00

DATE: 9-5-75
DENSITY STANDARD COUNT:
MOISTURE STANDARD COUNT:

| | | | | | | | | |
|-----------------------------------|----------|----------|-------|---------|---------|---------|--|--|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | | |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 426 | 438 | 412 | 406 | 424 | 438 | | |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 127.5 | 126.0 | 125.5 | 130.0 | 128.0 | 126.0 | | |
| (F) Moist Count | 1002 | 898 | 942 | 992 | 926 | 884 | | |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 19.3 | 17.1 | 18.0 | 19.1 | 17.8 | 16.6 | | |
| (I) Dry Wt. | 148.2 | 168.9 | 111.5 | 110.9 | 110.2 | 109.4 | | |
| (J) Proctor Wt. | 108 | 108 | 110 | 110 | 110 | 110 | | |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | | |
| (L) % Moist | | | | | | | | |
| (N) Location | 6450 | 6460 | 7400 | 7415 | 8400 | 8415 | | |
| | 101' R 4 | 115' R 4 | 2 | 20' L 4 | 80' R 4 | 90' R 4 | | |
| (O) Elev. | 738 | 737 | 731 | 730 | 729 | 728 | | |

Compaction Required 100%

CONFIDENTIAL BUSINESS
INFORMATION

Technician UD/HO

NUCLEAR DENSITY METER WORK SHEET

PROJECT: WMA-5/10
 JOB NO.: 1000
 AREA: 1000

DATE: 9-3-73
 DENSITY STANDARD COUNT: 231
 MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-------|---------|---------|---------|---------|---------|---------|---------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 428 | 430 | 446 | 418 | 448 | 432 | 432 | 422 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 127.5 | 127.0 | 125.0 | 129.0 | 123.0 | 127.0 | 127.0 | 128.5 |
| (F) Moist Count | 924 | 916 | 872 | 958 | 1004 | 884 | 908 | 966 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 17.5 | 17.5 | 16.3 | 18.5 | 19.3 | 16.6 | 17.3 | 18.7 |
| (I) Dry Wt. | 110.0 | 109.5 | 108.7 | 116.5 | 105.7 | 110.4 | 109.7 | 114.5 |
| (J) Proctor Wt. | 110 | 110 | 106.3 | 110 | 106.3 | 110 | 110 | 110 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 4+25 | 4+40 | 4+75 | 5+10 | 4+50 | 4+60 | 5+75 | 5+85 |
| | q | 15' R L | 40' R L | 50' R L | 60' L L | 70' L L | 80' L L | 90' L L |
| (O) Elev. | 747 | 746 | 746 | 745 | 746 | 745 | 746 | 745 |

Compaction Required 100%

Technician U.D. / TD

CONFIDENTIAL BUSINESS INFORMATION

GLASSBORO POWER COMPANY - SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: See Plans

DATE: 9/5/77
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | | | |
|-----------------------------------|-----------------|----------------|----------------|-------|-----------------|-------|-----------------|-------|
| (A) Test Number | 8 | 9 | 10 | 11 | 12 | 14 | 15 | 16 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 464 | 450 | 450 | 508 | 442 | 460 | 442 | 428 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 123.0 | 124.7 | 124.7 | 118.0 | 125.7 | 123.5 | 125.7 | 127.5 |
| (F) Moist Count | 860 | 910 | 840 | 920 | 950 | 980 | 900 | 990 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 15.1 | 17.3 | 15.7 | 17.5 | 18.2 | 18.9 | 17.1 | 19.1 |
| (I) Dry Wt. | 106.9 | 107.4 | 109.0 | 100.5 | 107.5 | 104.6 | 108.6 | 108.4 |
| (J) Proctor Wt. | 106.2 | 106.2 | 106.2 | 100 | 106 | 103 | 106 | 106 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 9+70 125.812 | 9+10 30.518 | 7+00 30.518 | 7+20 | 5+50 110.179 | 5+60 | 5+00 100.878 | 5+20 |
| (O) Elev. | 717 | 716 | 730 | 729 | 745 | 744 | 744 | 745 |

Compaction Required 100

Technician M.K.

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: 2nd Floor

DATE: 9/5/73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
|-----------------------------------|-----------------|-------|-----------------|-----------------|-----------------|-----------------|-------------------|-------|
| (B) Probe Depth | 6" — | — | — | — | — | — | — | — |
| (C) Dens. Count | 458 | 438 | 464 | 440 | 430 | 460 | 426 | 422 |
| (D) C ÷ Std Count | — | — | — | — | — | — | — | — |
| (E) Wet Wt. (lb/ft ³) | 123.7 | 126.2 | 123.0 | 126.1 | 127.2 | 123.5 | 124.4 | 125.2 |
| (F) Moist Count | 900 | 1020 | 860 | 1020 | 980 | 1040 | 1160 | 1132 |
| (G) F ÷ Std Count | — | — | — | — | — | — | — | — |
| (H) Wt. Moist (lbs) | 17.1 | 19.9 | 16.1 | 19.9 | 18.1 | 22.3 | 23.2 | 22.4 |
| (I) Dry Wt. | 106.6 | 106.3 | 106.9 | 106.1 | 108.3 | 103.2 | 104.4 | 107.8 |
| (J) Proctor Wt. | | | | | | | | |
| (K) % Comp. I ÷ J | | | | | | | | |
| (L) % Moist | | | | | | | | |
| (N) Location | 19+00 245119 | 19+00 | 20+20 230179 | 20+55 245119 | 22+20 220119 | 22+60 224160 | 23+50 215' 219 | 23+60 |
| (O) Elev. | 725 | 724 | 726 | 725 | 728 | 729 | 732 | 731 |

Compaction Required 100

Technician W. J. Davis

CONFIDENTIAL BUSINESS
INFORMATION

BLUING POWER COMPANY - SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: 17777777
JOB NO.: 17777777
AREA: 17777777

DATE: 9-5-73
DENSITY STANDARD COUNT: 201
MOISTURE STANDARD COUNT: 100

| | | | | | | | | |
|-----------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 462 | 406 | 410 | 415 | 450 | 450 | 420 | 424 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (1b/ft ³) | 123.0 | 123.0 | 123.0 | 123.0 | 123.0 | 123.0 | 123.0 | 123.0 |
| (F) Moist Count | 310 | 310 | 310 | 310 | 310 | 310 | 310 | 310 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 11.3 | 10.3 | 21.1 | 17.3 | 20.8 | 20.6 | 17.0 | 17.1 |
| (I) Dry Wt. | 106.6 | 106.7 | 102.4 | 107.2 | 102.2 | 106.6 | 11.2 | 11.1 |
| (J) Proctor Wt. | 106.3 | 106.3 | 103 | 106 | 103 | 106 | 10 | 1 |
| (K) % Comp. I ÷ J | 100 | 100 | 99 | 11 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 420 | 406 | 410 | 415 | 450 | 450 | 420 | 424 |
| (O) Elev. | 12 | 10 | 10 | 10 | 10 | 10 | 10 | 10 |

Compaction Required 100%

Technician 6

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: _____

DATE: 2-5-77
DENSITY STANDARD COUNT: 200
MOISTURE STANDARD COUNT: _____

| | | | | | | | | |
|-----------------------------------|------|-------|------|-----|-------|-------|-------|-------|
| (A) Test Number | 4 | 70 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 490 | 478 | 515 | 416 | | 512 | 416 | 478 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 120 | 121.5 | 115 | | 120.0 | 117.5 | 121.0 | 125.2 |
| (F) Moist Count | 1000 | 114 | | | | | | |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 100 | 100 | 16.7 | | | | | |
| (I) Dry Wt. | 100 | 100 | 100 | 100 | 100 | 100 | 110 | 111.0 |
| (J) Proctor Wt. | 100 | 100 | 100 | 100 | 100 | 100 | 110 | 111 |
| (K) % Comp. I ÷ J | | | | | | | | |
| (L) % Moist | | | | | | | | |
| (N) Location | 2A | 2B | 2C | 2D | 2E | 2F | 2G | 2H |
| (O) Elev. | 111 | 111 | 712 | 716 | | 113 | 111 | 111 |

Compaction Required _____

Technician 1

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: 101710-107
JOB NO.:
AREA:

DATE: 9-5-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | |
|-----------------------------------|-------|-------|-------|------|--|--|--|
| (A) Test Number | 7 | 18 | 17 | 20 | | | |
| (B) Probe Depth | 6 | | | | | | |
| (C) Dens. Count | 422 | 412 | 4 | 42 | | | |
| (D) C ÷ Std Count | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 120.2 | 120.5 | 120.5 | 120 | | | |
| (F) Moist Count | 66 | 172 | 152 | 1 | | | |
| (G) F ÷ Std Count | | | | | | | |
| (H) Wt. Moist (lbs) | 8.5 | 18.5 | 10.1 | 10.1 | | | |
| (I) Dry Wt. | 66 | 110 | 10.6 | 10.6 | | | |
| (J) Proctor Wt. | 10 | 110 | 100 | 100 | | | |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | | | |
| (L) % Moist | | | | | | | |
| (N) Location | 2-3-7 | 1 | 100 | 11 | | | |
| (O) Elev. | 1 | 1 | 7.2 | 1 | | | |

Compaction Required _____ Technician _____

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — BUILD
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: Sep Davis

DATE: 9/4/73
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | | | | |
|-----------------------------------|-----------------------|-------------|-----------------------|-------|--|--|--|--|--|
| (A) Test Number | 17 | 18 | 19 | 20 | | | | | |
| (B) Probe Depth | | | | | | | | | |
| (C) Dens. Count | 400 | 420 | 418 | 422 | | | | | |
| (D) C ÷ Std Count | | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 131.0 | 128.5 | 128.7 | 128.2 | | | | | |
| (F) Moist Count | 1270 | 1180 | 1250 | 1300 | | | | | |
| (G) F ÷ Std Count | | | | | | | | | |
| (H) Wt. Moist (lbs) | 25.7 | 23.6 | 25.2 | 26.4 | | | | | |
| (I) Dry Wt. | 105.3 | 104.9 | 103.5 | 101.8 | | | | | |
| (J) Proctor Wt. | 103 | 103 | 103 | 103 | | | | | |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 99 | | | | | |
| (L) % Moist | | | | | | | | | |
| (N) Location | 20+00 180' R+4E -A | 19+89 -A | 18+75 165' R+4E -A | 18+66 | | | | | |
| (O) Elev. | 712 | 711 | 712 | 711 | | | | | |

Compaction Required 100

Technician MM

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Plant Wansley
JOB NO.:
AREA: Separation Dam

DATE: 9/4/73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-----------|-----------------|-------------------|-------|-------------------|-------|-------------------|-------|
| (A) Test Number | 7 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 452 | 516 | 454 | 434 | 466 | 430 | 426 | 460 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 124.7 | 117.2 | 124.2 | 126.7 | 122.7 | 127.2 | 127.7 | 123.5 |
| (F) Moist Count | 950 | 920 | 1300 | 970 | 1200 | 1010 | 1330 | 890 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 18.5 | 17.0 | 26.4 | 18.7 | 24.0 | 19.6 | 27.1 | 16.9 |
| (I) Dry Wt. | 106.2 | 100.2 | 97.8 | 108.0 | 98.7 | 107.6 | 100.6 | 106.6 |
| (J) Proctor Wt. | 104.0 | 100 | 98 | 107.0 | 98 | 108 | 98 | 106 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | E 6+00 | 10 RT E 6+00 | 24+50 250 RT E | 24+60 | 22+50 240 RT E | 22+60 | 21+00 250 RT E | 20+55 |
| (O) Elev. | 72.5 | 72.6 | 71.1 | 71.0 | 71.2 | 71.1 | 71.0 | 71.1 |

Compaction Required 100

Technician W. F.

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: Sep. 1944
AREA: _____

DATE: 9/4/73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 12

[illegible]

Compaction Required 100

Technician *DAK*

**CONFIDENTIAL BUSINESS
INFORMATION**

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT:
JOB NO.:
AREA:

DATE: 21.7.70
DENSITY STANDARD COUNT:
MOISTURE STANDARD COUNT:

| | | | | | | |
|-----------------------------------|--------|--------|--------|--------|--------|--------|
| (A) Test Number | 1 | 10 | 12 | 12 | 14 | 18 |
| (B) Probe Depth | | | | | | |
| (C) Dens. Count | 410 | 462 | 502 | 506 | 416 | 462 |
| (D) C ÷ Std Count | | | | | | |
| (E) Wet Wt. (1b/ft ³) | | 112.5 | 112.6 | 112.8 | 112.8 | 112.8 |
| (F) Moist Count | 410 | 1176 | 1176 | 1176 | 1176 | 1176 |
| (G) F ÷ Std Count | | | | | | |
| (H) Wt. Moist (lbs) | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 |
| (I) Dry Wt. | | | | | | |
| (J) Proctor Wt. | | | | | | |
| (K) % Comp. I ÷ J | 90 | 90 | 90 | 90 | 90 | 90 |
| (L) % Moist | | | | | | |
| (N) Location | 150 R4 | 150 R4 | 150 R4 | 150 R4 | 150 R4 | 150 R4 |
| (O) Elev. | 117.4 | 117.6 | 117.6 | 117.6 | 117.6 | 117.6 |

Compaction Required 150 / 8

Technician

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: beam test
JOB NO.: 1
AREA: 2

DATE: 5.21.78
DENSITY STANDARD COUNT: 200
MOISTURE STANDARD COUNT: 11

| | | | | | | | | |
|-----------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 477 | 410 | 410 | 410 | 416 | 466 | 482 | 170 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 122.0 | 123.5 | 122.5 | 125.3 | 117.0 | 120.0 | 124.2 | 111.1 |
| (F) Moist Count | 1110 | 862 | 111 | 994 | 797 | 776 | 8 | |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 22.1 | 16.1 | | 15.1 | | 12.1 | 10.3 | |
| (I) Dry Wt. | 100.0 | 107.4 | 101.6 | 109.4 | 103.4 | 107.9 | | |
| (J) Proctor Wt. | 100 | 101 | | | | | | |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 6-116 | | 14 | 11 | | 8 | | |
| | 24.14 | 101.4 | 101.4 | 101.4 | 101.4 | 101.4 | 101.4 | |
| (O) Elev. | | 73.1 | 73.7 | | | | | |

Compaction Required 100%

Technician 101/0

CONFIDENTIAL BUSINESS
INFORMATION

PROJECT: _____

JOB NO.: _____

AREA: Sep. Dam

DATE: 8/31/73

DENSITY STANDARD COUNT: _____

MOISTURE STANDARD COUNT: _____

| A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
|----------------------------------|------------------|------------|-------------------|------------|-------------------|------------|-------------------|------------|
| B) Probe Depth | 6" | | | | | | | |
| C) Dens. Count | 466 | 464 | 540 | 534 | 450 | 438 | 480 | 530 |
| D) C ÷ Std Count | — | — | — | — | — | — | — | — |
| E) Wet Wt. (lb/ft ³) | 122.7 | 123.0 | 114.7 | 115.2 | 124.7 | 126.2 | 121.2 | 115.7 |
| F) Moist Count | 1210 | 1260 | 1250 | 1170 | 1120 | 1200 | 1290 | 1060 |
| G) F ÷ Std Count | — | — | — | — | — | — | — | — |
| H) Wt. Moist (lbs) | 24.2 | 25.4 | 25.2 | 23.4 | 27.2 | 24.0 | 26.2 | 20.8 |
| I) Dry Wt. | 98.5 | 98.6 | 89.5 | 91.8 | 102.5 | 102.7 | 75.0 | 94.9 |
| J) Proctor Wt. | 98 | 98 | 92 | 92 | 100 | 100 | 92 | 92.0 |
| K) % Comp. I ÷ J | 100 | 100 | 98 | 100 | 100 | 100 | 100 | 100 |
| L) % Moist | | | 28.2 | | | | | |
| N) Location | 21+00 50 RT E | 21+10 → | 19+75 Rerolled | 19+85 → | 18+75 75' RT E | 18+65 → | 18+50 200 RT E | 18+60 → |
| O) Elev. | 710 | 709 | 705 | 704 | 702 | 701 | 700 | 701 |

Compaction Required 100

Technician MK

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: Se. Dam

DATE: 8/31/73
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | | | |
|-----------------------------------|---------------------------|----------|----------|----------|----------|----------|----------|----------|
| (A) Test Number | | | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 432 | 472 | 400 | 428 | 418 | 430 | 428 | 440 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | ^{128.4} 127.0 | 122.2 | 131.0 | 127.5 | 128.7 | 127.2 | 127.5 | 126.0 |
| (F) Moist Count | 1040 | 1100 | 1140 | 1120 | 1350 | 1180 | 1280 | 1190 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 20.3 | 21.7 | 22.7 | 22.2 | 27.5 | 23.6 | 25.9 | 23.8 |
| (I) Dry Wt. | ^{108.5} 106.7 | 100.5 | 108.3 | 105.3 | 101.2 | 103.6 | 101.6 | 102.2 |
| (J) Proctor Wt. | 105.0 | 100 | 108.0 | 105.00 | 100 | 103.0 | 101.0 | 101.0 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | ^{16.9} 19.0 | | | | | | | |
| (N) Location | 20+50 | 20+60 | 19+00 | 19+10 | 20+25 | 20+35 | 23+50 | 25+60 |
| | 200 R7 E | 200 R7 E | 265 L1 E | 265 L1 E | 220 L7 E | 220 L7 E | 230 L7 E | 230 L7 E |
| (O) Elev. | 706 | 705 | 722 | 721 | 726 | 725 | 730 | 731 |
| | | | 150 | 100 | 100 | 120 | | |

Compaction Required 100

Technician M. K.

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY -- SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: 50p Para

DATE: 8/30/73
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | | |
|-----------------------------------|------------------|------------|------------|--|--|--|--|
| (A) Test Number | 17 | 18 | 19 | | | | |
| (B) Probe Depth | | | | | | | |
| (C) Dens. Count | 432 | 440 | 428 | | | | |
| (D) C ÷ Std Count | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 127.0 | 126.0 | 127.5 | | | | |
| (F) Moist Count | 1250 | 1180 | 1120 | | | | |
| (G) F ÷ Std Count | | | | | | | |
| (H) Wt. Moist (lbs) | 25.2 | 23.6 | 22.5 | | | | |
| (I) Dry Wt. | 101.8 | 102.4 | 105.0 | | | | |
| (J) Proctor Wt. | 100 | 100 | 105 | | | | |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | | | | |
| (L) % Moist | | | | | | | |
| (N) Location | 19+55 70672 → | 18+00 → | 18+10 → | | | | |
| (O) Elev. | 718 | 720 | 719 | | | | |

Compaction Required 100

Technician M. X

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Port Wansley
JOB NO.:
AREA: Separation Dam

DATE: 8/30/73
DENSITY STANDARD COUNT:
MOISTURE STANDARD COUNT:

| | | | | | | | | |
|-----------------------------------|-------------------|------------|------------------|------------|------------------|------------|--------------|------------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ |
| (C) Dens. Count | 418 | 416 | 414 | 410 | 450 | 444 | 430 | 428 |
| (D) C ÷ Std Count | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ |
| (E) Wet Wt. (lb/ft ³) | 128.3 | 129.0 | 129.2 | 129.7 | 124.7 | 125.5 | 127.4 | 127.5 |
| (F) Moist Count | 1172 | 1210 | 1182 | 1170 | 1100 | 1140 | 1110 | 1160 |
| (G) F ÷ Std Count | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ |
| (H) Wt. Moist (lbs) | 23.4 | 24.2 | 23.6 | 23.4 | 21.7 | 22.7 | 24.2 | 23.2 |
| (I) Dry Wt. | 105.4 | 104.8 | 102.6 | 106.3 | 103.0 | 102.8 | 103.2 | 104.3 |
| (J) Proctor Wt. | 103 | 103 | 103 | 103 | 103 | 103 | 103 | 103 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 24+00 175' L/E | 24+15 → | 23+30 200 L/E | 23+45 → | 21+05 220 L/E | 21+20 → | 19+75 240 | 19+65 → |
| (O) Elev. | 955 | 954 | 952 | 950 | 724 | 723 | 720 | 719 |

Compaction Required 100

Technician W.H.

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY -- SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: Sep. Dam

DATE: 8/30/73
DENSITY/STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-----------|-------|---------|-------|-------|---------|-------|---------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | 6 | → | → | → | → | → | → | → |
| (C) Dens. Count | 402 | 416 | 444 | 454 | 422 | 424 | 418 | 424 |
| (D) C ÷ Std Count | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ |
| (E) Wet Wt. (lb/ft ³) | 130.7 | 129.0 | 125.5 | 124.2 | 128.0 | 128.0 | 128.7 | 128.0 |
| (F) Moist Count | 1340 | 1350 | 1200 | 1170 | 1058 | 1252 | 1290 | 1272 |
| (G) F ÷ Std Count | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ |
| (H) Wt. Moist (lbs) | 27.3 | 27.5 | 24.0 | 23.4 | 20.8 | 25.2 | 26.2 | 26.2 |
| (I) Dry Wt. | 103.4 | 101.5 | 101.5 | 100.8 | 107.2 | 102.8 | 102.5 | 101.8 |
| (J) Proctor Wt. | 103 | 100 | 100 | 100 | 105 | 103 | 103 | 100 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 24+50 | 24+60 | 23+50 | 23+60 | 23+40 | 22+50 | 22+60 | 21+00 |
| | 50 LITE → | → | 75 LITE | → | → | 80 LITE | → | 80 LITE |
| (O) Elev. | 735 | 734 | 730 | 729 | 728 | 726 | 725 | 725 |

Compaction Required 100

Technician M. J. K. K. K.

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: _____

DATE: _____
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | | | | |
|----------------------|----------|--|--|--|--|--|--|--|--|
| (A) Test Number | | | | | | | | | |
| (B) Probe Depth | 1' | | | | | | | | |
| (C) Dens. Count | 1108 | | | | | | | | |
| (D) C ÷ Std Count | | | | | | | | | |
| (E) Wet Wt. (lb/ft³) | 121.0 | | | | | | | | |
| (F) Moist Count | 1108 | | | | | | | | |
| (G) F ÷ Std Count | | | | | | | | | |
| (H) Wt. Moist (lbs) | 18.1 | | | | | | | | |
| (I) Dry Wt. | 167.7 | | | | | | | | |
| (J) Proctor Wt. | | | | | | | | | |
| (K) % Comp. I ÷ J | | | | | | | | | |
| (L) % Moist | | | | | | | | | |
| (N) Location | 2470 | | | | | | | | |
| | 125' L 4 | | | | | | | | |
| (O) Elev. | 745 | | | | | | | | |

Compaction Required

Technician

**CONFIDENTIAL BUSINESS
INFORMATION**

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: 12/07

DATE: _____
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | | |
|-----------------------------------|-----------|---------------|-------------|-------------|-------------|-------------|-------------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| (B) Probe Depth | 6" | | | | | | |
| (C) Dens. Count | 412 | 416 | 426 | 422 | 424 | 416 | 412 |
| (D) C ÷ Std Count | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 125.5 | 129.0 | 125.0 | 127.0 | 128.0 | 129.0 | 127.5 |
| (F) Moist Count | 1282 | 1301 | 1280 | | 1340 | 1326 | 1311 |
| (G) F ÷ Std Count | | | | | | | |
| (H) Wt. Moist (lbs) | 2.59 | 26.6 | 2.5 | 24.6 | 27.3 | 27.1 | 24.2 |
| (I) Dry Wt. | 103.6 | 102.4 | 103.3 | 102.4 | 100.7 | 101.7 | 103.3 |
| (J) Proctor Wt. | | 100 | 100 | 100 | 100 | 100 | 100 |
| (K) % Comp. I ÷ J | 100 | 100 | 99 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | Reptd | | | | |
| (N) Location | 18" 75" L | 18" 15" 85" L | 174" 602" 4 | 181" 962" 4 | 204" 100" L | 201" 500" 1 | 211" 112" 8 |
| (O) Elev. | 721 | 722 | 720 | 721 | 722 | 723 | 721 |

Compaction Required 100% Technician (100) / (100)

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: 11111111
JOB NO.: 1
AREA: 1

DATE: 11/11/11
DENSITY STANDARD COUNT: 11
MOISTURE STANDARD COUNT: 11

| | | | | | | | |
|-----------------------------------|-------|-------|-------|-------|-------|-------|-------|
| (A) Test Number | 61 | 100 | 11 | 12 | 13 | 14 | 15 |
| (B) Probe Depth | 6" | | | | | | |
| (C) Dens. Count | 411 | 422 | 433 | 444 | 455 | 466 | 477 |
| (D) C ÷ Std Count | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 123.0 | 124.0 | 125.0 | 126.0 | 127.0 | 128.0 | 129.0 |
| (F) Moist Count | 130 | 131 | 132 | 133 | 134 | 135 | 136 |
| (G) F ÷ Std Count | | | | | | | |
| (H) Wt. Moist (lbs) | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (I) Dry Wt. | 3 | 4 | 5 | 6 | 7 | 8 | 9 |
| (J) Proctor Wt. | 100 | 101 | 102 | 103 | 104 | 105 | 106 |
| (K) % Comp. I ÷ J | 80 | 81 | 82 | 83 | 84 | 85 | 86 |
| (L) % Moist | | | | | | | |
| (N) Location | 18450 | 18451 | 18452 | 18453 | 18454 | 18455 | 18456 |
| (O) Elev. | 722 | 723 | 724 | 725 | 726 | 727 | 728 |

Compaction Required 100%

CONFIDENTIAL BUSINESS
INFORMATION

Technician UD/10

LAW ENGINEERING TESTING COMPANY
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Plant Wansley
JOB NO.: G-4100
REA: Station Dam

DATE: 3-20-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1110

| | | | | | | | | |
|----------------------------------|------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| B) Probe Depth | | | | | | | | |
| C) Dens. Count | 442 | 420 | 484 | 450 | 426 | 438 | 430 | 432 |
| D) C ÷ Std Count | 1 | | | | | | | |
| E) Wet Wt. (lb/ft ³) | 125.7 | 128.5 | 123.0 | 124.4 | 127.9 | 126.0 | 127.3 | 127.0 |
| F) Moist Count | 1110 | 1120 | 1133 | 131 | 1260 | 1220 | 1142 | 1260 |
| G) F ÷ Std Count | | | | | | | | |
| H) Wt. Moist (lbs) | 22.0 | 22.2 | 23.7 | 27.3 | 25.4 | 24.6 | 22.8 | 25.4 |
| I) Dry Wt. | 103.7 | 106.3 | 99.3 | 97.1 | 102.5 | 101.4 | 104.5 | 101.6 |
| J) Proctor Wt. | 1030 | 105 | 100 | 100 | 100 | 100 | 103 | 100 |
| K) % Comp. I ÷ J | 100 | 100 | 99 | 97 | 100 | 100 | 100 | 100 |
| L) % Moist | | | | | | | | |
| M) Location | Sta 19+2.5 | Sta 19+40 | Sta 20+30 | Sta 21+50 | Sta 22+25 | Sta 22+40 | Sta 24+30 | Sta 24+45 |
| | 175' Sta | 175' Sta | 175' Sta | 175' Sta | 200' Sta | 200' Sta | 200' Sta | 200' Sta |
| N) Elev. | 717 | 716 | 716 | 715 | 720 | 719 | 722 | 725 |

CONFIDENTIAL BUSINESS
INFORMATION

Compaction Required 100%

Technician AM

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT:
JOB NO.: Sep Day
AREA:

DATE: 8/29/73
DENSITY STANDARD COUNT:
MOISTURE STANDARD COUNT:

| | | | | | | | | |
|-----------------------------------|-------------------|------------|-------------------|------------|--------------------|------------|--------------------|------------|
| (A) Test Number | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 458 | 460 | 422 | 434 | 440 | 436 | 440 | 414 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 123.7 | 123.5 | 128.2 | 126.7 | 126.0 | 126.2 | 126.0 | 129.2 |
| (F) Moist Count | 1400 | 1380 | 1280 | 1240 | 1160 | 1200 | 1310 | 1280 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 28.7 | 28.3 | 26.2 | 25.3 | 23.2 | 24.0 | 26.0 | 25.9 |
| (I) Dry Wt. | 95.0 | 95.2 | 102.0 | 101.4 | 102.8 | 102.2 | 100.0 | 102.3 |
| (J) Proctor Wt. | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (K) % Comp. I ÷ J | to wet | 110d | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | Re | Re | | | | | | |
| (N) Location | 19+50 100L7E → | 19+60 → | 21+00 100L7E → | 21+20 → | 22+50 80' L7E → | 22+60 → | 24+25 75' L7E → | 24+35 → |
| (O) Elev. | 714 | 713 | 716 | 715 | 723 | 724 | 722 | 722 |

Compaction Required

CONFIDENTIAL BUSINESS
INFORMATION

Technician

PAK: A. N. L.

LAW ENGINEERING TESTING COMPANY
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Plant Wansley
OB NO.: G-4100
REA: Sep. Dam

DATE: 8/29/73
DENSITY STANDARD COUNT:
MOISTURE STANDARD COUNT:

| A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
|---------------------|------------------|-----------------|-----------------|-----------------|-----------------|-----------------|-----------------|-----------------|
| B) Probe Depth | 6" 10 | 10 | 10 | 10 | 10 | 10 | 10 | 10 |
| C) Dens. Count | 436 | 438 | 450 | 424 | 436 | 428 | 432 | 436 |
| D) C ÷ Std Count | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ |
| E) Wet Wt. (lb/ft³) | 126.2 | 126.2 | 124.7 | 128.0 | 126.2 | 127.5 | 127.0 | 126.2 |
| F) Moist Count | 1090 | 1020 | 1080 | 1000 | 1060 | 1040 | 1080 | 1020 |
| G) F ÷ Std Count | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ | ✓ |
| H) Wt. Moist (lbs) | 21.5 | 19.9 | 21.3 | 19.3 | 20.8 | 20.3 | 21.2 | 19.9 |
| I) Dry Wt. | 104.7 | 106.3 | 103.4 | 108.7 | 105.4 | 107.2 | 105.7 | 106.3 |
| J) Proctor Wt. | 105 | 105 | 100 | 108 | 105 | 105 | 105 | 105 |
| K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| L) % Moist | | | | | | | | |
| N) Location | 19+60 280L+E | 19+70 280L+E | 21+40 255L+E | 21+50 280L+E | 23+25 275L+E | 23+35 280L+E | 24+75 270L+E | 24+10 270L+E |
| O) Elev. | 718 | 717 | 720 | 719 | 720 | 725 | 724 | 726 |

40

Compaction Required 100

CONFIDENTIAL BUSINESS
INFORMATION

Technician M. K.

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WATKINSLEY
JOB NO.: 1
AREA: S&P DAM

DATE: 8.28.73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-------|-------|--------|--------|--------|--------|-------|--------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 428 | 432 | 456 | 398 | 404 | 412 | 452 | 450 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 127.5 | 127.6 | 124.0 | 131.5 | 130.5 | 129.5 | 124.5 | 124.5 |
| (F) Moist Count | 1198 | 1184 | 988 | 1216 | 1156 | 1165 | 1000 | 968 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 24.6 | 23.6 | 19.1 | 24.6 | 23.2 | 22.0 | 19.3 | 18.7 |
| (I) Dry Wt. | 103.5 | 103.4 | 104.9 | 107.9 | 107.3 | 107.5 | 105.2 | 105.8 |
| (J) Proctor Wt. | 103 | 103 | 105 | 108 | 108 | 108 | 105 | 105 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 23+00 | 23+10 | 24+50 | 24+60 | 25+00 | 25+15 | 18+50 | 18+100 |
| | 90' L | 80' L | 150' L | 160' L | 100' L | 110' L | 80' L | 90' L |
| (O) Elev. | 727 | 728 | 730 | 731 | 728 | 729 | 718 | 719 |

Compaction Required 100%

Technician UD/70

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WANDER
JOB NO.: 1
AREA: SEP 1, 1970

DATE: 8-29-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1231

| | | | | | | | | |
|-----------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 438 | 428 | 406 | 402 | 412 | 392 | 434 | 460 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 126.0 | 127.5 | 130.0 | 131.0 | 129.5 | 132.0 | 126.5 | 123.5 |
| (F) Moist Count | 1230 | 1220 | 1038 | 1022 | 1016 | 934 | 1114 | 976 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 24.8 | 24.6 | 20.3 | 19.9 | 19.9 | 18.0 | 22.0 | 18.9 |
| (I) Dry Wt. | 101.2 | 102.9 | 109.7 | 111.1 | 109.6 | 114.0 | 104.5 | 104.6 |
| (J) Proctor Wt. | 100 | 100 | 109 | 109 | 109 | 114 | 105 | 105 |
| (K) % Comp. I ÷ J | 100% | 100% | 100 | 100% | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 19+25 | 19+35 | 20+53 | 20+50 | 21+00 | 21+15 | 22+25 | 22+35 |
| | 260' L | 275' L | 175' L | 185' L | 200' L | 215' L | 250' L | 260' L |
| (O) Elev. | 715' | 716' | 716' | 717' | 717' | 718' | 724' | 725' |

Compaction Required 100%

Technician UD/TO

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: _____

DATE: 2-2-66
DENSITY STANDARD COUNT: 220
MOISTURE STANDARD COUNT: _____

| | | | | | | | |
|-----------------------------------|---------|---------|---------|---------|---------|---------|---|
| (A) Test Number | 7 | 10 | 11 | 12 | 13 | 14 | |
| (B) Probe Depth | 6" | | | | | | |
| (C) Dens. Count | 476 | 448 | 510 | 470 | 462 | 454 | |
| (D) C ÷ Std Count | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 123.5 | 125.0 | 124.1 | 123.5 | 123.5 | 123.0 | |
| (F) Moist Count | 1235 | 1216 | 1212 | 1198 | 1192 | 1182 | |
| (G) F ÷ Std Count | | | | | | | |
| (H) Wt. Moist (lbs) | 7.50 | 24.6 | 24.2 | 7 | 15.0 | 22.5 | 1 |
| (I) Dry Wt. | 101.5 | 100.4 | 102.0 | 116.0 | 108.5 | 111.2 | |
| (J) Proctor Wt. | 100 | 11 | | | | | |
| (K) % Comp. I ÷ J | 100 | | | | 100 | | |
| (L) % Moist | | | | | | | |
| (N) Location | 18th St | 18th St | 18th St | 18th St | 18th St | 18th St | |
| (O) Elev. | 77' | 77.0 | 77.0 | 77.0 | 77.0 | 77.0 | |

Compaction Required 100%

CONFIDENTIAL BUSINESS
INFORMATION

Technician 110/110

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: _____

DATE: 3-7-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1311

| | | | | | | | | | | |
|-----------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 |
| (B) Probe Depth | 1" | | | | | | | | | |
| (C) Dens. Count | 448 | 458 | 478 | 482 | 492 | 497 | 498 | 499 | 500 | 501 |
| (D) C ÷ Std. Count | | | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 125.4 | 127.0 | 127.5 | 128.0 | 128.5 | 128.8 | 129.0 | 129.2 | 129.4 | 129.6 |
| (F) Moist Count | 1428 | 1382 | 1267 | 1268 | 1282 | 1112 | 1122 | 1122 | 1122 | 1122 |
| (G) F ÷ Std. Count | | | | | | | | | | |
| (H) Wt. Moist (lbs) | 27.1 | 28.3 | 25.4 | 25.7 | 25.9 | 23.2 | 23.2 | 23.2 | 23.2 | 23.2 |
| (I) Dry Wt. | 47.9 | 48.7 | 45.2 | 45.3 | 45.6 | 45.6 | 45.6 | 45.6 | 45.6 | 45.6 |
| (J) Proctor Wt. | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (K) % Comp. I ÷ J | 47.9 | 48.7 | 45.2 | 45.3 | 45.6 | 45.6 | 45.6 | 45.6 | 45.6 | 45.6 |
| (L) % Moist | | | | | | | | | | |
| (N) Location | 71+00 | 71+10 | 71+20 | 71+30 | 71+40 | 71+50 | 71+60 | 71+70 | 71+80 | 71+90 |
| (O) Elev. | 711 | 710 | 712 | 712 | 712 | 712 | 712 | 712 | 712 | 712 |

Compaction Required 100 %

CONFIDENTIAL BUSINESS
INFORMATION

Technician L.D./T.D.

LAW ENGINEERING TESTING COMPANY
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Plant Wansley
JOB NO.: G-4100
REA: Sap Dam

DATE: 8/28/73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1571

| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
|----------------------------------|---------|---------|---------|--------|--------|--------|--------|
| 1) Test Number | | | | | | | |
| 2) Probe Depth | | | | | | | |
| 3) Dens. Count | 410 | 426 | 400 | 450 | 420 | 430 | 418 |
| 4) C ÷ Std Count | | | | | | | |
| 5) Wet Wt. (lb/ft ³) | 129.7 | 127.7 | 131.2 | 124.7 | 128.5 | 124.4 | 128.7 |
| 6) Moist Count | 1060 | 980 | 1110 | 1090 | 1110 | 1080 | 1020 |
| 7) F ÷ Std Count | | | | | | | |
| 8) Wt. Moist (lbs) | 20.7 | 18.9 | 21.7 | 21.5 | 21.7 | 21.3 | 19.9 |
| 9) Dry Wt. | 107.0 | 108.8 | 110.5 | 103.2 | 106.8 | 105.9 | 108.8 |
| 10) Proctor Wt. | 108 | 108.0 | 108 | 103 | 106 | 106 | 108 |
| 11) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| 12) % Moist | | | | | | | |
| 13) Location | 19+50 | 17+50 | 19+60 | 19+80 | 19+80 | 20+20 | 20+20 |
| | 265.47% | 250.47% | 175.17% | 60.47% | 75.17% | 60.47% | 75.17% |
| 14) Elev. | 712 | 711 | 712 | 710 | 709 | 709 | 718 |

Compaction Required: 100

CONFIDENTIAL BUSINESS
INFORMATION

Technician

M. R.

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: _____

SEPA

DATE: _____
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | | | | |
|-----------------------------------|-------|-------|-------|-----|--------|--------|--------|--------|--------|
| (A) Test Number | 10 | | | | | | | | |
| (B) Probe Depth | | | | | | | | | |
| (C) Dens. Count | 2138 | 444 | | | | | | | |
| (D) C ÷ Std Count | | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 116.1 | | | | | | | | |
| (F) Moist Count | 182 | 970 | | | | | | | |
| (G) F ÷ Std Count | | | | | | | | | |
| (H) Wt. Moist (lbs) | 5.1 | | | | | | | | |
| (I) Dry Wt. | 177.1 | 106.8 | 104.6 | | | | | | |
| (J) Proctor Wt. | | | 183 | | | | | | |
| (K) % Comp. I ÷ J | | | 100 | | | | | | |
| (L) % Moist | | | | | | | | | |
| (N) Location | 113.2 | 100 | | | | | | | |
| (O) Elev. | 735 | 170 | 744 | 731 | 2052.2 | 2052.4 | 2052.4 | 2052.4 | 2052.4 |

Compaction Required

100%

**CONFIDENTIAL BUSINESS
INFORMATION**

Technician

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: 600000
JOB NO.: 210
AREA: SEPAR

DATE: 2-2-77
DENSITY STANDARD COUNT: 1015
MOISTURE STANDARD COUNT: 1046

| | | | | | | | |
|-----------------------------------|--------|---------|---------|---------|----------|----------|----------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| (B) Probe Depth | 6" | | | | | | |
| (C) Dens. Count | 464 | 446 | 470 | 458 | 470 | 470 | 470 |
| (D) C ÷ Std Count | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 123.0 | 125.0 | 127.0 | 127.5 | 127.5 | 127.5 | 128.0 |
| (F) Moist Count | 762 | 948 | 912 | 900 | 900 | 900 | 1046 |
| (G) F ÷ Std Count | | | | | | | |
| (H) Wt. Moist (lbs) | 18.5 | 18.2 | 17.7 | 17.3 | 17.1 | 17.5 | 18.0 |
| (I) Dry Wt. | 104.5 | 106.8 | 109.7 | 106.2 | 105.4 | 105.0 | 107.4 |
| (J) Proctor Wt. | 108 | 106.3 | 105 | 106.3 | 106.3 | 106.3 | 106.3 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 99 | 99 | 100 |
| (L) % Moist | | | | | | | |
| (N) Location | 75' | 7460 | 30'P L | 7418 | 9400 | 5-118 | 10160 |
| | 4 D Ke | 20' R L | 30' P L | 20' R L | 200' L d | 210' L d | 250' L d |
| (O) Elev. | 725 | 976 | 729 | 725 | 735 | 726 | 726 |

Compaction Required 170 %

Technician U.P. / T.1

CONFIDENTIAL BUSINESS
INFORMATION

LAW ENGINEERING TESTING COMPANY
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Plant Wansley
OB NO.: G-4100
REA: 5ep Dam

DATE: 8/27/83
DENSITY STANDARD COUNT:
MOISTURE STANDARD COUNT:

| | | | | | | | | |
|----------------------------------|-----------------|-----------------|-----------------|-----------------|--|--|--|--|
| A) Test Number | 17 | 18 | 19 | 20 | | | | |
| B) Probe Depth | | | | | | | | |
| C) Dens. Count | 482 | 478 | 463 | 460 | | | | |
| D) C ÷ Std Count | | | | | | | | |
| E) Wet Wt. (lb/ft ³) | 123.7 | 128.2 | 125.7 | 126.7 | | | | |
| F) Moist Count | 1320 | 1280 | 1120 | 1480 | | | | |
| G) F ÷ Std Count | | | | | | | | |
| H) Wt. Moist (lbs) | 21.0 | 20.2 | 17.2 | 24.2 | | | | |
| I) Dry Wt. | 102.7 | 108.0 | 108.5 | 102.5 | | | | |
| J) Proctor Wt. | 103 | 108 | 108 | 103 | | | | |
| K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | | | | |
| L) % Moist | | | | | | | | |
| N) Location | 13+75 265+7E | 13+90 265+7E | 17400 22027E | 17415 22027E | | | | |
| O) Elev. | 732 | 731 | 731 | 730 | | | | |

Compaction Required 100

CONFIDENTIAL BUSINESS
INFORMATION

Technician MK

LAW ENGINEERING TESTING COMPANY
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Plant Wansley
JOB NO.: G-4100
REA: Cap Day

DATE: 27/73
DENSITY STANDARD COUNT:
MOISTURE STANDARD COUNT:

| A) Test Number | | | 11 | 12 | 13 | 14 | 15 | 16 |
|----------------------------------|---------|-------|---------|-------|---------|-------|---------|-------|
| B) Probe Depth | | | | | | | | |
| C) Dens. Count | 442 | 410 | 432 | 444 | 428 | 436 | 436 | 440 |
| D) C ÷ Std Count | | | | | | | | |
| E) Wet Wt. (lb/ft ³) | 125.7 | 129.7 | 130.0 | 128.7 | 131.7 | 129.7 | 129.7 | 129.2 |
| F) Moist Count | 980 | 1040 | 1270 | 1240 | 1400 | 1280 | 1320 | 1130 |
| G) F ÷ Std Count | | | | | | | | |
| H) Wt. Moist (lbs) | 13.9 | 20.8 | 20.0 | 19.5 | 22.7 | 20.2 | 21.0 | 17.5 |
| I) Dry Wt. | 106.8 | 108.9 | 110.0 | 109.2 | 109.0 | 109.5 | 108.7 | 111.7 |
| J) Proctor Wt. | 106 | 109 | 109 | 106 | 106 | 106 | 106 | 109 |
| K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| L) % Moist | | | | | | | | |
| N) Location | 7+75 | 7+90 | 7+25 | 7+40 | 9+20 | 9+40 | 10+50 | 10+55 |
| | 220 LTR | → | 245 LTR | → | 270 LTR | → | 280 LTR | → |
| O) Elev. | 733 | 732 | 733 | 732 | 730 | 729 | 732 | 731 |

Compaction Required . 190

**CONFIDENTIAL BUSINESS
INFORMATION**

Technician

LAW ENGINEERING TESTING COMPANY
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Plant Mansley
JOB NO.: G-4100
AREA: Geo. Area

DATE: 8/22/78
DENSITY STANDARD COUNT: 831
MOISTURE STANDARD COUNT: 1000

| A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
|----------------------------------|---------|-------|---------|-------|---------|---------|---------|---------|
| B) Probe Depth | | | | | | | | |
| C) Dens. Count | 440 | 432 | 400 | 438 | 406 | 420 | 414 | 424 |
| D) C ÷ Std Count | | | | | | | | |
| E) Wet Wt. (lb/ft ³) | 125.7 | 127.0 | 131.0 | 125.7 | 130.2 | 128.5 | 128.0 | 122.5 |
| F) Moist Count | 960 | 900 | 1010 | 980 | 1070 | 1050 | 1020 | 1110 |
| G) F ÷ Std Count | | | | | | | | |
| H) Wt. Moist (lbs) | 18.5 | 19.3 | 19.6 | 18.9 | 21.1 | 20.6 | 20.1 | 19.2 |
| I) Dry Wt. | 107.2 | 107.7 | 111.4 | 106.8 | 109.1 | 107.9 | 107.9 | 108.2 |
| J) Proctor Wt. | 106 | 106 | 109 | 108 | 109 | 106 | 106 | 106 |
| K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| L) % Moist | | | | | | | | |
| N) Location | 17+10 | 17+25 | 15+00 | 15+15 | 12+50 | 12+65 | 10+20 | 10+35 |
| | 190 178 | 177 | 235 178 | 228 | 260 178 | 260 178 | 250 178 | 250 178 |
| O) Elev. | 728 | 727 | 729 | 728 | 732 | 731 | 731 | 731 |

Compaction Required 100

CONFIDENTIAL BUSINESS
INFORMATION

Technician M. K.

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: UNOS 104
JOB NO.: 8010211
AREA: 8010211

DATE: 8-24-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|--------|--------|----------|--------|--------|--------|--------|--------|
| (A) Test Number | 1 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 426 | 434 | 462 | 428 | 466 | 454 | 462 | 470 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 128.0 | 126.5 | 123.0 | 127.5 | 123.0 | 124.0 | 123.0 | 122.5 |
| (F) Moist Count | 792 | 744 | 984 | 972 | 972 | 964 | 926 | 916 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 14.2 | 13.3 | 18.9 | 19.1 | 18.7 | 18.5 | 17.8 | 17.5 |
| (I) Dry Wt. | 113.8 | 113.2 | 104.1 | 108.4 | 104.3 | 105.5 | 105.2 | 105.6 |
| (J) Proctor Wt. | 110 | 110 | 105 | 107 | 105 | 105 | 105 | 105 |
| (K) % Comp. I ÷ J | 106+ | 106+ | 99 | 100 | 99 | 100 | 100 | 100 |
| (L) % Moist | | | ReRolled | | | | | |
| (N) Location | 15425 | 15+10 | 13+40 | 13+20 | 11+65 | 11+50 | 9+75 | 9+60 |
| | 260' L | 210' L | 250' L | 230' L | 195' L | 220' L | 250' L | 265' L |
| (O) Elev. | 724 | 725 | 723 | 724 | 723 | 724 | 722 | 723 |

10070

Compaction Required

CONFIDENTIAL BUSINESS
INFORMATION

Technician UJ

70

LAW ENGINEERING TESTING COMPANY
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Plant Mansley
JOB NO.: G-4100
REA: Seep Dam

DATE: 8/24/73
DENSITY STANDARD COUNT:
MOISTURE STANDARD COUNT:

| | | | | | | | |
|----------------------------------|------------------|------------------|-----------------|-----------------|--|--|--|
| 1) Test Number | 17 | 18 | 19 | 20 | | | |
| 2) Probe Depth | | | | | | | |
| 3) Dens. Count | 422 | 400 | 440 | 428 | | | |
| 4) C ÷ Std Count | | | | | | | |
| 5) Wet Wt. (lb/ft ³) | 128.2 | 131.0 | 125.8 | 127.5 | | | |
| 6) Moist Count | 990 | 940 | 1020 | 960 | | | |
| 7) F ÷ Std Count | | | | | | | |
| 8) Wt. Moist (lbs) | 19.1 | 18.0 | 19.9 | 18.5 | | | |
| 9) Dry Wt. | 109.1 | 113.0 | 105.9 | 109.0 | | | |
| 10) Proctor Wt. | 106 | 110 | 106 | 109.0 | | | |
| 11) % Comp. I ÷ J | | | | | | | |
| 12) % Moist | | | | | | | |
| 13) Location | 11400 205 L14 | 11420 205 L14 | 9440 200 L14 | 9455 200 L14 | | | |
| 14) Elev. | 727 | 726 | 728 | 727 | | | |

Impaction Required 100

CONFIDENTIAL BUSINESS
INFORMATION

Technician M. K.

LAW ENGINEERING TESTING COMPANY
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Plant Wansley
OB NO.: G-4100
REA: Gravel

DATE: 05-11-1964
DENSITY STANDARD COUNT: 15
MOISTURE STANDARD COUNT: 16

| | | | | | | | | |
|----------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|
| A) Test Number | 3 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| B) Probe Depth | | | | | | | | |
| C) Dens. Count | 460 | 444 | 416 | 430 | 434 | 436 | 436 | 408 |
| D) C ÷ Std Count | | | | | | | | |
| E) Wet Wt. (lb/ft ³) | 122.5 | 125.5 | 129.0 | 127.2 | 126.7 | 126.2 | 126.2 | 130.0 |
| F) Moist Count | 970 | 1000 | 930 | 1010 | 1050 | 1050 | 1040 | 1010 |
| G) F ÷ Std Count | | | | | | | | |
| H) Wt. Moist (lbs) | 18.7 | 18.7 | 17.8 | 19.6 | 20.6 | 20.6 | 20.3 | 19.6 |
| I) Dry Wt. | 104.8 | 106.8 | 111.2 | 107.6 | 106.1 | 105.6 | 105.9 | 110.4 |
| J) Proctor Wt. | 105 | 105 | 110.3 | 106 | 106 | 106 | 106 | 109 |
| K) % Comp. I ÷ J | 100 | 100 | 113 | 100 | 100 | 100 | 100 | 100 |
| L) % Moist | | | | | | | | |
| M) Location | 16+00 | 16+20 | 16+00 | 16+20 | 15+40 | 15+15 | 13+50 | 13+65 |
| N) Elev. | 250.17 | 250.17 | 200.17 | 190.17 | 190.17 | 190.17 | 195.18 | 195.18 |
| O) Elev. | 723 | 723 | 723 | 724 | 725 | 724 | 725 | 724 |

CONFIDENTIAL BUSINESS
INFORMATION

Compaction Required 100

Technician W. J. P.

LAW ENGINEERING TESTING COMPANY
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Plant Wansley
JOB NO.: G-4100
AREA: Shop

DATE: 3-1-58
DENSITY STANDARD COUNT:
MOISTURE STANDARD COUNT:

| A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 |
|----------------------------------|----------------|-----------|-----------------|------------|-----------------|------------|------------|
| B) Probe Depth | | | | | | | |
| C) Dens. Count | 418 | 426 | 432 | 440 | 442 | 448 | 450 |
| D) C ÷ Std Count | | | | | | | |
| E) Wet Wt. (lb/ft ³) | 128.7 | 127.7 | 127.0 | 128.5 | 125.7 | 126.0 | 127.2 |
| F) Moist Count | 940 | 1020 | 1140 | 1010 | 950 | 1000 | 950 |
| G) F ÷ Std Count | | | | | | | |
| H) Wt. Moist (lbs) | 18.0 | 19.9 | 22.7 | 19.6 | 18.2 | 19.3 | 19.2 |
| I) Dry Wt. | 110.7 | 7.81 | 112.3 | 118.9 | 107.5 | 115.7 | 108.2 |
| J) Proctor Wt. | 110 | 107 | 102 | 100 | 100 | 105 | 106 |
| K) % Comp. I ÷ J | 100+ | | | | | | 100+ |
| L) % Moist | | | | | | | |
| N) Location | 9+00 270L+9 | 9+15 → | 10+60 275L+9 | 10+75 → | 12+25 290L+9 | 12+40 → | 14+15 → |
| O) Elev. | 726 | 725 | 724 | 724 | 725 | 724 | 723 |

Compaction Required 100

**CONFIDENTIAL BUSINESS
INFORMATION**

Technician

XLIII

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WATER
JOB NO.: 541
AREA: 200

DATE: 12-23-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1250

| | | | | | | | | |
|-----------------------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 454 | 438 | 442 | 432 | 428 | 438 | 410 | 406 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 124.0 | 126.0 | 125.5 | 127.0 | 127.5 | 126.0 | 130.0 | 130.5 |
| (F) Moist Count | 924 | 936 | 932 | 966 | 990 | 992 | 932 | 916 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 17.5 | 18.0 | 17.8 | 18.7 | 19.1 | 18.1 | 17.8 | 18.7 |
| (I) Dry Wt. | 106.5 | 108.0 | 107.7 | 108.3 | 108.5 | 106.9 | 112.2 | 111.8 |
| (J) Proctor Wt. | 107 | 107 | 107 | 101 | 107 | 107 | 110 | 110 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | |
| (L) % Moist | | | | | | | | |
| (N) Location | 14+30 2.50' L | 14+15 2.60' L | 12+60 2.85' L | 12+40 2.65' L | 11+60 2.00' L | 10+80 2.10' L | 10+15 2.25' L | 10+00 2.15' L |
| (O) Elev. | 723 | 724 | 722 | 723 | 722 | 723 | 720 | 713 |

Compaction Required 100%

CONFIDENTIAL BUSINESS
INFORMATION

Technician WD/70

PROJECT: _____
JOB NO.: _____
AREA: _____

DATE: 9-23-73
DENSITY STANDARD COUNT:
MOISTURE STANDARD COUNT:

Compaction Required 305%

**CONFIDENTIAL BUSINESS
INFORMATION**

Technician

LAW ENGINEERING TESTING COMPANY
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Plant Mansley
DB NO.: G-4100
REA: See Data

DATE: 8-23-73
DENSITY STANDARD COUNT: 921
MOISTURE STANDARD COUNT: 1000

| | | | | | | | |
|----------------------------------|-------------------|-------------------|------------------|------------------|--|--|--|
| 1) Test Number | 17 | 18 | 19 | 20 | | | |
| 2) Probe Depth | | | | | | | |
| 3) Dens. Count | 408 | 458 | 430 | 418 | | | |
| 4) C ÷ Std Count | | | | | | | |
| 5) Wet Wt. (lb/ft ³) | 130.0 | 122.5 | 127.2 | 128.7 | | | |
| 6) Moist Count | 1090 | 1160 | 1080 | 1000 | | | |
| 7) F ÷ Std Count | | | | | | | |
| 8) Wt. Moist (lbs) | 21.5 | 23.2 | 21.3 | 19.3 | | | |
| 9) Dry Wt. | 108.5 | 99.3 | 105.9 | 109.4 | | | |
| 10) Proctor Wt. | 106 | 100 | 100 | 100 | | | |
| 11) % Comp. I ÷ J | | | | | | | |
| 12) % Moist | | | | | | | |
| 13) Location | 10+50 270' 414 | 10+70 270' 414 | 9+00 245' 174 | 9+15 245' 174 | | | |
| 14) Elev. | 722 | 721 | 722 | 721 | | | |

CONFIDENTIAL BUSINESS
INFORMATION

Compaction Required 100 %

Technician M K

PROJECT: Plant Wansley
JOB NO.: G-4100
AREA: See Plan

DATE: 8-23-73

DENSITY STANDARD COUNT:

MOISTURE STANDARD COUNT:

| | | | | | | | | |
|----------------------------------|------------------|------------|------------------|------------|------------------|------------|------------------|------------|
| A) Test Number | 9 | Ten | 11 | 12 | 13 | 14 | 15 | 16 |
| B) Probe Depth | 6" | | | | | | | |
| C) Dens. Count | 428 | 420 | 424 | 416 | 446 | 410 | 434 | 462 |
| D) C ÷ Std Count | | | | | | | | |
| E) Wet Wt. (lb/ft ³) | 127.5 | 128.5 | 128.0 | 129.0 | 125.2 | 129.7 | 126.7 | 123.2 |
| F) Moist Count | 1120 | 108.0 | 860 | 1010 | 940 | 960 | 1200 | 940 |
| G) F ÷ Std Count | | | | | | | | |
| H) Wt. Moist (lbs) | 22.5 | 21.3 | 18.1 | 19.6 | 18.0 | 25 | 23.0 | 19.0 |
| I) Dry Wt. | 105.0 | 107.2 | 111.9 | 109.4 | 107.2 | 111.2 | 112.7 | 105.2 |
| J) Proctor Wt. | 105 | 105.0 | 109 | 116 | 106 | 119 | 111 | 105 |
| K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 110 | 100 | 114 | 119 |
| L) % Moist | | | | | | | | |
| N) Location | 15+50 240 L7E | 15+65 → | 16+00 265 L7E | 16+20 → | 14+25 290 L1E | 14+35 → | 12+50 290 L4E | 12+30 → |
| O) Elev. | 720 | 721 | 722 | 721 | 722 | 721 | 722 | 721 |

Compaction Required 100

**CONFIDENTIAL BUSINESS
INFORMATION**

Technician

ΣΚ

LAW ENGINEERING TESTING COMPANY
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Plant Mansley
JOB NO.: G-4100
AREA: Sep Dam

DATE: 8-23-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
|----------------------------------|------------------|-----------|------------------|-----------|-------------------|------------|-------------------|------------|
| B) Probe Depth | 6 inches | → | → | → | → | → | → | → |
| C) Dens. Count | 400 | 422 | 436 | 410 | 426 | 442 | 424 | 402 |
| D) C ÷ Std Count | | | | | | | | |
| E) Wet Wt. (lb/ft ³) | 131.2 | 128.7 | 126.2 | 129.7 | 127.8 | 125.7 | 128.0 | 130.7 |
| F) Moist Count | 1030 | 1010 | 1100 | 1100 | 1110 | 1120 | 1150 | 1140 |
| G) F ÷ Std Count | | | | | | | | |
| H) Wt. Moist (lbs) | 201 | 196 | 217 | 217 | 220 | 222 | 230 | 227 |
| I) Dry Wt. | 111.1 | 109.1 | 104.5 | 107.0 | 105.8 | 103.5 | 103.0 | 108.0 |
| J) Proctor Wt. | 109 | 109 | 105 | 105 | 105 | 105 | 105 | 109 |
| K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 99 | 100 | 99 |
| L) % Moist | | | | | | | | |
| M) Location | 7+75 200 L1 & | 7+90 → | 9+50 220 L1 & | 9+65 → | 11+25 250 L1 & | 11+40 → | 12+55 270 L1 & | 12+70 → |
| O) Elev. | 723 | 722 | 722 | 722 | 723 | 722 | 723 | 722 |

Compaction Required 100

CONFIDENTIAL BUSINESS
INFORMATION

Technician M. K.

LAM ENGINEERING TESTING COMPANY
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Plant Wansley
OB NO.: G-4100
REA: Sepi Dam

DATE: 8/22/73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | |
|----------------------------------|---------|-------|---------|---------|---------|-------|--|
| 1) Test Number | 17 | 18 | 19 | 20 | 21 | 22 | |
| 2) Probe Depth | | | | | | | |
| 3) Dens. Count | 424 | 474 | 428 | 440 | 406 | 426 | |
| 4) C ÷ Std Count | | | | | | | |
| 5) Wet Wt. (lb/ft ³) | 128.0 | 122.6 | 127.5 | 126.0 | 130.2 | 127.8 | |
| 6) Moist Count | 1170 | 990 | 1090 | 960 | 1030 | 1020 | |
| 7) F ÷ Std Count | | | | | | | |
| 8) Wt. Moist (lbs) | 23.4 | 19.1 | 21.5 | 18.5 | 20.1 | 19.9 | |
| 9) Dry Wt. | 104.6 | 102.9 | 106.0 | 107.5 | 110.1 | 107.9 | |
| 10) Proctor Wt. | 103 | 103 | 106 | 106 | 109 | 106 | |
| 11) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | |
| 12) % Moist | | | | | | | |
| 13) Location | 11+00 | 11+15 | 9+50 | 9+65 | 8+50 | 8+35 | |
| | 260' LT | → | 275' LT | 275' LT | 225' LT | → | |
| 14) Elev. | 719 | 720 | 722 | 721 | 723 | 722 | |

Impaction Required 100

CONFIDENTIAL BUSINESS
INFORMATION

Technician M. H.

LAW ENGINEERING TESTING COMPANY
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Plant Wansley
OB NO.: G-4100
REA: Seep. 50m

DATE: 8-22-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|----------------------------------|----------|-------|----------|-------|----------|-------|----------|-------|
| A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| B) Probe Depth | | | | | | | | |
| C) Dens. Count | 462 | 438 | 434 | 408 | 472 | 458 | 388 | 422 |
| D) C ÷ Std Count | | | | | | | | |
| E) Wet Wt. (lb/ft ³) | 123.2 | 126.3 | 126.7 | 130.0 | 122.2 | 123.7 | 132.7 | 128.2 |
| F) Moist Count | 920 | 930 | 940 | 960 | 970 | 920 | 1100 | 932 |
| G) F ÷ Std Count | | | | | | | | |
| H) Wt. Moist (lbs) | 17.5 | 17.8 | 18.0 | 18.5 | 18.7 | 17.5 | 21.7 | 17.8 |
| I) Dry Wt. | 105.7 | 108.5 | 108.7 | 111.5 | 103.5 | 106.2 | 111.0 | 110.4 |
| J) Proctor Wt. | 103 | 105 | 109 | 109 | 103 | 103 | 109 | 109 |
| K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| L) % Moist | | | | | | | | |
| M) Location | 16+00 | 16+25 | 16+00 | 16+15 | 13+85 | 14+00 | 12+80 | 12+75 |
| | 265 LT E | → | 300 LT E | → | 290 LT E | → | 310 LT E | → |
| N) Elev. | 716 | 717 | 716 | 715 | 718 | 719 | 719 | 718 |

CONFIDENTIAL BUSINESS
INFORMATION

Technician M. J.

Compaction Required 100

LAW ENGINEERING TESTING COMPANY
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Plant Mansley
 JOB NO.: 251
 REA: Seep Dam

DATE: 8/22/73

DENSITY STANDARD COUNT: 251

MOISTURE STANDARD COUNT: 1271

| 1) Test Number | 2 | 3 | 4 | 5 | Six | 7 | 8 |
|----------------------------------|------------------|-------------------|------------|-------------------|------------|-------------------|------------|
| 3) Probe Depth | | | | | | | |
| 2) Dens. Count | 470 | 442 | 470 | 440 | 438 | 466 | 478 |
| 2) C ÷ Std Count | | | | | | | |
| 3) Wet Wt. (lb/ft ³) | 122.0 | 125.7 | 122.0 | 125.8 | 126.2 | 123.8 | 121.2 |
| 3) Moist Count | 1020 | 1040 | 1030 | 970 | 960 | 1020 | 910 |
| 3) F ÷ Std Count | | | | | | | |
| 1) Wt. Moist (lbs) | 19.9 | 20.3 | 20.1 | 18.7 | 18.5 | 19.9 | 17.3 |
| 1) Dry Wt. | 102.1 | 105.4 | 101.9 | 107.1 | 107.7 | 102.9 | 108.9 |
| 1) Proctor Wt. | 100 | 103 | 100 | 105 | 105 | 103 | 103 |
| 1) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| 1) % Moist | | | | | | | |
| 1) Location | 9+50 250' LTR | 11+00 260' LTR | 11+15 → | 13+50 260' LTR | 13+70 → | 14+50 265' LTR | 14+65 → |
| 1) Elev. | 718 | 718 | 717 | 718 | 717 | 718 | 717 |

CONFIDENTIAL BUSINESS
INFORMATION

Technician M. J. K.

Impaction Required 100

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: _____

DATE: 6-22-73
DENSITY STANDARD COUNT: 222
MOISTURE STANDARD COUNT: 1571

| | | | | | | | |
|-----------------------------------|---------|---------|---------|---------|---------|---------|---------|
| (A) Test Number | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | |
| (C) Dens. Count | 428 | 428 | 418 | 418 | 418 | 418 | 418 |
| (D) C ÷ Std Count | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 126.5 | 126.5 | 129.0 | 130.0 | 123.5 | 123.5 | 123.5 |
| (F) Moist Count | 958 | 958 | 1070 | 1070 | 1058 | 1058 | 1058 |
| (G) F ÷ Std Count | | | | | | | |
| (H) Wt. Moist (lbs) | 12.5 | 12.5 | 21.5 | 21.2 | 17.6 | 17.9 | 17.9 |
| (I) Dry Wt. | 10.5 | 10.5 | 108.5 | 110.5 | 105.7 | 106.1 | 106.1 |
| (J) Proctor Wt. | | | | | | | |
| (K) % Comp. I ÷ J | | | 100 | 11 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | |
| (N) Location | 15' L 4 | 15' L 4 | 15' L 4 | 15' L 4 | 15' L 4 | 15' L 4 | 15' L 4 |
| (O) Elev. | 717 | 717 | 713 | 719 | 718 | 717 | 720 |

**CONFIDENTIAL BUSINESS
INFORMATION**

Compaction Required 1.50 / cu.

Technician

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: LAKE MEADOW

JOB NO.: 1-1

AREA: SEPARATION

DATE: 8-21-70

DENSITY STANDARD COUNT: 500

MOISTURE STANDARD COUNT: 1200

| | | | | | | | |
|-----------------------------------|-----------------------------|-----------------------------|-----------------------------|-----------------------------|-----------------------------|-----------------------------|--|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | |
| (B) Probe Depth | 2" | | | | | | |
| (C) Dens. Count | 456 | 466 | 474 | 452 | 462 | 468 | |
| (D) C ÷ Std Count | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 124.0 | 122.5 | 122.0 | 124.5 | 123.5 | 122.5 | |
| (F) Moist Count | | | | | | | |
| (G) F ÷ Std Count | 95.2 | 944 | 975 | 918 | 940 | 978 | |
| (H) Wt. Moist (lbs) | 18.9 | 18.0 | 18.2 | 18.2 | 18.6 | 18.7 | |
| (I) Dry Wt. | 105.1 | 104.5 | 102.7 | 106.3 | 105.5 | 103.8 | |
| (J) Proctor Wt. | 105 | 105.0 | 103 | 106.7 | 106.3 | 103 | |
| (K) % Comp. I ÷ J | 100 | 100 | 106 | 106 | 100 | 110 | |
| (L) % Moist | | | | | | | |
| (N) Location | 1140 350' 60' | 11415 360' 2' | 12451 320' 2' | 12465 330' 2' | 13485 360' 2' | 14100 315' 2' | |
| (O) Elev. | 709 | 708 | 707 | 710 | 711 | 712 | |

Compaction Required 100%

CONFIDENTIAL BUSINESS
INFORMATION

Technician

UD/70

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WANSLEY
JOB NO.: _____
AREA: _____

DATE: AUG 21, 73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

SEPARATION DAM

| | | | | | | | | |
|-----------------------------------|-------------------|-------------------|--------------------|--------------------|--------------------|-------------------|------------------|-------------------|
| (A) Test Number | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 |
| (B) Probe Depth | 6" | | | | | | | 6" |
| (C) Dens. Count | 462 | 458 | 490 | 486 | 456 | 432 | 424 | 430 |
| (D) C ÷ Std Count | 123.5 | 124.0 | 119.0 | 120.5 | 124.0 | 107.0 | 122.0 | 107.2 |
| (E) Wet Wt. (lb/ft ³) | | | | | | | | |
| (F) Moist Count | 1032 | 950 | 1072 | 1168 | 1016 | 1010 | 1020 | 940 |
| (G) F ÷ Std Count | 20.1 | 18.2 | | 23.7 | 19.9 | | | |
| (H) Wt. Moist (lbs) | 103.4 | 105.8 | 21.1 | | | 19.6 | 19.9 | 18.1 |
| (I) Dry Wt. | | 106.0 | 97.9 | 93.4 | 104.1 | 107.4 | 108.1 | 109.2 |
| (J) Proctor Wt. | 103.0 | | 100 | 100.0 | 103.0 | 106 | 106 | 107 |
| (K) % Comp. I ÷ J | 100% | 100% | 97.9 | 93.4 | 100% | 100 | 100 | 100 |
| (L) % Moist | | | REROLLED | REROLLED | | | | |
| (N) Location | 13+40 225 LT E | 15+00 225 LT E | 14+90 230' LT E | 16+20 240' LT E | 16+25 230' LT E | 14+00 320 LT E | 1420 320 LT E | 12+50 320 LT E |
| (O) Elev. | 716 | 715 | 716 | 715 | 716 | 715 | 714 | 715 |

* LIGHT MATERIAL NOT USED AGAIN

Compaction Required 100%

Technician M. K. C.E.

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: _____

SEPARATION DAM

DATE: 8/21/73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
|-----------------------------------|-------------------|------------------|------------------|------------------|-------------------|-------------------|-------------------|-------------------|
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 452 | 452 | 464 | 500 | 458 | 462 | 454 | 490 |
| (D) C ÷ Std Count | 109.3 | 109.5 | 123.0 | 119.0 | 124.0 | 123.5 | 124.0 | 120.0 |
| (E) Wet Wt. (lb/ft ³) | | | | | | | | |
| (F) Moist Count | 1030 | 1030 | 980 | 948 | 1020 | 1010 | 1056 | 1096 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 20.7 | 20.7 | 18.9 | 18.2 | 19.9 | 19.6 | 20.8 | 21.7 |
| (I) Dry Wt. | 107.9 | 107.7 | 104.1 | 100.8 | 104.1 | 103.9 | 103.2 | 98.3 |
| (J) Proctor Wt. | 106. | 106. | 103.0 | 100 | 103 | 103* | 1030 | 100.0 |
| (K) % Comp. I ÷ J | 100% | 100% | 100% | 100% | 100% | 100% | 100% | 98.3 |
| (L) % Moist | | | | | | | | RECORDED |
| (N) Location | 14150 250' L18 | 14135 25027 E | 9+50 225' L18 | 9+70 225' L18 | 11+10 230' L18 | 11+20 220' L18 | 13+50 225' L18 | 13+70 225' L18 |
| (O) Elev. | 711 | 710 | 712 | 711 | 715 | 716 | 717 | 718 |

Compaction Required 100

CONFIDENTIAL BUSINESS
INFORMATION

Technician MIKE K. CE

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____

JOB NO.: _____

AREA: _____

DATE: 8/21/53

DENSITY STANDARD COUNT: 231

MOISTURE STANDARD COUNT: 1271

SEPARATION

| | | | | | | | | |
|-----------------------------------|--------------------|-----------|------------|------------|------------|-----------------|-------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | 6" |
| (C) Dens. Count | 444 | 448 | 452 | 476 | 402 | 212 | 418 | 302 |
| (D) C ÷ Std Count | 125.5 | 25.2 | 122.7 | 121.7 | 150.7 | 150.5 | 127.0 | 122.2 |
| (E) Wet Wt. (lb/ft ³) | | | | | | | | |
| (F) Moist Count | 870 | 1700 | 1010 | 1030 | 1080 | 1110 | 1110 | 1000 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 13.5 | 10.3 | 10.1 | 10.1 | 20.8 | 22.0 | 22.0 | 21.5 |
| (I) Dry Wt. | 109.2 | 175.9 | 104.1 | 101.6 | 109.9 | 127.5 | 109.9 | 105.7 |
| (J) Proctor Wt. | 105 | 106 | 103 | 100 | 105 | 112 | 113 | 110 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 9400 225' 41" S | 9415 → | 10450 → | 10455 → | 12400 → | 12415 250412 | 13120 | 13120 |
| (O) Elev. | 709 | 10 | 708 | 709 | 711 | 712 | | |

Compaction Required 100

Technician M/KE K

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: W. 2nd St.
JOB NO.: 1
AREA: 0.0001

DATE: 8.2.1.73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1211

| | | | | | | | | |
|-----------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 |
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 418 | 436 | 452 | 448 | 436 | 425 | 447 | 412 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 128.5 | 126.5 | 124.5 | 125.0 | 126.5 | 127.5 | 125.5 | 123.0 |
| (F) Moist Count | 994 | 988 | 1120 | 1016 | 998 | 1014 | 911 | 855 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 19.1 | 19.1 | 22.2 | 19.7 | 19.3 | 22.0 | 17.5 | 16.7 |
| (I) Dry Wt. | 109.4 | 107.4 | 102.3 | 105.1 | 107.2 | 105.5 | 108.0 | 106.1 |
| (J) Proctor Wt. | 109.6 | 106.3 | 100.5 | 105.0 | 106.3 | 111 | 106.3 | 111 |
| (K) % Comp. I ÷ J | 100 | 100.1 | 111 | 110 | 100.1 | 100 | 100.3 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 9490 | 10400 | 12450 | 12460 | 12475 | 12480 | 16150 | 16160 |
| | 350'2 | 360'2 | 330'2 | 340'2 | 365'2 | 370'2 | 300'2 | 310'2 |
| (O) Elev. | 713 | 714 | 715 | 716 | 716 | 717 | 716 | 717 |

Compaction Required 100%

Technician U.D. / 70

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Waples
JOB NO.: 1111
AREA: 1111

DATE: 8-21-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 414 | 406 | 434 | 422 | 438 | 430 | 446 | 428 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 129.5 | 130.5 | 126.5 | 128.5 | 126.0 | 127.0 | 125.5 | 127.5 |
| (F) Moist Count | 978 | 964 | 978 | 976 | 922 | 934 | 946 | 932 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 18.9 | 18.5 | 18.9 | 18.9 | 17.5 | 17.8 | 18.2 | 17.8 |
| (I) Dry Wt. | 110.6 | 112.0 | 107.6 | 109.6 | 108.5 | 109.2 | 107.3 | 109.7 |
| (J) Proctor Wt. | 109.0 | 109.0 | 106.3 | 109.0 | 106.3 | 109.0 | 106.3 | 109.0 |
| (K) % Comp. I ÷ J | 100.1 | 100.1 | 100.4 | 100.4 | 100.4 | 100.4 | 100.4 | 100.4 |
| (L) % Moist | | | | | | | | |
| (N) Location | 10+50 | 10+60 | 10+100 | 12+20 | 15+100 | 5+20 | 11+10 | 11+15 |
| | 225' L | 230' L | 280' L | 270' L | 300' L | 285' L | 180' L | 185' L |
| (O) Elev. | 713 | 714 | 714 | 715 | 715 | 716 | 714 | 715 |

Compaction Required

100%

Technician

UD/70

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: SOP Dam

DATE: 9/21/73
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| | | | | | | |
|-----------------------------------|------------------|------------|------------|--|--|--|
| (A) Test Number | 25 | 26 | 27 | | | |
| (B) Probe Depth | | | | | | |
| (C) Dens. Count | 446 | 452 | 480 | | | |
| (D) C ÷ Std Count | 1 | | | | | |
| (E) Wet Wt. (lb/ft ³) | 125.2 | 124.2 | 121.2 | | | |
| (F) Moist Count | 1050 | 910 | 1150 | | | |
| (G) F ÷ Std Count | 20.6 | 17.3 | 23.0 | | | |
| (H) Wt. Moist (lbs) | 104.6 | 96.9 | 98.2 | | | |
| (I) Dry Wt. | 103 | 105 | 99 | | | |
| (J) Proctor Wt. | | | | | | |
| (K) % Comp. I ÷ J | 100 | 100 | 99.1 | | | |
| (L) % Moist | | | | | | |
| (N) Location | 10+50 390.279 | 10+60 → | 10+70 → | | | |
| (O) Elev. | 713 | 712 | 710 | | | |

Compaction Required 150

CONFIDENTIAL BUSINESS
INFORMATION

Technician M. H.

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: Sep Duke

DATE: 3/20/73
DENSITY STANDARD COUNT: _____
MOISTURE STANDARD COUNT: _____

| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
|-----------------------------------|-------------------|------------|------------|------------|-------------------|------------|-------------------|------------|
| (B) Probe Depth | | | | | | | | |
| (C) Dens. Count | 444 | 430 | 430 | 432 | 416 | 422 | 406 | 438 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 125.5 | 127.2 | 127.2 | 127.0 | 129.0 | 128.2 | 130.2 | 126.0 |
| (F) Moist Count | 1070 | 1100 | 970 | 1030 | 1030 | 1040 | 1110 | 1090 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 21.1 | 22.0 | 18.7 | 20.1 | 20.1 | 22.3 | 22.0 | 20.1 |
| (I) Dry Wt. | 104.4 | 105.2 | 108.5 | 106.9 | 108.9 | 107.9 | 107.2 | 105.9 |
| (J) Proctor Wt. | 103.0 | 103.0 | 106.0 | 106 | 106 | 106 | 106 | 106 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 11+00 320' L79 | 10+85 → | 12+00 → | 12+50 → | 13+00 325' L79 | 13+15 → | 14+00 306' L79 | 14+20 → |
| (O) Elev. | 708 | 707 | 710 | 709 | 711 | 710 | 708 | 709 |

Compaction Required _____

CONFIDENTIAL BUSINESS
INFORMATION

Technician M. H.

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WAPAS/10
JOB NO.: 1110
AREA: SEPARATION Dike

DATE: 8-20-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 464 | 500 | 464 | 456 | 476 | 492 | 412 | 474 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (1b/ft ³) | 123.0 | 119.0 | 123.0 | 124.0 | 121.5 | 119.5 | 127.5 | 122.0 |
| (F) Moist Count | 892 | 846 | 934 | 902 | 996 | 988 | 1046 | 1036 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 16.9 | 15.8 | 17.8 | 17.1 | 19.7 | 19.1 | 20.6 | 20.3 |
| (I) Dry Wt. | 106.1 | 103.2 | 105.2 | 106.9 | 102.2 | 100.4 | 108.9 | 101.7 |
| (J) Proctor Wt. | 106.3 | 102 | 105 | 106.3 | 100 | 100 | 106.3 | 100 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 10+80 | 10+95 | 11+75 | 11+85 | 13+25 | 13+45 | 14+60 | 14+75 |
| | 200' Lick | 210' Lick | 225' Lick | 350' Lick | 200' Lick | 220' Lick | 300' Lick | 315' Lick |
| (O) Elev. | 708 | 709 | 709 | 710 | 711 | 712 | 710 | 711 |

Compaction Required 100%

CONFIDENTIAL BUSINESS
INFORMATION

Technician VD/-10

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: Dep. Dike

DATE: 8/17/73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | |
|-----------------------------------|------------------|------------------|------------------|--------------|--|--|--|
| (A) Test Number | 9 | 10 | 11 | 12 | | | |
| (B) Probe Depth | 6" | Six inches | 6" | 6" | | | |
| (C) Dens. Count | 430 | 440 | 416 | 428 | | | |
| (D) C ÷ Std Count | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 126.2 | 126.2 | 129.0 | 127.5 | | | |
| (F) Moist Count | 1000 | 1000 | 1080 | 1000 | | | |
| (G) F ÷ Std Count | | | | | | | |
| (H) Wt. Moist (lbs) | 17.5 | 19.3 | 21.3 | 20.8 | | | |
| (I) Dry Wt. | 107.4 | 105.9 | 107.7 | 106.7 | | | |
| (J) Proctor Wt. | 105 | 105 | 115 | 115 | | | |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | | | |
| (L) % Moist | | | | | | | |
| (N) Location | 10400 17027 E | 12445 17027 E | 13400 20027 E | 13420 --- | | | |
| (O) Elev. | 704 | 703 | 702 | 703 | | | |

Compaction Required 100

Technician M.H.

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: Sep. Drive

DATE: 8/17/77
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1200

| | | | | | | | | |
|-----------------------------------|----------------|------------|-----------------|------------|-----------------|-----------------|-----------------|-----------------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | 6" | 6" | 6" | 6" | 6" | 6" | 6" |
| (C) Dens. Count | 422 | 422 | 440 | | 422 | 420 | 428 | 424 |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 123.2 | 123.2 | 126.3 | | 123.2 | 126.5 | 127.5 | 128.0 |
| (F) Moist Count | 1260 | 1030 | 1210 | 1200 | 1060 | 1130 | 1000 | 1010 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 25.4 | 20.1 | 24.2 | 25 | 20.8 | 22.4 | 12.4 | 20.8 |
| (I) Dry Wt. | 101.8 | 123.1 | 102.1 | 101.3 | 107.9 | 106.1 | 100.2 | 107.2 |
| (J) Proctor Wt. | 100 | 105 | 100 | 100 | 105 | 105 | 100 | 105 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 2250 325' ± | 12470 → | 11450 350' ± | 11470 → | 10470 325' ± | 10450 325' ± | 10475 250' ± | 10470 200' ± |
| (O) Elev. | 405 | 104 | 405 | 404 | 404 | 400 | 702 | 702 |

Compaction Required 100

CONFIDENTIAL BUSINESS
INFORMATION

Technician ML MA

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: 1100000000
JOB NO.: 1100
AREA: SEPARATION

DATE: 2-16-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1071

| | | | | | | | |
|-----------------------------------|------------|------------|---------|---------|---------|---------|--|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | |
| (B) Probe Depth | 6" | | | | | | |
| (C) Dens. Count | 462 | 472 | 448 | 426 | 456 | 464 | |
| (D) C ÷ Std Count | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 123.0 | 123.0 | 125.0 | 128.0 | 124.0 | 123.0 | |
| (F) Moist Count | 1084 | 1154 | 1085 | 1104 | 1026 | 1177 | |
| (G) F ÷ Std Count | 2 | | | | | | |
| (H) Wt. Moist (lbs) | 27.5 | 24.5 | 22.5 | 23.0 | 21.0 | 12.0 | |
| (I) Dry Wt. | 106.5 | 108.5 | 102.5 | 105.0 | 103.0 | 101.0 | |
| (J) Proctor Wt. | 100 | 106.2 | 100 | 105.0 | 103.0 | 101.0 | |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | |
| (L) % Moist | | | | | | | |
| (N) Location | 1100000000 | 1100000000 | 12410 | 12415 | 14100 | 14120 | |
| | 390.5 L | 360.5 L | 380.5 L | 360.5 L | 300.5 L | 310.5 L | |
| (O) Elev. | 704 | 705 | 705 | 706 | 708 | 707 | |

Compaction Required 100%

CONFIDENTIAL BUSINESS
INFORMATION

Technician UD/fo

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT:
JOB NO.:
AREA:

SEPARATION

DATE: 7-16-73
DENSITY STANDARD COUNT: 21
MOISTURE STANDARD COUNT: 1271

| | | | | | | | |
|-----------------------------------|-------|-------|-------|-------|-------|-------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| (B) Probe Depth | 6" | | | | | | |
| (C) Dens. Count | 464 | 416 | 442 | 430 | 416 | 424 | 432 |
| (D) C ÷ Std Count | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 123.0 | 129.0 | 125.5 | 127.0 | 129.0 | 128.0 | 127.0 |
| (F) Moist Count | 1222 | 1120 | 1152 | 1078 | 1108 | 1114 | 1078 |
| (G) F ÷ Std Count | | | | | | | |
| (H) Wt. Moist (lbs) | 26.0 | 20.2 | 24.5 | 22.0 | 23.0 | 20.2 | 22.0 |
| (I) Dry Wt. | 97.0 | 108.8 | 101.0 | 105.0 | 106.0 | 107.7 | 105.0 |
| (J) Proctor Wt. | 97 | 106.7 | 100 | 105 | 106.3 | 106.2 | 105.5 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| (L) % Moist | | | | | | | |
| (N) Location | 10+00 | 10+20 | 11+35 | 11+30 | 12+50 | 12+75 | 13+90 |
| | 19054 | 20054 | 18054 | 17054 | 22054 | 23054 | 24054 |
| (O) Elev. | 703 | 704 | 704 | 705 | 705 | 706 | 711 |

Compaction Required 100%

Technician UD/70

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: W7100 107
JOB NO.: 107
AREA: SEPA AREA

DATE: 8-13-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 100

| | | | | | | | |
|-----------------------------------|------------|-------|-------|-------|---------------|------------|--|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | |
| (B) Probe Depth | 6" | | | | | | |
| (C) Dens. Count | 422 | 416 | 458 | 446 | 462 | 468 | |
| (D) C ÷ Std Count | 1526 | 1800 | 1982 | 1750 | 2000 | 2025 | |
| (E) Wet Wt. (lb/ft ³) | 125.0 | 129.0 | 124.0 | 125.0 | 123.5 | 122.5 | |
| (F) Moist Count | 1112 | 1084 | 955 | 1042 | 1108 | 1200 | |
| (G) F ÷ Std Count | 874 | 852 | 777 | 817 | 871 | 743 | |
| (H) Wt. Moist (lbs) | 22.0 | 21.5 | 17.0 | 20.3 | 22.0 | 24.0 | |
| (I) Dry Wt. | 106.0 | 107.5 | 105.0 | 104.7 | 101.5 | 98.5 | |
| (J) Proctor Wt. | 100.5 | 106.3 | 106.2 | 106.5 | 98 | 98 | |
| (K) % Comp. I ÷ J | 100 | 00 | 99 | 17 | 100 | 100 | |
| (L) % Moist | | | | | | | |
| (N) Location | 27 60'E | 20' E | 30' F | 24' E | 17+20 25'E | 11- 6'E | |
| (O) Elev. | 704 | 705 | 702 | 702 | 701 | 702 | |

Compaction Required 100 %

WEST TIE

Technician 607

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WINDSLEY
JOB NO.:
AREA: Dry
SEPARATION

DATE: 8-13-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1211

| | | | | | | | | |
|-----------------------------------|-----------|-------|-------|-------|-----------|-------|-------|-------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 480 | 478 | 420 | 426 | 462 | 478 | 512 | 492 |
| (D) C-1 Std Count | 2113 | 2069 | 1818 | 1894 | 2000 | 2069 | 2216 | 2079 |
| (E) Wet Wt. (lb/ft ³) | 1221.0 | 121.5 | 128.5 | 127.5 | 123.5 | 121.5 | 117.5 | 120.0 |
| (F) Moist Count | 1232 | 1130 | 936 | 900 | 1066 | 1090 | 1256 | 1020 |
| (G) F ÷ Std Count | 967 | 889 | 736 | 708 | 838 | 857 | 988 | 802 |
| (H) Wt. Moist (lbs) | 24.7 | 22.5 | 13.0 | 17.0 | 21.0 | 21.5 | 23.0 | 19.7 |
| (I) Dry Wt. | 76.5 | 77.0 | 110.5 | 110.5 | 102.5 | 106.0 | 78.5 | 100.3 |
| (J) Proctor Wt. | 78.0 | 95 | 107 | 101 | 103 | 98 | 78 | 78 |
| (K) % Comp. I ÷ J | 98 | 100 | 100 | 100 | 99 | 100 | | 100 |
| (L) % Moist | Rechecked | | | | Rechecked | | | |
| (N) Location | 14+80 | 14+65 | 13+00 | 13+20 | 12+20 | 12+10 | 11+00 | 11-15 |
| | 130'E | 120'E | 150'E | 160'E | 150'E | 150'E | 150'E | 100'E |
| (O) Elev. | 704 | 702 | 703 | 704 | 701 | 702 | 701 | 702 |

Compaction Required 100% Ease of West Toe Technician WD/TC

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: _____
JOB NO.: _____
AREA: SEPARATION DAM

DATE: 8/13/73
DENSITY STANDARD COUNT: 262
MOISTURE STANDARD COUNT: 1522

| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
|-----------------------------------|-----------------|------------|-----------------|------------|-----------------|-------|-------|------------|
| (B) Probe Depth | 6" | 6" | | | | 6" | | |
| (C) Dens. Count | 446 | 440 | 428 | 452 | 458 | 494 | 492 | 464 |
| (D) C ÷ Std Count | | | | | 1.75 | 1.88 | 1.88 | 1.77 |
| (E) Wet Wt. (lb/ft ³) | 125.0 | 124.0 | 127.5 | 124.5 | 127.0 | 123.0 | 123.0 | 126.5 |
| (F) Moist Count | 120 | 1160 | 1200 | 1000 | 1660 | 1120 | 730 | 1280 |
| (G) F ÷ Std Count | | | | | 1.09 | .775 | 1.114 | .820 |
| (H) Wt. Moist (lbs) | 23.1 | 23.2 | 24.0 | 19.3 | 27.5 | 18.5 | 28.2 | 21.2 |
| (I) Dry Wt. | 101.4 | 102.8 | 103.5 | 105.2 | 100.5 | 104.5 | 94.8 | 106.3 |
| (J) Proctor Wt. | 100 | 100 | 113 | 115 | 100 | 105 | 94 | 115 |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 120 | 100+ | 100+ | 100+ | 100+ |
| (L) % Moist | | | | | | | | |
| (N) Location | 11+50 250479 | 11+65 → | 12+75 200478 | 12+90 → | 13+00 300479 | 13+20 | 11+00 | 11+20 → |
| (O) Elev. | 700 | 699 | 700 | 699 | 705 | 703 | 702 | 703 |

Compaction Required 100%

CONFIDENTIAL BUSINESS
INFORMATION

Technician MIKE K

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: W Anderson
JOB NO.:
AREA: DYKE

LA DAM

DATE: 8-12-77
DENSITY STANDARD COUNT: 221
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|----------------------------|-------------------|----------------|------------------|-------------------|-------------------|--|--|
| (A) Test Number | 9 | 10 | 11 | 12 | 13 | 14 | | |
| (B) Probe Depth | 6" | | | | | | | |
| (C) Dens. Count | 404 | 406 | 416 | 406 | 414 | 428 | | |
| (D) C ÷ Std Count | | | | | | | | |
| (E) Wet Wt. (lb/ft ³) | 130.5 | 130.0 | 129.0 | 130.0 | 129.5 | 127.5 | | |
| (F) Moist Count | 1172 | 1166 | 1108 | 1086 | 1022 | 996 | | |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 23.4 | 23.4 | 22.0 | 21.7 | 19.9 | 19.3 | | |
| (I) Dry Wt. | 107.1 | 106.6 | 107.0 | 108.3 | 109.6 | 108.3 | | |
| (J) Proctor Wt. | 106.7 | 106.7 | 106.7 | 106.3 | 106.5 | 106.7 | | |
| (K) % Comp. I ÷ J | 100 | 100 | 100 | 100 | 100 | 100 | | |
| (L) % Moist | | | | | | | | |
| (N) Location | 13+75 200' L ÷ 50' ÷ | 13+85 185' L ÷ | 14+10 50' ÷ | 14+10 10' R ÷ | 12+50 100' L ÷ | 12+60 120' L ÷ | | |
| (O) Elev. | 688 700 | 704 | 703 | 702 | 699 | 700 | | |

Compaction Required 100

CONFIDENTIAL BUSINESS
INFORMATION

Technician JD

PROJECT: Wansley
JOB NO.:
AREA: Dike

SEP DA M

DATE: 8-11-73
DENSITY STANDARD COUNT: 231
MOISTURE STANDARD COUNT: 1271

| | | | | | | | | |
|-----------------------------------|-------------|----------------------|-------|-------|------------|-----------------|------------|------------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | 6" | 6" | 6" | 6" | 6" | 6" | 6" |
| (C) Dens. Count | 468 | 430 | 426 | 404 | 452 | 450 | 416 | 412 |
| (D) C ÷ Std Count | | | 127.5 | 130.5 | 124.5 | 124.5 | 122.0 | 129.5 |
| (E) Wet Wt. (lb/ft ³) | 122.5 | 127.0 | 4 | | | | | |
| (F) Moist Count | 976 | 1074 | 1008 | 1060 | 1112 | 972 | 966 | 1012 |
| (G) F ÷ Std Count | | | | | | | | |
| (H) Wt. Moist (lbs) | 18.9 | 18.7 21.1 | 19.6 | 20.8 | 22.0 | 18.7 | 18.7 | 22.0 |
| (I) Dry Wt. | 103.6 | 105.9 | 107.9 | 109.7 | 102.5 | 105.8 | 110.3 | 107.5 |
| (J) Proctor Wt. | 103 | 106.3 | 106.3 | 103 | 103 | 106.3 | 109 | 106 |
| (K) % Comp. I ÷ J | 100 | 99 | 100+ | 100 | 100 | 99 | 100 | 100 |
| (L) % Moist | | | | | | | | |
| (N) Location | 11+35 | 11+45 | 11+50 | 11+75 | 12+85 | 12+75 | 13+00 | 13+15 |
| | Along ditch | | | | 100' ditch | 120' ditch | 220' ditch | 240' ditch |
| (O) Elev. | 699 | 695 | 658 | 659 | 658 | 659 | 702 | 703 |

Compaction Required 100%

Technician UD

CONFIDENTIAL BUSINESS INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

6044 were 28.8%
6044 were 28.8%

PROJECT: Yellow Dirt
JOB NO.: SAG-638
AREA: Separation Dike

DATE: 8/11/73
DENSITY STANDARD COUNT: 2622 (131)
MOISTURE STANDARD COUNT: 16222 (76.1)

| | 7:00 AM | 7:05 AM | 7:30 AM | 1:30 PM | 2:35 PM | 2:30 PM | 3:25 PM | 3:30 PM |
|-----------------------------------|------------------------------------|------------------------------------|------------------------------------|---------------------------------|---------------------------------|---------------------------------|---------------------------------|---|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | | | 6" | 6" | 6" | 6" | 6" | 6" |
| (C) Dens. Count | | | 226 | 252 | 254 | 246 | 254 | 247 |
| (D) C ÷ Std Count | | | 1.725 | 1.920 | 1.970 | 1.880 | 1.970 | 1.885 |
| (E) Wet Wt. (lb/ft ³) | | | 122.80 | 122.00 | 121.50 | 123.00 | 120.50 | 123.00 |
| (F) Moist Count | 756 | 676 | 847 | 575 | 458 | 672 | 543 | 545 |
| (G) F ÷ Std Count | 0.860 | 0.890 | 1.111 | 0.755 | 0.605 | 0.883 | 0.715 | 0.716 |
| (H) Wt. Moist (lbs) | 23.50 | 21.75 | 28.20 | 17.75 | 13.50 | 21.50 | 16.75 | 16.75 |
| (I) Dry Wt. | | | 99.6 | 103.25 | 108.00 | 101.50 | 103.75 | 106.25 |
| (J) Proctor Wt. | | | 106.3 | 103.0 | 106.3 | 106.3 | 103.0 | 106.3 |
| (K) % Comp. I ÷ J | | | 94% | 100% | 100% | 96% | 100% | 100% |
| (L) % Moist | | | | | | | | |
| (N) Location | Sta. 13+00 125' E. of W. Toe | Sta. 13+25 120' E. of W. Toe | Sta. 13+00 150' E. of W. Toe | Sta. 14+00 80' W. of Core | Sta. 12+50 75' W. of Core | Sta. 13+00 85' W. of Core | Sta. 12+00 40' W. of Core | Sta. 13+00 85' W. of Core Retest at 14+6 |
| (O) Elev. | 701.0 | 701.0 | 701.0 | 697.0 | 697.0 | 692.0 | 697.5 | 697.0 |

+ Test # 142 for moisture only

Compaction Required 100%

CONFIDENTIAL BUSINESS
INFORMATION

Technician

[Signature]

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Yellow Dirt
JOB NO.: SAG-638
AREA: Separation Dike

DATE: 8/11/73
DENSITY STANDARD COUNT: 262 (131)
MOISTURE STANDARD COUNT: 1522 (261)

| | | | | |
|-----------------------------------|-------------------------------|---------|-------------------------------|----------|
| (A) Test Number | 9 | 4.47 gm | 10 | 24.40 gm |
| (B) Probe Depth | 6" | 6" | 6" | |
| (C) Dens. Count | 235 | 235 | 231 | |
| (D) C ÷ Std Count | 1.795 | 1.795 | 1.780 | |
| (E) Wet Wt. (lb/ft ³) | 125.50 | 125.50 | 126.00 | |
| (F) Moist Count | 578 | 578 | 560 | |
| (G) F ÷ Std Count | 0.760 | 0.760 | 0.735 | |
| (H) Wt. Moist (lbs) | 18.00 | 18.00 | 17.25 | |
| (I) Dry Wt. | 107.50 | 107.50 | 108.75 | |
| (J) Proctor Wt. | 106.3 | 106.3 | 106.3 | |
| (K) % Comp. I ÷ J | 100% | 100% | 100% | |
| (L) % Moist | | | | |
| (N) Location | Sta 11+50 35' W of Core | | Sta 11+50 43' W of Core | |
| (O) Elev. | 698.0 | | 698 | |

Compaction Required _____

CONFIDENTIAL BUSINESS
INFORMATION

Technician

Bates

GEORGIA POWER COMPANY - SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Yellow Dirt
JOB NO.: SAG-638
AREA: Separation Dike

DATE: 8/10/73
DENSITY STANDARD COUNT: 2622 (130)
MOISTURE STANDARD COUNT: 1522 (761)

| | | | | | | | | |
|-----------------------------------|---------------------------------|---------------------------------|---------------------------------|---------------------------------|---------------------------------|--------------------------------|--------------------------------|--------------------------------|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | 6" | 6" | 6" | 6" | 6" | 6" | 6" |
| (C) Dens. Count | 206 | 222 | 206 | 224 | 211 | 214 | 210 | 213 |
| (D) C ÷ Std Count | 1.57 | 1.70 | 1.57 | 1.71 | 1.61 | 1.67 | 1.61 | 1.62 |
| (E) Wet Wt. (lb/ft ³) | 133.00 | 128.50 | 133.00 | 128.00 | 131.00 | 129.50 | 131.00 | 131.00 |
| (F) Moist Count | 685 | 634 | 703 | 688 | 632 | 646 | 638 | 635 |
| (G) F ÷ Std Count | 0.900 | 0.830 | 0.924 | 0.906 | 0.830 | 0.850 | 0.850 | 0.830 |
| (H) Wt. Moist (lbs) | 22.00 | 20.00 | 22.75 | 22.25 | 20.00 | 20.75 | 20.25 | 20.00 |
| (I) Dry Wt. | 111.00 | 108.50 | 110.25 | 106.75 | 111.00 | 108.75 | 110.75 | 111.00 |
| (J) Proctor Wt. | 106.3 | 106.3 | 106.3 | 106.3 | 106.3 | 106.3 | 106.3 | 106.3 |
| (K) % Comp. I ÷ J | 100%+ | 100%+ | 100%+ | 100%+ | 100%+ | 100%+ | 100%+ | 100%+ |
| (L) % Moist | | | | | | | | |
| (N) Location | Sta. 13+00 100' E. of W. Toe | Sta. 13+00 110' E. of W. Toe | Sta. 11+50 100' E. of W. Toe | Sta. 14+50 150' E. of W. Toe | Sta. 14+50 156' E. of W. Toe | Sta. 13+00 50' E. of W. Toe | Sta. 13+10 55' E. of W. Toe | Sta. 12+00 50' E. of W. Toe |
| (O) Elev. | 700.0 | 700.0 | 694.0 | 705.0 | 705.0 | 700.5 | 700.5 | 700.5 |

Compaction Required 100%

Technician

Buckley

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: Yellow Dirt
JOB NO.: 5A6-638
AREA: Separation Dike

DATE: 8/10/73
DENSITY STANDARD COUNT: 262 (131)
MOISTURE STANDARD COUNT: 1522 (761)

| | | | | | | | | | |
|-----------------------------------|---------------------------------|---------------------------------|---------------------------------|---------------------------------|---------------------------------|--|--|--|--|
| (A) Test Number | 7 | 8 | 9 | 10 | 11 | | | | |
| (B) Probe Depth | 6" | 6" | 6" | 6" | 6" | | | | |
| (C) Dens. Count | 246 | 224 | 231 | 225 | 241 | | | | |
| (D) C ÷ Std Count | 1.88 | 1.71 | 1.76 | 1.71 | 1.84 | | | | |
| (E) Wet Wt. (lb/ft ³) | 123.00 | 128.00 | 126.50 | 128.00 | 124.00 | | | | |
| (F) Moist Count | 863 | 755 | 693 | 802 | 735 | | | | |
| (G) F ÷ Std Count | 1.13 | .990 | .910 | 1.080 | 0.970 | | | | |
| (H) Wt. Moist (lbs) | 28.50 | 24.75 | 22.25 | 27.25 | 24.25 | | | | |
| (I) Dry Wt. | 94.50 | 107.25 | 104.25 | 100.75 | 99.75 | | | | |
| (J) Proctor Wt. | 106.3 | 106.3 | 106.3 | 106.3 | 106.3 | | | | |
| (K) % Comp. I ÷ J | 89% | 100% | 98% | 95% | 94% | | | | |
| (L) % Moist | | | | | | | | | |
| (N) Location | STA. 13+00 125' E. of W. Toe | STA. 12+50 125' E. of W. Toe | STA. 12+00 125' E. of W. Toe | STA. 13+00 100' E. of W. Toe | STA. 13+25 105' E. of W. Toe | | | | |
| (O) Elev. | 700.8 | 700.5 | 700.0 | 701.0 | 701.0 | | | | |

Note: Material was to wet, fill was stopped.

Note: Moisture was checked with the "Speedy" in this area; it was 27.6%.

Compaction Required

100%

Technician

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WANSLEY
JOB NO.: SEP. DAB
AREA: SEP. DAB

DATE: AUG 7
DENSITY STANDARD COUNT: 262
MOISTURE STANDARD COUNT: 1522

| | | | | | | | | |
|-----------------------------------|------------------|---------|----------|---------|---------|---|---|----|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | | | | | | | 6" |
| (C) Dens. Count | 488 | 484 | 496 | 490 | 490 | | | |
| (D) C ÷ Std Count | 0.848 | 1.85 | 1.89 | 1.87 | 1.87 | | | |
| (E) Wet Wt. (lb/ft ³) | 126.0 | 124.0 | 123.0 | 123.5 | 123.5 | | | |
| (F) Moist Count | 1294 | 1316 | 1426 | 1188 | 1258 | | | |
| (G) F ÷ Std Count | 0.850 | 0.863 | 0.935 | 0.780 | 0.825 | | | |
| (H) Wt. Moist (lbs) | 20.5 | 21.0 | 23.0 | 18.5 | 20.0 | | | |
| (I) Dry Wt. | 105.5 | 103 | 100.0 | 105.0 | 103.5 | | | |
| (J) Proctor Wt. | 105 | 103 | 103.0 | 105.0 | 103 | | | |
| (K) % Comp. I ÷ J | 100% | 100% | 97% | 100% | 100% | | | |
| (L) % Moist | | | REROLLED | | | | | |
| (N) Location | 13+50 | 13+00 | 13+00 | 13+50 | 13+25 | | | |
| | 200'W E | 200'W E | 250'W E | 250'W E | 225'W E | | | |
| (O) Elev. | 696 | 697 | 697 | 698 | 696 | | | |

Technician EDWARDS

Compaction Required 100%

CONFIDENTIAL BUSINESS
INFORMATION

GEORGIA POWER COMPANY — SOILS
NUCLEAR DENSITY METER WORK SHEET

PROJECT: WANSLEY

JOB NO.: 1


AREA: SEPARATION DAM

DATE: AUG 6 1973
DENSITY STANDARD COUNT: 241 260
MOISTURE STANDARD COUNT: 111 1522


| | | | | | | | | |
|-----------------------------------|---------------------------|------------------------------|------------------------------|----|----|----|----|----|
| (A) Test Number | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| (B) Probe Depth | 6" | 6" | 6" | 6" | 6" | 6" | 6" | 6" |
| (C) Dens. Count | 504 | 494 | 548 | | | | | |
| (D) C ÷ Std Count | 1.92 | 1.89 | 2.09 | | | | | |
| (E) Wet Wt. (lb/ft ³) | 124.5 | 122.0 | 117.0 | | | | | |
| (F) Moist Count | 1038 | 1070 | 1086 | | | | | |
| (G) F ÷ Std Count | 0.683 | 0.704 | 0.713 | | | | | |
| (H) Wt. Moist (lbs) | 15.8 | 16.3 | 16.6 | | | | | |
| (I) Dry Wt. | 108.7 | 106.2 | 100.4 | | | | | |
| (J) Proctor Wt. | 107 | 106.0 | 103 | | | | | |
| (K) % Comp. I ÷ J | 100% | 100% | 97% | | | | | |
| (L) % Moist | | | REROLLED | | | | | |
| (N) Location | 13+50 40' E. W. TOE | 13+50 50' E. W. W. TOE | 13+40 40' E. W. W. TOE | | | | | |
| (O) Elev. | 695 | 695 | 695 | | | | | |

Compaction Required 100%


Technician L. ANKFOED



UNDER CONSTRUCTION




STEADY SEEPAGE



STORAGE POND DRAWDOWN EL. 795 - EL. 725

CIRCLE ANALYSIS

SECTION A-A



TOTAL STRESS
SOIL CHARACTERISTICS

| TYPE SOIL | CONSTRUCTIVE | | STEADY SEEPAGE | | DRAWDOWN | |
|------------------|---------------|--------------------|----------------|--------------------|---------------|--------------------|
| | DEPTH FEET | DEGREES PERCENT | DEPTH FEET | DEGREES PERCENT | DEPTH FEET | DEGREES PERCENT |
| EMB. FILL (A) | 12.4 | 26.5 | 12.00 | 12.4 | 19 | 14.00 |
| FILTER (B) | 130 | 40 | 0 | 130 | 40 | 0 |
| RIP-RAP (C) | 130 | 38 | 0 | 130 | 38 | 0 |
| BEDROCK (D) | 150 | 40 | 3000 | 150 | 40 | 3000 |
| FILL 1 (E) | 112 | 8 | 550 | 112 | 12 | 700 |

NOTES:


- SAFETY FACTORS SHOWN ARE THE MINIMUM FOR EACH CONDITION. COMPLETE COMPUTER RESULTS AVAILABLE FROM SOUTHERN SERVICE, INC.
- SAFETY FACTORS DO NOT INCLUDE BENEFIT FROM DEPOSIT OF ASH.
- SOIL CHARACTERISTICS FROM LAW ENGINEERING AND TESTING CO. THROUGH GEORGIA POWER CO.
- MATERIALS RECOMMENDED BY LETCO FOR EMBANKMENT FILLS ARE: A. FINE TO MEDIUM SANDY SILT (WEST BORROW); B. STIFF TO HARD FINE TO MEDIUM MICACEOUS SILT (NORTH BORROW); C. PARTIALLY WEATHERED ROCK (LETCO REPORT NO. 40, OCT. 1972). USE OF FINE TO COARSE SAND AND HIGHLY MICACEOUS SOILS IN THE EMBANKMENT SHOULD BE AVOIDED, HOWEVER, SAND CAN BE USED IN THE DRAINS.
- EMBANKMENT FILLS SHALL BE COMPACTED AT LEAST TO SECURE THE DESIGN STRENGTH CHARACTERISTICS USED IN THE ANALYSIS OF SLOPES. FIELD CONTROL SHOULD ENSURE THE DESIGN STRENGTH OF THE MATERIALS USED IN THE DESIGN.


CONFIDENTIAL BUSINESS INFORMATION
WAN-API 009

| | |
|---------------------------------|-------------------|
| GEORGIA POWER CO., ATLANTA, GA. | |
| GENERAL ENGINEERING DEPARTMENT | |
| PLANT WANSLEY | |
| SEPARATION DIKE | |
| STABILITY ANALYSIS-SHEET 1 OF 3 | |
| DATE: 6-7-73 | SCALE: 1"=50'-0" |
| DRAWING NUMBER: 10-209 | SHEET NO. H-12496 |

RETURN TO HYDRO


30X







NOTE: DIMENSIONS SHOWN IN THIS DRAWING ARE TYPICAL FOR THIS SECTION


UNDER CONSTRUCTION



UNDER CONSTRUCTION



STEADY SEEPAGE



| TYPE | CONSTRUCTION | | | STEADY SEEPAGE | | |
|---------------|--------------|------------------|------------------|------------------|------------------|------------------|
| | SOIL | γ _{sat} | γ _{sub} | γ _{sat} | γ _{sub} | γ _{sub} |
| EMB. FILL (A) | 12.4 | 26.5 | 1200 | 12.4 | 19 | 1400 |
| FILTER (B) | 130 | 40 | 0 | 130 | 40 | 0 |
| RIP-RAP (C) | 130 | 30 | 8 | 130 | 30 | 8 |
| BEDROCK (D) | 150 | 40 | 3000 | 150 | 40 | 3000 |
| FDN. 1 (E) | 112 | 8 | 550 | 112 | 12 | 700 |
| FDN. 2 (F) | 120 | 12 | 1300 | 120 | 12 | 1300 |


NOTE: FOR GENERAL NOTES SEE DWG. H-12396.


CONFIDENTIAL BUSINESS INFORMATION
WAN-API 010

| | |
|---------------------------------|--------------------|
| GEORGIA POWER CO., ATLANTA, GA. | |
| GENERAL ENGINEERING DEPARTMENT | |
| PLANT WANSLEY | |
| SEPARATION DIKE | |
| STABILITY ANALYSIS-SHEET 2 OF 3 | |
| DATE: 6-27-73 | SCALE: 1" = 20' |
| DRAWING NUMBER: 10-209 | SHEET NO.: H-12397 |


RETURN TO HYDRO

30x








UNDER CONSTRUCTION



UNDER CONSTRUCTION



STEADY SEEPAGE




STEADY SEEPAGE

TOTAL STRESS
SOIL CHARACTERISTICS


| TYPE SOIL | CONSTRUCTION | | STEADY SEEPAGE | | DRAWDOWN | |
|---------------|--------------|---------|----------------|---------|----------|---------|
| | FEET | DEGREES | FEET | DEGREES | FEET | DEGREES |
| EMP. FILL (A) | 124 | 26.5 | 120 | 19 | 14.00 | |
| FILTER (B) | 130 | 40 | 0 | 130 | 40 | 0 |
| RIP-RAP (C) | 130 | 38 | 0 | 130 | 38 | 0 |
| BEDROCK (D) | 150 | 40 | 30.00 | 150 | 40 | 30.00 |
| FOOTING (E) | 112 | 8 | 550 | 112 | 12 | 700 |

- NOTE:
- FOR SECTION C-C ONLY, MATERIAL "B" EXISTS IN SITU. PROPER CARE SHALL BE TAKEN TO COMPACT THIS MATERIAL IN ACCORDANCE WITH THE SPECIFICATIONS. FIELD INSPECTION MUST BE MADE TO INSURE EXISTENCE OF THIS MATERIAL AS SHOWN.
 - FOR GENERAL NOTES SEE DWG. H-12396.
 - FOR CONSTRUCTION DETAILS SEE DWG. H-12365.



STORAGE POND DRAWDOWN EL. 795 - EL. 725

CIRCLE ANALYSIS




STORAGE POND DRAWDOWN EL. 795 - EL. 725

WEDGE ANALYSIS

CONFIDENTIAL BUSINESS INFORMATION
WAN-API 011

| | | | |
|---|--------------------------|---------------------------|---------------------|
| GEORGIA POWER CO., ATLANTA, GA. GENERAL ENGINEERING DEPARTMENT | | | |
| SEPARATION DIKE STABILITY ANALYSIS SHEET 3 OF 3 | | | |
| DESIGNED BY H. R. RAY | CHECKED BY H. R. RAY | SCALE AS SHOWN | DATE 6-7-73 |
| DRAWN BY H. R. RAY | APPROVED BY H. R. RAY | DRAWING NUMBER H-12396 | SHEET NO. 3 OF 3 |

30X




RETURN TO HYDRO

PLANT WANSLEY

SEPARATION DAM


STA 2+00




CONFIDENTIAL BUSINESS
INFORMATION

WAN-API 044

PLANT WANSLEY
SEPARATION DAM
 STA. 12+50





CONFIDENTIAL BUSINESS
 INFORMATION



PLAN OF SEPARATION DAM

1" = 100'-0"



GEOLOGIC SECTIONS

HORIZ. SCALE: 1" = 100'-0"
VERT. SCALE: 1" = 20'-0"

- ☐ STIFF CLAY AND SILT MATERIAL TO REMAIN IN PLACE
- ☐ SOFT CLAY AND SILT MATERIAL TO BE REMOVED
- ☐ SAND AND GRAVEL MATERIAL TO BE REMOVED
- ☐ SAND AND GRAVEL MATERIAL TO REMAIN IN PLACE

- NOTE:
- SOFT TO VERY SOFT ALLUVIUM (CLAY AND SILT) IS TO BE REMOVED UNDER THE SUPERVISION OF THE FIELD ENGINEER. THE APPROXIMATE BOUNDARY IS SHOWN BY THE SHADED AREA. LEAVE STIFF CLAY AND SILT IN PLACE.
 - SAND AND GRAVEL LAYER BELOW THE CLAY AND SILT IS TO BE REMOVED FROM THE HATCHED AREA ONLY. THE REST WILL BE CONSOLIDATED BY ROLLERS BEFORE PLACING EMBANKMENT FILL AND USED AS A DRAINAGE BLANKET.
 - FOR GEOLOGIC CROSS SECTIONS & OTHER RELATED DETAILS SEE LAW'S COMMUNICATION NO. 39, FIGURES 1-5, 9.
 - APPROXIMATE LOCATION OF LIMITS OF MATERIAL TO BE REMOVED ARE NOT TO BE CONSTRUED AS EXACT. ACTUAL EXCAVATION IS TO BE DETERMINED BY NATURE OF THE MATERIAL.
 - LOGS OF SOIL BORINGS MAY BE OBTAINED FROM GEORGIA POWER COMPANY OR SOUTHERN SERVICES INC.
 - USUAL STRIPPING SHOULD BE DONE AS NECESSARY BEFORE PLACING THE FILL.

REFERENCES: SEPARATION DAM

- H-2364 — DIVERSION SCHEME — STAGE DRAWINGS & SECTIONS
- H-2365 — SECTION & DETAILS
- H-2366 — CONSTRUCTION DIVERSION SCHEME — STAGE DRAWINGS & PLANS
- H-2373 — STORAGE POND DAM, SHEET 4
- H-2396 — STABILITY ANALYSIS, SHEET 1 OF 3
- H-2397 — " " " " SHEET 2 OF 3
- H-2398 — " " " " SHEET 3 OF 3
- H-2237 — GEN. ARRANGEMENT, ASH PIPE ROUTING

CONFIDENTIAL BUSINESS INFORMATION
WAN-API 012


SOUTHERN SERVICES, INC.
FOR


GEORGIA POWER CO., ATLANTA, GA.
GENERAL ENGINEERING DEPARTMENT

PLANT WANSLEY
SEPARATION DAM — GENERAL ARRANGEMENT
WITH LIMITS OF EXCAVATION

| NO. | DATE | BY | REVISIONS | FOR | DATE | BY | REVISIONS |
|-----|--------|----|-----------|----------|--------|----|-----------|
| 1 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 2 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 3 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 4 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 5 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 6 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 7 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 8 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 9 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 10 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 11 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 12 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 13 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 14 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 15 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 16 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 17 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 18 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 19 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 20 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 21 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 22 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 23 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 24 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 25 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 26 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 27 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 28 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 29 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |
| 30 | 4/1/52 | PL | | AS SHOWN | 4/1/52 | PL | |

30 X






CONFIDENTIAL BUSINESS INFORMATION
WAN-API 002

| | | | |
|---|---------|-----------|--------|
| GEORGIA POWER CO., ATLANTA, GA. GENERAL ENGINEERING DEPARTMENT | | | |
| PLANT WANSLEY UNIT NO. 1 | | | |
| ASH POND | | | |
| DATE | BY | SCALE | DATE |
| 10-209 | G-10023 | 1" = 200' | 3-1-78 |
| DRAWING NUMBER | | SHEET NO. | |
| 10-209 | | G-10023 | |

G-10023





Engineering and Construction Services Calculation

Calculation Number:
TV-WN-ECS3201-001

| | | |
|--|----------------------------------|----------------------------------|
| Project/Plant: Plant Wansley Ash Pond | Unit(s): Units 1-2 | Discipline/Area: ES&EE |
| Title/Subject: Slope Stability Analyses of Ash Pond Separation Dike | | |
| Purpose/Objective: Analyze slope stability of Ash Pond Separation Dike | | |
| System or Equipment Tag Numbers: NA | Originator: Wayne Wang | |

Contents

| Topic | Page | Attachments (Computer Printouts, Tech. Papers, Sketches, Correspondence) | # of Pages |
|---|-------|---|------------|
| Purpose of Calculation | 1 | Attachment A – Figure 1 | 1 |
| Methodology | 1 | Attachment B – Boring Log | 4 |
| Criteria & Assumptions | 1 | Attachment C – Soil Laboratory Analyses | 8 |
| Summary of Conclusions | 3 | Attachment D – Historic Soil Laboratory Analyses | 1 |
| Design Inputs/References | 3 | | |
| Body of Calculation (print outs) | 4 - 9 | | |
| | | | |
| Total # of pages including cover sheet & attachments: | 30 | | |

Revision Record

| Rev. No. | Description | Originator Initial / Date | Reviewer Initial / Date | Approver Initial / Date |
|----------|------------------------|---------------------------|-------------------------|-------------------------|
| 0 | Issued for Information | WW/8-6-10 | GHM/8-10-10 | JCP/8-10-10 |
| | | | | |
| | | | | |
| | | | | |

Notes:

Purpose of Calculation

Plant Wansley has disposed of coal combustion by-products (ash) in one main storage impoundment since 1976. The Plant Wansley ash pond was commissioned in 1975. The separation dike (ash pond dike) was installed in 1975 between the ash pond and the downstream storage water pond. The dike was constructed to a crest elevation of El. 805 with 2.3 (H):1(V) and 3 (H):1(V) upstream and downstream slopes, intermediate berms at El. 775 and El. 745, and a maximum height of approximately 105 feet.

The purpose of this calculation is to determine the stability of the separation dike of the Ash Pond.

Methodology

The calculation was performed using the following methods and software:

GeoStudio 2007 (Version 7.16, Build 4840), Copyright 1991-2008, GEO-SLOPE International, Ltd.

Bishop, Ordinary, Janbu, and Morgenstern-Price analytical methods were run. Morgenstern-Price was reported.

Criteria and Assumptions

The slope stability models were run using the following assumptions and design criteria:

- According to the USGS earthquake acceleration probability maps for the vicinity of Plant Wansley, and “Pseudostatic Coefficient for Use in Simplified Seismic Slope Stability Evaluation” published in *Journal of Geotechnical and Geoenvironmental Engineering, ASCE September 2009* by Jonathan Bray and Thaleia Travararou, a seismic load of 0.15g was used in the analyses.
- The current required minimum criteria (factors of safety) were taken from US Corps of Engineers Manual EM 1110-2-1902, October 2003 and the Georgia Department of Natural Resources, Environmental Protection, Rules for Dam Safety, Rule 391-3-8-09 Standards for the Design and Evaluation of Dams.
- The soil properties of unit weight, phi angle, and cohesion were obtained from triaxial shear testing performed on UD samples of the dike fill material obtained during drilling in July 2010 and from parameters used during the 1973 stability analysis indicated on Drawings H12396 - H12398. The triaxial shear testing was performed according to ASTM D 4767.
- Properties for ash were based on laboratory testing performed on undisturbed and remolded samples of ash from various plants and on previous project experience.
- The data obtained from piezometers BB and DD was used to provide phreatic data for the slope stability analysis for the separation dike.
- The cross-section of the dike was obtained using the following sources:

- 1) Original design Drawing No. H12365 Section G-G.
- 2) A boring conducted in July 2010.

The following soil properties were used in the analyses:

| | Dry Unit Weight (pcf) | Moist Unit Weight (pcf) | Effective Stress Parameters | | Total Stress Parameters | |
|----------------------------|-----------------------|-------------------------|-----------------------------|----------------|-------------------------|----------------|
| | | | Internal Friction Angle | Cohesion (psf) | Internal Friction Angle | Cohesion (psf) |
| Embankment Fill | 102 | 123 | 32 | 140 | 29 | 400 |
| Foundation Soil | -- | 112 | 37 | 0 | 24 | 80 |
| Foundation (Gravel Filter) | -- | 130 | 40 | 0 | 40 | 0 |
| Sluiced Ash | -- | 80 | 10 | 0 | 10 | 0 |
| Rock | -- | 150 | 40 | 3000 | 40 | 3000 |

As shown on drawing H-12398, the 1973 stability analysis used unconsolidated - undrained (UU) strength parameters of $c = 700$ psf and $\phi = 12^\circ$ for the foundation soils under a steady state loading condition. The Law Engineering Testing Company Report dated April 3, 1972, reported results for a consolidated – undrained (CU) triaxial shear test performed on a foundation sample from Boring 8.12, sample depth of 14 ft to 16 ft, or approximate Elev. 696. The total and effective parameters from this test were used in this 2010 analysis.

The following hydraulic information was used in the analyses:

| Elevation (ft) | Min. Pool | Normal Pool | Max. Pool |
|----------------|-----------|-------------|-----------|
| Ash Pond | -- | 795 | 802.6 |
| Storage Pond | 725 | 780 | -- |

Based on Georgia Power's (GP) Land Department Drawing M-187-6, Plant Wansley Ash Pond – August 2005 Survey, the top elevation of the ash in the impoundment is approximately El. 765. The normal pool is El. 795. The maximum surcharge pool is El. 802.6 which corresponds to the crest elevation of the emergency spillway. According to the Plant Wansley Ash Pond Storm Water Analysis prepared by SCG Hydro Services, the storage capacity of the ash pond from, conservatively, El. 799 to El. 802.6 is 1044 ac-ft, 2.22 times the storage necessary for the 100 year, 24 hour storm event. For our analysis, we assumed that rapid drawdown would occur from El. 802.6 of the maximum surcharge pool to El. 795, the normal pool elevation.

The normal (and maximum) pool elevation of the storage water pond is El. 780. This maximum level constraint has been established to minimize the occurrence of excessive seepage conditions along the downstream slope/toe of the dike. Based on the 1973 original slope analyses shown on

GP Drawings H12396 –H12398, the minimum pool is El. 725. We assume conservatively that rapid drawdown occurs from El. 780 to El. 725.

Summary of Conclusions

The following table lists the factors of safety for various slope stability failure conditions. All conditions are steady state except where noted. Construction cases were not considered. Based on the results of these analyses, the dike is stable. The minimum factor of safety for each load case was taken from the USACOE EM 1110-2-1902 (2003) or the Georgia Department of Natural Resources, Environmental Protection, Rules for Dam Safety, Rule 391-3-8-09 Standards for the Design and Evaluation of Dams.

| Failure Conditions | Computed Factor of Safety | Required Minimum Factor of Safety ¹ |
|--|---------------------------|--|
| Downstream Steady State | 1.9 | 1.5 |
| Downstream Seismic | 1.2 | 1.1 |
| Downstream Maximum Surcharge Pool (Ash Pond) | 1.7 | 1.4 |
| Upstream Rapid Drawdown (Ash Pond) | 1.9 | 1.3 |
| Downstream Rapid Drawdown (Storage Pond) | 1.4 | 1.3 |

¹ US Corps of Engineers Manual EM 1110-2-1902, October 2003

The analyses show that in all cases the separation dike is stable. Safety factors for all cases were acceptable and exceeded the minimum safety factors required.

Design Inputs/References

USGS Earthquake Hazards website, <http://www.usgs.gov/hazards/earthquakes/>.
 NOAA website, <http://www.srh.noaa.gov/ffc/html/rva.php>.
 Georgia Department of Natural Resources, Environmental Protection, Rules for Dam Safety.
 GPC Land Department Drawing M-187-6 Plant Wansley Ash Pond – August 2005 Survey
 GPC Drawing H10027 Project Location Map
 GPC Drawing H12363 - Plant Wansley Ash Pond Discharge Structure General Arrangement
 GPC Drawing H12364 - Plant Wansley Separation Dike Construction
 GPC Drawing H12365 - Plant Wansley Separation Dike section and Details
 GPC Drawing H12366 - Plant Wansley Separation Dike Construction
 GPC Drawing H12396 - Plant Wansley Separation Dike Stability Analysis – Sheet 1 of 3
 GPC Drawing H12397 - Plant Wansley Separation Dike Stability Analysis – Sheet 2 of 3
 GPC Drawing H12398 - Plant Wansley Separation Dike Stability Analysis – Sheet 3 of 3
 GPC Drawing H12399 - Plant Wansley Separation Dike General Arrangement
 SCG Hydro Services - Dam Safety Surveillance, 4th Quarter 2009 Report, Plant Wansley

Evaluate Storm Water Capacity of Wansley Ash Pond by SCG Hydro Services – August 2010


Body of Calculation

Calculation consists of Slope-W modeling attached.

US EPA ARCHIVE DOCUMENT

Plant Wansley Ash Pond Separation Dam Stability Analysis


Downstream Steady State



Method: Morgenstern-Price


Plant Wansley Ash Pond Separation Dam Stability Analysis

Downstream Max. Surcharge Pool (Ash Pond)




Method: Morgenstern-Price

Downstream Seismic




Plant Wansley Ash Pond Separation Dam Stability Analysis
Rapid Drawdown (Ash Pond)



Plant Wansley Ash Pond Separation Dam Stability Analysis


Rapid Drawdown (Storage Pond)




Method: Morgenstern-Price

Attachment A

Figure - Boring Location




PLAN OF SEPARATION DAM
1" = 100'-0"



GEOLOGIC SECTIONS

HORIZ. SCALE: 1" = 100'-0"

VERT. SCALE: 1" = 20'-0"



LEGEND: SAND AND GRAVEL MATERIAL TO REMAIN IN PLACE
SAND AND GRAVEL MATERIAL TO BE REMOVED

NOTE: 1. SOFT TO VERY SOFT SILTCLAY (CLAY AND SILT) IS TO BE REMOVED UNLESS THE SUPERFICIAL OF THE FIELD ENGINEER THE APPROXIMATE BOUNDARY IS SHOWN BY THE HATCHED AREA. LEAVE STIFF CLAY AND SILT IN PLACE.

2. SAND AND GRAVEL LAYERS BELOW THE CLAY AND SILT ARE TO BE REMOVED FROM THE HATCHED AREA ONLY. THE FILL WILL BE COMPOSITION OF ROLLERS BEFORE PLACING EMERGENCY FILL AND USED AS A DRAINAGE BLANKET.

3. FOR GEOLOGIC CROSS SECTIONS AND OTHER RELATED DETAILS SEE LAW'S COMMUNICATION NO. 19; FIGURES 1-5, 9.

4. APPROXIMATE LOCATION OF LIMITS OF MATERIAL TO BE REMOVED ARE NOT TO BE CONSIDERED AS EXACT. ACTUAL ELEVATION IS TO BE DETERMINED BY HISTORY OF THE MATERIAL.

5. LOSS OF SOIL BORINGS MAY BE OBTAINED FROM GEORGIA POWER COMPANY OR SOUTHERN SERVICES, INC.

6. USUAL STRIPPING SHOULD BE DONE AS NECESSARY BEFORE PLACING THE FILL.

NOTES:

1. SOFT TO VERY SOFT SILTCLAY (CLAY AND SILT) IS TO BE REMOVED UNLESS THE SUPERFICIAL OF THE FIELD ENGINEER THE APPROXIMATE BOUNDARY IS SHOWN BY THE HATCHED AREA. LEAVE STIFF CLAY AND SILT IN PLACE.
2. SAND AND GRAVEL LAYERS BELOW THE CLAY AND SILT ARE TO BE REMOVED FROM THE HATCHED AREA ONLY. THE FILL WILL BE COMPOSITION OF ROLLERS BEFORE PLACING EMERGENCY FILL AND USED AS A DRAINAGE BLANKET.
3. FOR GEOLOGIC CROSS SECTIONS AND OTHER RELATED DETAILS SEE LAW'S COMMUNICATION NO. 19; FIGURES 1-5, 9.
4. APPROXIMATE LOCATION OF LIMITS OF MATERIAL TO BE REMOVED ARE NOT TO BE CONSIDERED AS EXACT. ACTUAL ELEVATION IS TO BE DETERMINED BY HISTORY OF THE MATERIAL.
5. LOSS OF SOIL BORINGS MAY BE OBTAINED FROM GEORGIA POWER COMPANY OR SOUTHERN SERVICES, INC.
6. USUAL STRIPPING SHOULD BE DONE AS NECESSARY BEFORE PLACING THE FILL.

REFERENCES - SEPARATION DAM

- 1. L-101 - GEOTECHNICAL SURVEY - STIFF MATERIAL & SECTION
- 2. L-101 - SECTION 6 DETAILS
- 3. L-101 - GEOTECHNICAL SURVEY - STIFF MATERIAL & SECTION
- 4. L-101 - STORAGE POND DAM, SHEET 4
- 5. L-101 - STABILITY ANALYSIS, SHEET 1 OF 3
- 6. L-101 - STABILITY ANALYSIS, SHEET 2 OF 3
- 7. L-101 - STABILITY ANALYSIS, SHEET 3 OF 3
- 8. L-101 - GEOTECHNICAL SURVEY, STIFF MATERIAL & SECTION

SOUTHERN SERVICES, INC.

GEORGIA POWER CO., ATLANTA, GA.
GENERAL ENGINEERING DEPARTMENT
PLANT HANLEY
SEPARATION DAM - FIFTH DAM
WITH LIMITS OF EXCAVATION

PROJECT NO. H-2375
SHEET NO. 1

DATE: 11-1-54
BY: J. E. HANLEY
CHECKED: J. E. HANLEY
APPROVED: J. E. HANLEY
10-209 H-2375

Confidential Business Information

Attachment B

Soil Log

US EPA ARCHIVE DOCUMENT

DRILLING LOG
GEOLOGICAL SERVICES

Hole No. D-1

Sheet 1 of 4

SITE **Plant Wansley Separation Dyke** HOLE DEPTH **106** SURF. ELEV. **806**
 LOCATION **Plant Wansley** COORDINATES N **27943.78** E **61716.41**
 ANGLE **0** BEARING **0** CONTRACTOR **Ranger** DRILL NO. **N/A**
 DRILLING METHOD **H.S.A.** NO. SAMPLES **21** NO. U.D. SAMPLES **4**
 CASING SIZE **N/A** LENGTH **N/A** CORE SIZE **N/A** TOTAL % REC. **N/A**
 WATER TABLE DEPTH **26'** ELEV. **N/A** TIME AFTER COMP. **17 hours** DATE TAKEN **7/8/2010**
 TYPE GROUT **Portland** QUANTITY **N/A** MIX **1:1** DRILLING START DATE **7/7/2010**
 DRILLER **Justen Crowe** RECORDER **Korey Young** APPROVED **Korey Young** DRILLING COMP. DATE **7/7/2010**

| Depth | Elev. | Material Description, Classification and Remarks | Sample No. | Standard Penetration Test | | | Comments | % Rec | RQD |
|-------|-------|--|------------|---------------------------|----------|----|----------------------------|-------|-----|
| | | | | From To | Blows | N | | | |
| 0 | | | | | | | | | |
| 1 | | | | | | | T.O.B. water level was 62' | | |
| 2 | | | | | | | | | |
| 3 | | | | | | | | | |
| 4 | | | | | | | | | |
| 5 | | red brown micaceous SILT (ML) | 1 | 3.5-5 | 11-12-14 | 26 | | | |
| 6 | | | | | | | | | |
| 7 | | | | | | | | | |
| 8 | | | | | | | | | |
| 9 | | | | | | | | | |
| 10 | | red brown micaceous SILT (ML) | 2 | 8.5-10 | 7-6-8 | 14 | | | |
| 11 | | | | | | | | | |
| 12 | | | | | | | | | |
| 13 | | | | | | | | | |
| 14 | | | | | | | | | |
| 15 | | red brown micaceous SILT (ML) | 3 | 13.5-15 | 8-10-12 | 22 | | | |
| 16 | | | | | | | | | |
| 17 | | | | | | | UD 16-18.5 | | |
| 18 | | | | | | | | | |
| 19 | | | | | | | | | |
| 20 | | red brown micaceous SILT (ML) | 4 | 18.5-20 | 8-13-17 | 30 | | | |
| 21 | | | | | | | | | |
| 22 | | | | | | | UD 21-23.5 | | |
| 23 | | | | | | | | | |
| 24 | | | | | | | | | |



DRILLING LOG GEOLOGICAL SERVICES

Hole No. D-1

Sheet 2 of 4

| SITE | | Plant Wansley Separation Dyke | | | | TOTAL DEPTH | | SURF. ELEV. | |
|-------|-------|--|------------|---------------------------|---------|-------------|--|-------------|-----|
| | | | | | | 106 | | 806 | |
| Depth | Elev. | Material Description, Classification and Remarks | Sample No. | Standard Penetration Test | | | Comments | % Rec | RQD |
| | | | | From To | Blows | N | | | |
| 25 | | red brown micaceous SILT (ML) | 5 | 23.5-25 | 7-12-10 | 22 | | | |
| 26 | | | | | | | | | |
| 27 | | | | | | | | | |
| 28 | | | | | | | | | |
| 29 | | | | | | | | | |
| 30 | | red brown micaceous SILT (ML) | 6 | 28.5-30 | 8-10-12 | 22 | | | |
| 31 | | | | | | | | | |
| 32 | | | | | | | | | |
| 33 | | | | | | | | | |
| 34 | | | | | | | | | |
| 35 | | red brown micaceous SILT (ML) | 7 | 33.5-35 | 6-8-9 | 17 | | | |
| 36 | | | | | | | | | |
| 37 | | | | | | | | | |
| 38 | | | | | | | | | |
| 39 | | | | | | | | | |
| 40 | | red brown micaceous SILT (ML) | 8 | 38.5-40 | 6-9-13 | 22 | | | |
| 41 | | | | | | | | | |
| 42 | | | | | | | | | |
| 43 | | | | | | | | | |
| 44 | | | | | | | | | |
| 45 | | red brown micaceous SILT (ML) | 9 | 43.5-45 | 7-9-12 | 21 | | | |
| 46 | | | | | | | | | |
| 47 | | | | | | | UD 46-47.5 short push due to hard material | | |
| 48 | | | | | | | | | |
| 49 | | | | | | | | | |
| 50 | | red brown micaceous SILT (ML) | 10 | 48.5-50 | 7-9-10 | 19 | | | |
| 51 | | | | | | | | | |
| 52 | | | | | | | UD 51-53 short push due to hard materia | | |
| 53 | | | | | | | | | |
| 54 | | | | | | | | | |
| 55 | | red brown micaceous SILT (ML) | 11 | 53.5-55 | 5-7-12 | 19 | | | |
| 56 | | | | | | | | | |

Form GS9901 7-26-2004

**DRILLING LOG**
GEOLOGICAL SERVICES

Hole No. D-1

Sheet 3 of 4

| SITE | | Plant Wansley Separation Dyke | | | TOTAL DEPTH | | 106 | | SURF.ELEV. | | 806 | |
|-------|-------|--|------------|---------------------------|-------------|----|----------|-------|------------|--|-----|--|
| Depth | Elev. | Material Description, Classification and Remarks | Sample No. | Standard Penetration Test | | | Comments | % Rec | RQD | | | |
| | | | | From To | Blows | N | | | | | | |
| 57 | | multi colored sandy SILT (ML) | 12 | 58.5-60 | 5-10-16 | 26 | | | | | | |
| 58 | | | | | | | | | | | | |
| 59 | | | | | | | | | | | | |
| 60 | | | | | | | | | | | | |
| 61 | | brown gray micaceous SILT (ML) | 13 | 63.5-65 | 7-16-14 | 30 | | | | | | |
| 62 | | | | | | | | | | | | |
| 63 | | | | | | | | | | | | |
| 64 | | | | | | | | | | | | |
| 65 | | brown gray micaceous SILT (ML) | 14 | 68.5-70 | 7-14-16 | 30 | | | | | | |
| 66 | | | | | | | | | | | | |
| 67 | | | | | | | | | | | | |
| 68 | | | | | | | | | | | | |
| 69 | | brown gray micaceous SILT (ML) | 15 | 73.5-75 | 7-12-15 | 27 | | | | | | |
| 70 | | | | | | | | | | | | |
| 71 | | | | | | | | | | | | |
| 72 | | | | | | | | | | | | |
| 73 | | tan fine sandy SILT (ML) | 16 | 78.5-80 | 6-12-17 | 29 | | | | | | |
| 74 | | | | | | | | | | | | |
| 75 | | | | | | | | | | | | |
| 76 | | | | | | | | | | | | |
| 77 | | brown micaceous SILT (ML) | 17 | 83.5-85 | 7-16-13 | 29 | | | | | | |
| 78 | | | | | | | | | | | | |
| 79 | | | | | | | | | | | | |
| 80 | | | | | | | | | | | | |
| 81 | | | | | | | | | | | | |
| 82 | | | | | | | | | | | | |
| 83 | | | | | | | | | | | | |
| 84 | | | | | | | | | | | | |
| 85 | | | | | | | | | | | | |
| 86 | | | | | | | | | | | | |
| 87 | | | | | | | | | | | | |
| 88 | | | | | | | | | | | | |

Form GS9901 7-26-2004



DRILLING LOG GEOLOGICAL SERVICES

Hole No. D-1
Sheet 4 of 4

| SITE | | Plant Wansley Separation Dyke | | | TOTAL DEPTH | | 106 | | SURF.ELEV. | | 806 | |
|-------|-------|--|------------|---------------------------|-------------|----|----------|-------|------------|--|-----|--|
| Depth | Elev. | Material Description, Classification and Remarks | Sample No. | Standard Penetration Test | | | Comments | % Rec | RQD | | | |
| | | | | From To | Blows | N | | | | | | |
| 89 | | pink brown micaceous SILT (ML) | 18 | 88.5-90 | 13-20-22 | 42 | | | | | | |
| 90 | | | | | | | | | | | | |
| 91 | | | | | | | | | | | | |
| 92 | | | | | | | | | | | | |
| 93 | | | | | | | | | | | | |
| 94 | | tan brown micaceous SILT (ML) | 19 | 93.5-95 | 9-13-19 | 32 | | | | | | |
| 95 | | | | | | | | | | | | |
| 96 | | | | | | | | | | | | |
| 97 | | | | | | | | | | | | |
| 98 | | | | | | | | | | | | |
| 99 | | tan brown silty CLAY (CL) | 20 | 98.5-100 | 9-12-15 | 27 | | | | | | |
| 100 | | | | | | | | | | | | |
| 101 | | | | | | | | | | | | |
| 102 | | | | | | | | | | | | |
| 103 | | | | | | | | | | | | |
| 104 | | tan orange clayey fine SAND (SC) | 21 | 103-5-105 | 12-18-23 | 41 | | | | | | |
| 105 | | | | | | | | | | | | |
| 106 | | | | | | | | | | | | |
| 107 | | | | | | | | | | | | |
| 108 | | | | | | | | | | | | |
| 109 | | Auger Refusal @ 106' | | | | | | | | | | |
| 110 | | | | | | | | | | | | |
| 111 | | | | | | | | | | | | |
| 112 | | | | | | | | | | | | |
| 113 | | | | | | | | | | | | |
| 114 | | | | | | | | | | | | |
| 115 | | | | | | | | | | | | |
| 116 | | | | | | | | | | | | |
| 117 | | | | | | | | | | | | |
| 118 | | | | | | | | | | | | |
| 119 | | | | | | | | | | | | |
| 120 | | | | | | | | | | | | |



Form GS9901 7-26-2004

Attachment C

Soil Laboratory Analyses by MACTEC Engineering and Consulting.

US EPA ARCHIVE DOCUMENT

CONSOLIDATED UNDRAINED TRIAXIAL TEST by ASTM D4767



| | | | | |
|--------------|-----------------------------|------------|------------|-------|
| Symbol | ⊙ | △ | □ | |
| Sample No. | UD | UD | UD | |
| Test No. | 10353.1 | 10353.2 | 10353.3 | |
| Depth | 21-23.3 ft | 21-23.3 ft | 21-23.3 ft | |
| Initial | Diameter, in | 2.865 | 2.872 | 2.873 |
| | Height, in | 5.57 | 5.973 | 5.572 |
| | Water Content, % | 19.2 | 19.7 | 20.4 |
| Before Shear | Dry Density, pcf | 104.7 | 101.1 | 101.1 |
| | Saturation, % | 87.8 | 82.2 | 84.8 |
| | Void Ratio | 0.58 | 0.636 | 0.636 |
| | Water Content, % | 21.8 | 23.5 | 23.1 |
| | Dry Density, pcf | 104.8 | 102. | 102.6 |
| | Saturation*, % | 100.0 | 100.0 | 100.0 |
| | Void Ratio | 0.578 | 0.622 | 0.613 |
| Before Shear | Back Press., psi | 120. | 110. | 110. |
| | Ver. Eff. Cons. Stress, psi | 5.252 | 10.5 | 17.49 |
| | Shear Strength, psi | 18.14 | 27.35 | 39.71 |
| Before Shear | Strain at Failure, % | 17 | 16.5 | 16.4 |
| | Strain Rate, %/min | 0.05 | 0.05 | 0.05 |
| | B-Value | 0.96 | 0.93 | 0.95 |
| Before Shear | Estimated Specific Gravity | 2.65 | 2.65 | 2.65 |
| | Liquid Limit | --- | --- | --- |
| | Plastic Limit | --- | --- | --- |




| | | |
|------------------------|---------------------------------|--|
| MACTEC | Project: Plant Wansley Ash Pond | |
| | Location: D-1 | |
| | Project No.: 6152100244 | |
| | Boring No.: D-1 | |
| | Sample Type: Undisturbed | |
| | Description: Brown Silty Sand | |
| Remarks: ASTM D4767-04 | | |

Phase calculations based on start and end of test.


* Saturation is set to 100% for phase calculations.

Confidential Business Information



CONSOLIDATED UNDRAINED TRIAXIAL TEST by ASTM D4767





| | Sample No. | Test No. | Depth | Tested By | Test Date | Checked By | Check Date | Test File |
|---|------------|----------|------------|-----------|-----------|------------|------------|-------------------|
| ○ | UD | 10353.1 | 21-23.3 ft | JW | 7/26/10 | | | 10353.1_2581.dat |
| △ | UD | 10353.2 | 21-23.3 ft | JW | 7/26/10 | | | 10353.2a_2582.dat |
| □ | UD | 10353.3 | 21-23.3 ft | JW | 7/26/10 | | | 10353.3a_2583.dat |

| | | | |
|---|---------------------------------|--------------------------|-------------------------|
|  | | | |
| | Project: Plant Wansley Ash Pond | Location: D-1 | Project No.: 6152100244 |
| | Boring No.: D-1 | Sample Type: Undisturbed | |
| | Description: Brown Silty Sand | | |
| | Remarks: ASTM D4767-04 | | |

CONSOLIDATED UNDRAINED TRIAXIAL TEST by ASTM D4767






| | | | | |
|--------------|-----------------------------|------------|------------|-------|
| Symbol | ○ | Δ | □ | |
| Sample No. | UD | UD | UD | |
| Test No. | 10353.1 | 10353.2 | 10353.3 | |
| Depth | 21-23.3 ft | 21-23.3 ft | 21-23.3 ft | |
| Initial | Diameter, in | 2.865 | 2.872 | 2.873 |
| | Height, in | 5.57 | 5.973 | 5.572 |
| | Water Content, % | 19.2 | 19.7 | 20.4 |
| | Dry Density, pcf | 104.7 | 101.1 | 101.1 |
| | Saturation, % | 87.8 | 82.2 | 84.8 |
| Before Shear | Void Ratio | 0.58 | 0.636 | 0.636 |
| | Water Content, % | 21.8 | 23.5 | 23.1 |
| | Dry Density, pcf | 104.8 | 102. | 102.6 |
| | Saturation*, % | 100.0 | 100.0 | 100.0 |
| | Void Ratio | 0.578 | 0.622 | 0.613 |
| | Back Press., psi | 120. | 110. | 110. |
| | Ver. Eff. Cons. Stress, psi | 5.252 | 10.5 | 17.49 |
| | Shear Strength, psi | 18.14 | 27.35 | 39.71 |
| | Strain at Failure, % | 17 | 16.5 | 16.4 |
| | Strain Rate, %/min | 0.05 | 0.05 | 0.05 |
| | B-Value | 0.96 | 0.93 | 0.95 |
| | Estimated Specific Gravity | 2.65 | 2.65 | 2.65 |
| | Liquid Limit | --- | --- | --- |
| | Plastic Limit | --- | --- | --- |

| | | |
|--|---------------------------------|---|
|  | Project: Plant Wansley Ash Pond |  |
| | Location: D-1 | |
| | Project No.: 6152100244 | |
| | Boring No.: D-1 | |
| | Sample Type: Undisturbed | |
| | Description: Brown Silty Sand | |
| Remarks: ASTM D4767-04 | | |


Phase calculations based on start and end of test

Confidential Business Information

CONSOLIDATED UNDRAINED TRIAXIAL TEST by ASTM D4767





| | Sample No. | Test No. | Depth | Tested By | Test Date | Checked By | Check Date | Test File |
|---|------------|----------|------------|-----------|-----------|------------|------------|-------------------|
| ⊙ | UD | 10353.1 | 21-23.3 ft | JW | 7/26/10 | | | 10353.1_2581.dat |
| △ | UD | 10353.2 | 21-23.3 ft | JW | 7/26/10 | | | 10353.2a_2582.dat |
| □ | UD | 10353.3 | 21-23.3 ft | JW | 7/26/10 | | | 10353.3a_2583.dat |

| | | | |
|---|---------------------------------|--------------------------|-------------------------|
|  | | | |
| | Project: Plant Wansley Ash Pond | Location: D-1 | Project No.: 6152100244 |
| | Boring No.: D-1 | Sample Type: Undisturbed | |
| | Description: Brown Silty Sand | | |
| | Remarks: ASTM D4767-04 | | |

Confidential Business Information

CONSOLIDATED UNDRAINED TRIAXIAL TEST by ASTM D4767



| | | | | |
|--------------|-----------------------------|----------|----------|-------|
| Symbol | ⊙ | △ | □ | |
| Sample No. | UD | UD | UD | |
| Test No. | 10352.1 | 10352.2 | 10352.3 | |
| Depth | 51-53 ft | 51-53 ft | 51-53 ft | |
| Initial | Diameter, in | 2.843 | 2.872 | 2.872 |
| | Height, in | 5.56 | 5.955 | 5.562 |
| | Water Content, % | 23.3 | 22.5 | 19.3 |
| | Dry Density, pcf | 97.62 | 99.59 | 107.4 |
| | Saturation, % | 88.9 | 90.2 | 94.8 |
| Before Shear | Void Ratio | 0.695 | 0.661 | 0.54 |
| | Water Content, % | 25.5 | 23.9 | 20.1 |
| | Dry Density, pcf | 98.7 | 101.3 | 108. |
| | Saturation*, % | 100.0 | 100.0 | 100.0 |
| | Void Ratio | 0.676 | 0.633 | 0.532 |
| | Back Press., psi | 120. | 110. | 100. |
| | Ver. Eff. Cons. Stress, psi | 14. | 27.99 | 42. |
| | Shear Strength, psi | 11.93 | 22.38 | 44.54 |
| | Strain at Failure, % | 15.9 | 15.8 | 15.5 |
| | Strain Rate, %/min | 0.05 | 0.05 | 0.05 |
| | B-Value | 0.96 | 0.92 | 0.96 |
| | Estimated Specific Gravity | 2.65 | 2.65 | 2.65 |
| | Liquid Limit | --- | --- | --- |
| | Plastic Limit | --- | --- | --- |




| | | |
|--|---------------------------------|--|
| | Project: Plant Wansley Ash Pond | |
| | Location: D-1 | |
| | Project No.: 6152100244 | |
| | Boring No.: D-1 | |
| | Sample Type: Undisturbed | |
| | Description: Brown Silty Sand | |
| | Remarks: ASTM D4767-04 | |

Phase calculations based on start and end of test


Confidential Business Information

* Saturation is set to 100% for phase calculations.

CONSOLIDATED UNDRAINED TRIAXIAL TEST by ASTM D4767





| | Sample No. | Test No. | Depth | Tested By | Test Date | Checked By | Check Date | Test File |
|---|------------|----------|----------|-----------|-----------|------------|------------|-------------------|
| ○ | UD | 10352.1 | 51-53 ft | JW | 7/23/10 | | | 10352.1a_2581.dat |
| △ | UD | 10352.2 | 51-53 ft | JW | 7/23/10 | | | 10352.2a_2582.dat |
| □ | UD | 10352.3 | 51-53 ft | JW | 7/23/10 | | | 10352.3a_2583.dat |






| | | | |
|--|---------------------------------|--------------------------|-------------------------|
|  | | | |
| | Project: Plant Wansley Ash Pond | Location: D-1 | Project No.: 6152100244 |
| | Boring No.: D-1 | Sample Type: Undisturbed | |
| | Description: Brown Silty Sand | | |
| | Remarks: ASTM D4767-04 | | |

Confidential Business Information

CONSOLIDATED UNDRAINED TRIAXIAL TEST by ASTM D4767



| | | | | |
|-----------------------------|------------------|----------|----------|-------|
| Symbol | ⊙ | △ | □ | |
| Sample No. | UD | UD | UD | |
| Test No. | 10352.1 | 10352.2 | 10352.3 | |
| Depth | 51-53 ft | 51-53 ft | 51-53 ft | |
| Initial | Diameter, in | 2.843 | 2.872 | 2.872 |
| | Height, in | 5.56 | 5.955 | 5.562 |
| | Water Content, % | 23.3 | 22.5 | 19.3 |
| | Dry Density, pcf | 97.62 | 99.59 | 107.4 |
| | Saturation, % | 88.9 | 90.2 | 94.8 |
| | Void Ratio | 0.695 | 0.661 | 0.54 |
| Before Shear | Water Content, % | 25.5 | 23.9 | 20.1 |
| | Dry Density, pcf | 98.7 | 101.3 | 108. |
| | Saturation*, % | 100.0 | 100.0 | 100.0 |
| | Void Ratio | 0.676 | 0.633 | 0.532 |
| | Back Press., psi | 120. | 110. | 100. |
| Ver. Eff. Cons. Stress, psi | | 14. | 27.99 | 42. |
| Shear Strength, psi | | 11.93 | 22.38 | 44.54 |
| Strain at Failure, % | | 15.9 | 15.8 | 15.5 |
| Strain Rate, %/min | | 0.05 | 0.05 | 0.05 |
| B-Value | | 0.96 | 0.92 | 0.96 |
| Estimated Specific Gravity | | 2.65 | 2.65 | 2.65 |
| Liquid Limit | | --- | --- | --- |
| Plastic Limit | | --- | --- | --- |




| | | | | | |
|---|---------------------------------|---|---|---|---|
|  | Project: Plant Wansley Ash Pond |  |  |  |  |
| | Location: D-1 | | | | |
| | Project No.: 6152100244 | | | | |
| | Boring No.: D-1 | | | | |
| | Sample Type: Undisturbed | | | | |
| | Description: Brown Silty Sand | | | | |
| | Remarks: ASTM D4767-04 | | | | |

Phase calculations based on test data and test


Confidential Business Information

* Saturation is set to 100% for phase calculations.

CONSOLIDATED UNDRAINED TRIAXIAL TEST by ASTM D4767




| | Sample No. | Test No. | Depth | Tested By | Test Date | Checked By | Check Date | Test File |
|---|------------|----------|----------|-----------|-----------|------------|------------|-------------------|
| ⊙ | UD | 10352.1 | 51-53 ft | JW | 7/23/10 | | | 10352.1a_2581.dat |
| △ | UD | 10352.2 | 51-53 ft | JW | 7/23/10 | | | 10352.2a_2582.dat |
| □ | UD | 10352.3 | 51-53 ft | JW | 7/23/10 | | | 10352.3a_2583.dat |

| | | | |
|---|---------------------------------|--------------------------|-------------------------|
|  MACTEC | | | |
| | Project: Plant Wansley Ash Pond | Location: D-1 | Project No.: 6152100244 |
| | Boring No.: D-1 | Sample Type: Undisturbed | |
| | Description: Brown Silty Sand | | |
| | Remarks: ASTM D4767-04 | | |

Confidential Business Information

Particle Size Distribution ASTM D422-63 (2007)




| % COBBLES | % GRAVEL | | % SAND | | | % FINES | |
|-----------|----------|------|--------|--------|------|---------|------|
| | COARSE | FINE | COARSE | MEDIUM | FINE | SILT | CLAY |
| 0.0 | 0.0 | 3.8 | 2.0 | 6.1 | 28.7 | 59.4 | |
| | | | | | | | |
| | | | | | | | |

| SOURCE | SAMPLE # | DEPTH/ELEV. | DATE SAMPLED | USCS | MATERIAL DESCRIPTION | NM % | LL | PL |
|--------|----------|-------------|--------------|------|----------------------|------|----|----|
| D-1 | UD | 21-23.3 ft | 8/4/10 | | Brown Silty Sand | | | |
| | | | | | | | | |
| | | | | | | | | |

| | | | |
|--------------------------------|-------|--|---------------------------------|
| Client | | MACTEC ENGINEERING AND CONSULTING, INC. | ○ Tested By: EH Reviewed By: JW |
| Project Plant Wansley Ash Pond | | | |
| | | | |
| Project No. 6152-10-0244 | 10353 | | |

Particle Size Distribution ASTM D422-63 (2007)



| % COBBLES | % GRAVEL | | % SAND | | | % FINES | |
|-----------|----------|------|--------|--------|------|---------|------|
| | COARSE | FINE | COARSE | MEDIUM | FINE | SILT | CLAY |
| 0.0 | 0.0 | 2.4 | 4.4 | 9.9 | 31.0 | 52.3 | |

| SOURCE | SAMPLE # | DEPTH/ELEV. | DATE SAMPLED | USCS | MATERIAL DESCRIPTION | NM % | LL | PL |
|--------|----------|-------------|--------------|------|----------------------|------|----|----|
| D-1 | UD | 51-53 ft | 8/4/10 | | Brown Silty Sand | | | |


| | | | |
|--------------------------------|-------|--|---------------------------------|
| Client | | MACTEC ENGINEERING AND CONSULTING, INC. | ○ Tested By: EH Reviewed By: JW |
| Project Plant Wansley Ash Pond | | | |
| | | | |
| Project No. 6152-10-0244 | 10352 | | |

Attachment D

Historic Soil Laboratory Analyses by Law Engineering Testing Company

US EPA ARCHIVE DOCUMENT


SHEAR STRESS IN KIPS PER SQ. FT.



MOHR DIAGRAMS

EXCESS PORE PRESSURE IN KIPS PER SQ. FT.

STRAIN, IN/IN.



STRESS-STRAIN AND PORE PRESSURE-STRAIN CURVES

EFFECTIVE COHESION, c 0
 EFFECTIVE SHEAR ANGLE, ϕ 37.5
 TOTAL COHESION, c 0.08 KSF
 TOTAL SHEAR ANGLE, ϕ 24

SATURATED, CONSOLIDATED
 UNDRAINED TRIAXIAL SHEAR
 TEST WITH PORE PRESSURE
 MEASUREMENTS

SAMPLE NO. UD BORING NO. B-8.12
 DEPTH 14-16 JOB NO. SA-268

————— Total σ_1
 - - - - - Effective σ_1
 Effective σ_3
 Stress Path

Confidential Business Information

ENGINEERING TESTING COMPANY



| | | | |
|---|---------------|--|------------------------------|
| Project Wansley | | Calculation Number SH-WN10911-01 | |
| Objective | | Discipline Hydro Services | |
| Subject/Title Evaluate Stormwater Capacity of Ash Pond | | ____ Number | |
| Originator's Signature <i>Franklin Goff, Jr.</i> Date <i>8/1/2010</i> Last Page Number 10 | | | |
| Contents | | | |
| Topic | Page | Attachments (Computer Printouts, Technical Papers, Sketches, Correspondence, etc.) | Number of Pages |
| Purpose of Calculation/ Summary of Conclusions | 1 | | |
| Criteria | 1 | | |
| Major Equation Sources/ Derivation Methods | 1 | | |
| Assumptions | 1 | | |
| Listed References | 1 | | |
| Body of Calculations | 2-10 | | |
| Record of Revisions | | | |
| Rev. No. | Description | Originator Date | Reviewer Date |
| 0 | Initial Calcs | <i>FHG</i> <i>3/4/10</i> | <i>CRS</i> <i>3/10/10</i> |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| NOTES: | | | |

Design Calculations

| | | |
|---|-------------------------------------|------------------|
| Project Plant Wansley | Prepared By Fred L. Cox, Jr. | Date 8/1/2010 |
| Subject/Title Evaluate Stormwater capacity of Ash Pond | Reviewed By Courtenay O'Mara | Date 8/4/2010 |
| | Calculation Number SH-WN10911-01 | Sheet 1 of 10 |

1.0 Purpose of Calculation:

Determine the storm water handling capacity of the Wansley Ash Pond

2.0 Summary of Conclusions:

The Wansley Ash Pond can handle a 24 hour rainfall runoff of: 1) 16.9 inches of rainfall runoff, which is 2.13 times the 100 year storm, at the level of the emergency spillway crest, and 2) 23.5 inches of rain, which is 2.96 times the 100 year storm, at a level one foot below the crest of the dike. The probability of occurrence of these storms is exceedingly low. Based on these data and Georgia Power's tolerance for risk of this type of storm occurring, it is concluded that the capacity of the ash pond is far more than adequate.

3.0 Criteria:

See Section 7.0

4.0 References:

1. Georgia EPD Safe Dam Program Rules for Dam Safety
2. Dwg. 10-209-B1008, Plant Wansley Ash Pond Area-Volume Curve
3. Dwg. 10-209-E1C11102, Short Term Gypsum Disposal, General Arrangement and Site Plan
4. Georgia Stormwater Management Manual, Rainfall Table for Peachtree City
5. 4th Quarter - 2009 report on Dam Safety Surveillance for Plant Wansley
6. 2002 NPDES Co-Treatment Calculations

5.0 Assumptions:

See Section 7.0

6.0 Major Equation Sources/Derivation of Methods:

See Section 7.0

7.0 Body of Calculations

Ash Pond Data:

The Plant Wansley Ash Pond is not a Category I structure according to the Georgia EPD Safe Dam Program Rules for Dam Safety. Because of this; it is not required to pass the PMF, or some fraction of the PMF. A lesser storm event is acceptable.

Design Calculations

| | | |
|---|---|------------------|
| Project Plant Wansley | Prepared By Fred L. Cox, Jr. | Date 8/1/2010 |
| Subject/Title Evaluate Stormwater capacity of Ash Pond | Reviewed By Courtenay O'Mara <i>CO</i> | Date 8/4/2010 |
| | Calculation Number SH-WN10911-01 | Sheet 2 of 10 |

Elevation – Volume – Area Data

(Drawing. 10-209-B10008) (See Figure 1, page 5)

| Elevation | Volume Ac-Ft | Area Ac |
|-----------|-----------------|------------|
| 790 | 12300 | 312 |
| 795 | 14000 | 333 |
| 800 | 15700 | 354 |
| 805 | 17400 | 375 |

Top of Dike: 805

Emergency Spillway Crest: 802.6

Pond Operating Level: See attached of 2000-2009 levels from 2009 4th Qtr Inspection Report. The Ash Pond level generally fluctuates between 795 and 799. (See Figure 2, page 6)

Drainage Area: 711 Acres (2002 Co-Treatment calculations)

Rainfall Data: From the Georgia Stormwater Management Manual rainfall tables, the closest city is Peachtree City (See Figure 3, page 7)

| Return Period Yrs | 24 Hour Intensity Inches/hour | 24 Hour Rainfall Inches |
|----------------------|----------------------------------|----------------------------|
| 2 | .17 | 4.08 |
| 5 | .21 | 5.04 |
| 10 | .24 | 5.76 |
| 25 | .28 | 6.72 |
| 50 | .30 | 7.20 |
| 100 | .33 | 7.92 |

Design Calculations

| | | |
|---|---|------------------|
| Project Plant Wansley | Prepared By Fred L. Cox, Jr. | Date 8/1/2010 |
| Subject/Title Evaluate Stormwater capacity of Ash Pond | Reviewed By Courtenay O'Mara <i>CO</i> | Date 8/4/2010 |
| | Calculation Number SH-WN10911-01 | Sheet 3 of 10 |

Gypsum Stacking Area in Ash Pond:

In 2007 a 62 acre gypsum stacking area was established in the Ash Pond. The gypsum is stacked above the pond surface. The volume used by this stack must be deducted from the available storage volume in the pond. See Figure 4, page 8, for a drawing of the stack and Figure 5, page 9, for an aerial photo of the ash pond and gypsum stack.

Analysis

Determine how man inches of runoff can be stored up to the crest of the emergency spillway.

Assume a conservatively high starting ash pond level of 799 (see Figure 2, page 6, for a plot of ash pond levels from 2000 – 2009).

Original volume from 799 to 802.6 (crest of emergency spillway) = 1224 ac-ft

Adjustment for gypsum stack = $1224 - (3.6\text{ft} \times 62 \text{ acres}) = 1000.8 \text{ ac-ft}$

Assuming 100 % runoff determine how many inches of rain can be stored

$1000.8 \text{ ac-ft of storage} / 711 \text{ ac of drainage} = 1.408 \text{ ft of rain runoff storage available} = 16.9 \text{ inches of rain storage available}$

16.9 inches of rain is 2.13 times the 100 year 24 hour rain (7.92 inches)

Determine how man inches of runoff can be stored up one foot of the top of the dike

Original volume from 799 to 804 (one foot below top dike) = 1700 ac-ft

Adjustment for gypsum stack = $1700 - (5\text{ft} \times 62 \text{ ac}) = 1390 \text{ ac-ft}$


Assuming 100 % runoff & neglecting emergency spillway discharge

$1390 \text{ ac-ft of storage} / 711 \text{ ac of drainage} = 1.955 \text{ ft of rain runoff storage available} = 23.5 \text{ inches of rain storage available}$

23.5 inches of rain is 2.96 times the 100 year 24 hour rain (7.92 inches)

This analysis conservatively neglects spillway discharge during the storm

Design Calculations

| | | |
|---|---|------------------|
| Project Plant Wansley | Prepared By Fred L. Cox, Jr. | Date 8/1/2010 |
| Subject/Title Evaluate Stormwater capacity of Ash Pond | Reviewed By Courtenay O'Mara  | Date 8/4/2010 |
| | Calculation Number SH-WN10911-01 | Sheet 4 of 10 |

Summary

The Wansley Ash Pond can handle a 24 hour rainfall runoff of: 1) 16.9 inches of rainfall runoff, which is 2.13 times the 100 year storm, at the level of the emergency spillway crest, and 2) 23.5 inches of rain, which is 2.96 times the 100 year storm, at a level one foot below the crest of the dike.


Figure 6 (see page 10) is a semilog plot of the 2 to 100 year 24 hour rainfall with a line fit extended out to 200 years. It is obvious from this plot that the 16.9 inch runoff capacity up to the crest of the emergency spillway, and the 23.5 inch runoff capacity up to one foot below the crest of the dike, have very low probabilities of occurrence (probability of occurrence in a given year = the inverse of the return period).

The probability of occurrence of these storms is exceedingly low. Based on these data and Georgia Power's tolerance for risk of this type of storm occurring, it is concluded that the capacity of the ash pond is far more than adequate.

Design Calculations

| | | |
|---|---|------------------|
| Project Plant Wansley | Prepared By Fred L. Cox, Jr. | Date 8/1/2010 |
| Subject/Title Evaluate Stormwater capacity of Ash Pond | Reviewed By Courtenay O'Mara <i>CO</i> | Date 8/4/2010 |
| | Calculation Number SH-WN10911-01 | Sheet 5 of 10 |

Figure 1:




| | | | |
|---|--------------------|--|----------|
| GEORGIA POWER CO., ATLANTA, GA. GENERAL ENGINEERING DEPARTMENT | | GEORGIA POWER COMPANY PLANT WANSLEY ASH POND AREA-VOLUME CURVE | |
| DRAWN BY <i>JLS</i> | DATE <i>1-5-73</i> | REVISIONS | NUMBER |
| TRACED BY | SCALE | | |
| APPROVED | | LOCATION | SHEET NO |
| | | 10-209 | B1000B |

Design Calculations

| | | |
|---|-------------------------------------|------------------|
| Project Plant Wansley | Prepared By Fred L. Cox, Jr. | Date 8/1/2010 |
| Subject/Title Evaluate Stormwater capacity of Ash Pond | Reviewed By Courtenay O'Mara | Date 8/4/2010 |
| | Calculation Number SH-WN10911-01 | Sheet 6 of 10 |

Figure 2:

Wansley Separation Dike Pz's BB and DD



Design Calculations

| | | |
|---|-------------------------------------|------------------|
| Project Plant Wansley | Prepared By Fred L. Cox, Jr. | Date 8/1/2010 |
| Subject/Title Evaluate Stormwater capacity of Ash Pond | Reviewed By Courtenay O'Mara | Date 8/4/2010 |
| | Calculation Number SH-WN10911-01 | Sheet 7 of 10 |


Figure 3:

| Table A-10 Peachtree City | | | | | | | | |
|------------------------------|---------|--------------------|--------|--------|--------|--------|--------|--------|
| | | Return Period | | | | | | |
| | | 1 | 2 | 5 | 10 | 25 | 50 | 100 |
| n | | 0.7669 | 0.8184 | 0.7769 | 0.7471 | 0.7191 | 0.7243 | 0.7107 |
| a | | 38.81 | 57.93 | 61.46 | 61.89 | 64.80 | 74.70 | 77.93 |
| b | | 8 | 11 | 12 | 12 | 12 | 13 | 13 |
| Hours | Minutes | Rainfall Intensity | | | | | | |
| 0.08 | 5 | 5.43 | 5.99 | 6.80 | 7.45 | 8.45 | 9.21 | 9.99 |
| | 6 | 5.13 | 5.70 | 6.51 | 7.14 | 8.11 | 8.85 | 9.61 |
| | 7 | 4.86 | 5.44 | 6.24 | 6.86 | 7.80 | 8.53 | 9.27 |
| | 8 | 4.63 | 5.20 | 6.00 | 6.60 | 7.52 | 8.23 | 8.95 |
| | 9 | 4.42 | 4.99 | 5.77 | 6.36 | 7.26 | 7.96 | 8.66 |
| | 10 | 4.23 | 4.79 | 5.57 | 6.15 | 7.02 | 7.71 | 8.39 |
| | 11 | 4.06 | 4.62 | 5.38 | 5.95 | 6.80 | 7.48 | 8.14 |
| | 12 | 3.90 | 4.45 | 5.20 | 5.76 | 6.59 | 7.26 | 7.91 |
| | 13 | 3.76 | 4.30 | 5.04 | 5.59 | 6.40 | 7.05 | 7.69 |
| 0.25 | 14 | 3.63 | 4.16 | 4.89 | 5.43 | 6.22 | 6.86 | 7.49 |
| | 15 | 3.50 | 4.03 | 4.75 | 5.28 | 6.06 | 6.69 | 7.30 |
| | 16 | 3.39 | 3.90 | 4.62 | 5.13 | 5.90 | 6.52 | 7.12 |
| | 17 | 3.29 | 3.79 | 4.49 | 5.00 | 5.75 | 6.36 | 6.95 |
| | 18 | 3.19 | 3.68 | 4.38 | 4.88 | 5.61 | 6.21 | 6.79 |
| | 19 | 3.10 | 3.58 | 4.27 | 4.76 | 5.48 | 6.07 | 6.64 |
| | 20 | 3.01 | 3.49 | 4.16 | 4.65 | 5.36 | 5.94 | 6.49 |
| | 21 | 2.93 | 3.40 | 4.06 | 4.54 | 5.24 | 5.81 | 6.36 |
| | 22 | 2.86 | 3.31 | 3.97 | 4.44 | 5.13 | 5.69 | 6.23 |
| | 23 | 2.79 | 3.23 | 3.88 | 4.35 | 5.03 | 5.57 | 6.10 |
| | 24 | 2.72 | 3.16 | 3.80 | 4.25 | 4.92 | 5.46 | 5.99 |
| | 25 | 2.66 | 3.08 | 3.72 | 4.17 | 4.83 | 5.36 | 5.87 |
| | 26 | 2.60 | 3.02 | 3.64 | 4.09 | 4.74 | 5.26 | 5.77 |
| | 27 | 2.54 | 2.95 | 3.57 | 4.01 | 4.65 | 5.16 | 5.66 |
| | 28 | 2.49 | 2.89 | 3.50 | 3.93 | 4.57 | 5.07 | 5.57 |
| 0.50 | 29 | 2.43 | 2.83 | 3.43 | 3.86 | 4.49 | 4.98 | 5.47 |
| | 30 | 2.38 | 2.77 | 3.37 | 3.79 | 4.41 | 4.90 | 5.38 |
| | 31 | 2.34 | 2.72 | 3.31 | 3.73 | 4.33 | 4.82 | 5.29 |
| | 32 | 2.29 | 2.67 | 3.25 | 3.66 | 4.26 | 4.74 | 5.21 |
| | 33 | 2.25 | 2.62 | 3.19 | 3.60 | 4.19 | 4.67 | 5.13 |
| | 34 | 2.21 | 2.57 | 3.14 | 3.54 | 4.13 | 4.59 | 5.05 |
| | 35 | 2.17 | 2.52 | 3.09 | 3.49 | 4.07 | 4.52 | 4.98 |
| | 36 | 2.13 | 2.48 | 3.04 | 3.43 | 4.00 | 4.46 | 4.90 |
| | 37 | 2.09 | 2.44 | 2.99 | 3.38 | 3.95 | 4.39 | 4.83 |
| | 38 | 2.06 | 2.40 | 2.94 | 3.33 | 3.89 | 4.33 | 4.77 |
| | 39 | 2.03 | 2.36 | 2.90 | 3.28 | 3.83 | 4.27 | 4.70 |
| | 40 | 1.99 | 2.32 | 2.85 | 3.23 | 3.78 | 4.21 | 4.64 |
| | 41 | 1.96 | 2.28 | 2.81 | 3.19 | 3.73 | 4.15 | 4.58 |
| | 42 | 1.93 | 2.25 | 2.77 | 3.14 | 3.68 | 4.10 | 4.52 |
| | 43 | 1.90 | 2.21 | 2.73 | 3.10 | 3.63 | 4.05 | 4.46 |
| 0.75 | 44 | 1.87 | 2.18 | 2.69 | 3.06 | 3.58 | 4.00 | 4.40 |
| | 45 | 1.85 | 2.15 | 2.66 | 3.02 | 3.54 | 3.95 | 4.35 |
| | 46 | 1.82 | 2.12 | 2.62 | 2.98 | 3.49 | 3.90 | 4.30 |
| | 47 | 1.80 | 2.09 | 2.59 | 2.94 | 3.45 | 3.85 | 4.25 |
| | 48 | 1.77 | 2.06 | 2.55 | 2.90 | 3.41 | 3.80 | 4.20 |
| | 49 | 1.75 | 2.03 | 2.52 | 2.87 | 3.37 | 3.76 | 4.15 |
| | 50 | 1.72 | 2.00 | 2.49 | 2.83 | 3.33 | 3.72 | 4.10 |
| | 51 | 1.70 | 1.98 | 2.46 | 2.80 | 3.29 | 3.67 | 4.06 |
| | 52 | 1.68 | 1.95 | 2.43 | 2.77 | 3.26 | 3.63 | 4.01 |
| | 53 | 1.66 | 1.93 | 2.40 | 2.74 | 3.22 | 3.59 | 3.97 |
| | 54 | 1.64 | 1.90 | 2.37 | 2.71 | 3.18 | 3.55 | 3.93 |
| | 55 | 1.62 | 1.88 | 2.34 | 2.68 | 3.15 | 3.52 | 3.88 |
| | 56 | 1.60 | 1.86 | 2.32 | 2.65 | 3.12 | 3.48 | 3.84 |
| | 57 | 1.58 | 1.83 | 2.29 | 2.62 | 3.08 | 3.44 | 3.81 |
| | 58 | 1.56 | 1.81 | 2.27 | 2.59 | 3.05 | 3.41 | 3.77 |
| | 59 | 1.54 | 1.79 | 2.24 | 2.56 | 3.02 | 3.37 | 3.73 |
| 1 | 60 | 1.53 | 1.77 | 2.22 | 2.54 | 2.99 | 3.34 | 3.69 |
| 2 | 120 | 0.97 | 1.19 | 1.44 | 1.60 | 1.85 | 2.07 | 2.24 |
| 3 | 180 | 0.69 | 0.82 | 1.02 | 1.16 | 1.33 | 1.47 | 1.62 |
| 6 | 360 | 0.40 | 0.49 | 0.61 | 0.70 | 0.81 | 0.91 | 0.98 |
| 12 | 720 | 0.24 | 0.29 | 0.36 | 0.42 | 0.48 | 0.53 | 0.58 |
| 24 | 1440 | 0.14 | 0.17 | 0.21 | 0.24 | 0.28 | 0.30 | 0.33 |

SOUTHERN COMPANY
Energy to Serve Your World™

| | | |
|---|-------------------------------------|------------------|
| Project Plant Wansley | Prepared By Fred L. Cox, Jr. | Date 8/1/2010 |
| Subject/Title Evaluate Stormwater capacity of Ash Pond | Reviewed By Courtenay O'Mara | Date 8/4/2010 |
| | Calculation Number SH-WN10911-01 | Sheet 8 of 10 |


Figure 4:



Design Calculations

| | | |
|---|---|------------------|
| Project Plant Wansley | Prepared By Fred L. Cox, Jr. | Date 8/1/2010 |
| Subject/Title Evaluate Stormwater capacity of Ash Pond | Reviewed By Courtenay O'Mara <i>CO</i> | Date 8/4/2010 |
| | Calculation Number SH-WN10911-01 | Sheet 9 of 10 |

Figure 5:




Design Calculations

| | | |
|---|-------------------------------------|-------------------|
| Project Plant Wansley | Prepared By Fred L. Cox, Jr. | Date 8/1/2010 |
| Subject/Title Evaluate Stormwater capacity of Ash Pond | Reviewed By Courtenay O'Mara | Date 8/4/2010 |
| | Calculation Number SH-WN10911-01 | Sheet 10 of 10 |

Figure 6:

Plant Wansley



Site Name: Georgia Power - Wonsley Date: 30 JUNE 2010Unit Name: ASH Pond

Operator's Name:

Unit I.D.:

Hazard Potential Classification: High Significant LowInspector's Name: FREDERICK SHMURAK & JUSTIN STORY - DEWBERRY

Check the appropriate box below. Provide comments when appropriate. If not applicable or not available, record "N/A". Any unusual conditions or construction practices that should be noted in the comments section. For large diked embankments, separate checklists may be used for different embankment areas. If separate forms are used, identify approximate area that the form applies to in comments.

| Yes | | No | | Yes | | No | |
|--|---|-------------------------------------|--|---|-------------------------------------|-------------------------------------|--|
| 1. Frequency of Company's Dam Inspections? | <input checked="" type="checkbox"/> | <input type="checkbox"/> | | 18. Sloughing or bulging on slopes? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | |
| 2. Pool elevation (operator records)? | <u>796.5</u> | <input type="checkbox"/> | | 19. Major erosion or slope deterioration? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | |
| 3. Decant inlet elevation (operator records)? | <u>800.29</u> | <input type="checkbox"/> | | 20. Decant Pipes: | | | |
| 4. Open channel spillway elevation (operator records)? | <u>802.57</u> | <input type="checkbox"/> | | Is water entering inlet, but not exiting outlet? | <input type="checkbox"/> | <u>N/A</u> | |
| 5. Lowest dam crest elevation (operator records)? | <u>805.0</u> | <input type="checkbox"/> | | Is water exiting outlet, but not entering inlet? | <input type="checkbox"/> | <u>N/A</u> | |
| 6. If instrumentation is present, are readings recorded (operator records)? | <input checked="" type="checkbox"/> <u>NORMAL</u> | <input type="checkbox"/> | | Is water exiting outlet flowing clear? | <input type="checkbox"/> | <u>N/A</u> | |
| 7. Is the embankment currently under construction? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | | 21. Seepage (specify location, if seepage carries fines, and approximate seepage rate below): | | | |
| 8. Foundation preparation (remove vegetation, stumps, topsoil in area where embankment fill will be placed)? | <input type="checkbox"/> | <u>N/A</u> | | From underdrain? | <input type="checkbox"/> | <u>N/A</u> | |
| 9. Trees growing on embankment? (If so, indicate largest diameter below) | <input type="checkbox"/> | <input checked="" type="checkbox"/> | | At isolated points on embankment slopes? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | |
| 10. Cracks or scarps on crest? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | | At natural hillside in the embankment area? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | |
| 11. Is there significant settlement along the crest? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | | Over widespread areas? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | |
| 12. Are decant trashracks clear and in place? | <input type="checkbox"/> | <u>N/A</u> | | From downstream foundation area? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | |
| 13. Depressions or sinkholes in tailings surface or whirlpool in the pool area? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | | "Boils" beneath stream or ponded water? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | |
| 14. Clogged spillways, groin or diversion ditches? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | | Around the outside of the decant pipe? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | |
| 15. Are spillway or ditch linings deteriorated? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | | 22. Surface movements in valley bottom or on hillside? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | |
| 16. Are outlets of decant or underdrains blocked? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | | 23. Water against downstream toe? | <input checked="" type="checkbox"/> | <input type="checkbox"/> | |
| 17. Cracks or scarps on slopes? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | | 24. Were Photos taken during the dam inspection? | <input checked="" type="checkbox"/> | <input type="checkbox"/> | |

Major adverse changes in these items could cause instability and should be reported for further evaluation. Adverse conditions noted in these items should normally be described (extent, location, volume, etc.) in the space below and on the back of this sheet.

Inspection Issue #

Comments

1. Daily, Weekly, Quarterly, and Annual2. N.P. WSE 795.015. Monitor U/S Undermining Potential & Cracks Along Concrete Channel (NOT A Safety Issue AT THIS TIME)20. No discharge from Pond (None observed historically)23. Cooling Water Pond & Storm Water Management Pond located Along D/S TOE of E & W dike respectively



Coal Combustion Waste (CCW)
Impoundment Inspection

Impoundment NPDES Permit # GA0026778

INSPECTOR Dewberry

Date 30 JUN 2010

Impoundment Name Ash Pond

Impoundment Company Georgia Power

EPA Region IV

State Agency (Field Office) Address _____

Name of Impoundment Ash Pond

(Report each impoundment on a separate form under the same Impoundment NPDES Permit number)

New _____ Update ☒

Is impoundment currently under construction?

Yes

No

Is water or ccw currently being pumped into the impoundment?

☒

☒

IMPOUNDMENT FUNCTION: CCW settling & storage

Nearest Downstream Town : Name Centralhatchee
Distance from the impoundment 3.6 miles SW (NOT DIRECTLY D/S)

Impoundment

Location: Longitude N 85 Degrees 02 Minutes 46 Seconds
Latitude W 33 Degrees 25 Minutes 09 Seconds
State GA County HEARD / CARROLLTON

Does a state agency regulate this impoundment? YES ☒ NO _____

If So Which State Agency? GA Safe Dams Program -
category 2 dam

HAZARD POTENTIAL (In the event the impoundment should fail, the following would occur):

_____ **LESS THAN LOW HAZARD POTENTIAL:** Failure or misoperation of the dam results in no probable loss of human life or economic or environmental losses.

✓ _____ **LOW HAZARD POTENTIAL:** Dams assigned the low hazard potential classification are those where failure or misoperation results in no probable loss of human life and low economic and/or environmental losses. Losses are principally limited to the owner's property.


_____ **SIGNIFICANT HAZARD POTENTIAL:** Dams assigned the significant hazard potential classification are those dams where failure or misoperation results in no probable loss of human life but can cause economic loss, environmental damage, disruption of lifeline facilities, or can impact other concerns. Significant hazard potential classification dams are often located in predominantly rural or agricultural areas but could be located in areas with population and significant infrastructure.

_____ **HIGH HAZARD POTENTIAL:** Dams assigned the high hazard potential classification are those where failure or misoperation will probably cause loss of human life.

DESCRIBE REASONING FOR HAZARD RATING CHOSEN:

Georgia Safe Dams Program classified
embankment system as Low Hazard
Potential.

CONFIGURATION:



☒ Cross-Valley
☐ Side-Hill
☐ Diked
☐ Incised (form completion optional)
☐ Combination Incised/Diked

Embankment Height 110 feet Embankment Material SOIL
 Pool Area 343 acres Liner NONE
 Current Freeboard 8.5 feet Liner Permeability N/A


TYPE OF OUTLET (Mark all that apply)

Open Channel Spillway


- ☒ Trapezoidal *Emergency Spillway*
☐ Triangular
☐ Rectangular
☐ Irregular

____ depth
 ____ bottom (or average) width
 ____ top width


TRAPEZOIDAL




TRIANGULAR



RECTANGULAR



IRREGULAR




Outlet

____ inside diameter

Material

- ____ corrugated metal
 ____ welded steel
 ____ concrete
 ____ plastic (hdpe, pvc, etc.)
 ____ other (specify) _____



Is water flowing through the outlet? YES _____ NO _____

No Outlet

☒ **Other Type of Outlet** (specify) BROAD CREST CONCRETE WEIR
Primary Spillway and RCP CONDUIT.

The Impoundment was Designed By SOUTHERN COMPANY SERVICES

Has there ever been a failure at this site? YES _____ NO ☒

If So When?

[illegible]

Has there ever been significant seepages at this site? YES _____ NO ☒

If So When? _____

IF So Please Describe: _____


This image shows a single sheet of white paper with horizontal ruling lines. The lines are evenly spaced and run across the width of the page. There are no margins, text, or other markings on the paper.

YES _____ NO ✓

.....

18. The following information was obtained from the records of the Department of Health and Human Services, Office of Inspector General, Washington, D.C., regarding the activities of the American Medical Association's Committee on Professional Ethics during the period from January 1, 1970, to December 31, 1970:

This image shows a single sheet of white paper with horizontal ruling lines. The lines are evenly spaced and run across the width of the page. There are no margins, text, or other markings on the paper.








Photo 1: Upstream Slope adjacent to Gypsum Cells



Photo 2: Ash Pond inlet



Photo 3: Separation Dike Crest facing North



Photo 4: Close up where seeding occurred



Photo 5: Ash Pond Inlet



Photo 6: Separation Dike Crest downstream slope



Photo 7: Separation Dike downstream slope



Photo 8: Separation Dike upstream slope



Photo 9: Separation Dike upstream slope



Photo 10: Separation Dike downstream slope



Photo 11: Separation Dike upstream slope



Photo 12: Concrete ash piping support (not in use)



Photo 13: Separation Dike upstream slope



Photo 13B: Separation Dike upstream slope



Photo 14: Separation Dike downstream slope



Photo 15: Separation Dike left abutment upstream side



Photo 16: Separation Dike left abutment upstream side



Photo 17: Separation Dike left abutment downstream side



Photo 18: Erosion maintenance



Photo 19: Influent piping



Photo 20: Piezometer DD



Photo 21: Piezometer DD



Photo 22: Separation Dike downstream slope



Photo 23: Close up of downstream slope



Photo 24: Downstream slope erosion repair



Photo 25: Reservoir pond levels



Photo 26: Influent piping facing Gypsum Cells



Photo 27: Right abutment downstream slope



Photo 28: Separation Dike downstream slope



Photo 29: Right abutment facing reservoir



Photo 30: Influent piping



Photo 31: Piezometer BB



Photo 32: Gypsum Cell upstream slope



Photo 33: Gypsum Cell upstream slope



Photo 34: Gypsum Cell downstream slope facing Ash Pond



Photo 35: Gypsum Cell downstream slope facing Ash Pond



Photo 36: Gypsum Cell Discharge



Photo 37: Gypsum Cell upstream slope



Photo 38: Gypsum Cell upstream slope



Photo 39: Gypsum Cell upstream slope



Photo 40: Gypsum Cell downstream slope



Photo 41: Gypsum Cell downstream slope



Photo 42: Western Dike downstream slope



Photo 43: Western Dike downstream slope



Photo 44: Western Dike downstream slope



Photo 45: Western Dike overflow spillway



Photo 46: Stormwater channel



Photo 47: Stormwater channel discharge



Photo 48: Western Dike upstream slope



Photo 49: Western Dike upstream slope



Photo 50: Area adjacent to Western Dike



Photo 51: Area adjacent to Western Dike



Photo 52: Stormwater Channel



Photo 53: Western Dike upstream slope



Photo 54: Potential undermining at overflow



Photo 55: Potential undermining at overflow



Photo 56: Cracking along overflow channel



Photo 57: Western Dike downstream slope



Photo 58: Western Dike downstream slope



Photo 59: Stormwater Pond Dam



Photo 60: Stormwater pond



Photo 61: Western Dike outlet at Stormwater pond



Photo 62: Outlet at Stormwater pond



Photo 63: Western Dike outlet



Photo 64: Western Dike upstream slope and outlet