

### Proposed Modification to Design Basis: Groundwater Discharge Permit No. GW1810162

David List, P.E. Golder Associates Inc.



# Infiltration System: Existing Permitted Design versus Proposed Modified Design

### **Existing Permitted Designed Treated Water Infiltration System**



#### Proposed Modified Designed Treated Water Infiltration System











# Infiltration System: Existing Permitted Design versus Proposed Modified Design

#### **Existing Permitted Designed Treated Water Infiltration System**



#### **Proposed Modified Designed Treated Water Infiltration System**









DOCUMENT

п

ARCHIVI

(1)

10

ບ

# Infiltration System: Existing Permitted Design versus Proposed Modified Design

#### **Existing Permitted Designed Treated Water Infiltration**



#### **Proposed Modified Designed Treated Water Infiltration System**









DOCUMENT

ARCHIVE

EPA

S

# Infiltration System: Existing Permitted Design versus Proposed Modified Design



March 25, 2010









In summary, the proposed modifications include:

□Water is delivered to the infiltration system in a slightly different manner namely eliminating the distribution chamber and replacing it with individual valves and flow meters.

The diameter of the laterals has been increased from 1.5 inch PVC to 2 inch HDPE.

The length of the lateral distribution pipe has been decreased.

The cover system has changed from several feet of soil to synthetic insulation overlain by a geomembrane.





### Summary of What is Unchanged

Most importantly, this design does not change the chief precepts of the permitted rapid infiltration system. These design precepts include:

The source, quantity and quality of the treated water is unchanged.The location is unchanged.

The original footprint and dimensions are unchanged.

The maximum discharge rate of 504,000 gallons per day is unchanged.

The maximum loading rate of 10 gallons per square foot per day is unchanged.

The operational plan to use 4 cells at any given time and rest 1 cell is unchanged.

The perimeter ditch preventing surface water run-on and run-off remains unchanged.



